

APRIL 1881

V

MARK

801

INDEX

No inscriptions in stone or marble
in this book.

802

APOLLO

 $\frac{V}{G.H.MCF}$

803

19 DIARY 804
20 Nov. '47 fr. p. 771
Work called off at 10.00 AM.
on account of heavy rains.

20 Nov.

Began removing 2d street
trench 10, A-E east 4-6.
This street, of many stones
may well have served as foundation
for pavement of the Plateia.
See Plan p. 775.

21 Nov.

No excavations, on account of steady
heavy rain all morning. Cleared
somewhat during afternoon.

22. Removing pots and lamps
from Tr 7, E east 0-1 m,
on floor level and on paving
stone. Draughtsman has
made a drawing showing their
position in plan. 3 coins came
from this level in vicinity
F 51, 55, 87 and some lamps
were removed yesterday F 88-91 incl.
Mr. Hill excavating east and north

805

C 334

86

Coin

Licinins
320-324
Heraclaea

late R.

FINDS
cont. from p. 785-806

Wheelbarrow from
dump of north
room of Doric portico.

21 Nov. 47.

87.

Coin

possibly
or Pto

Alexander Jannaeus
163-76 B.C.

Trench 7, E-104-Z .46 east
of west line of trench up against
south face of wall crossing trench 7.
See Film 100 #30³² lying flat on
floor level under debris.

L 1249

88.

Lamp.

later than 1st cent. A.D.

Trench 7, A-E up against
inside of wall S. of E See drawing
for place where found lying on
floor level.

L 1250

89.

Lamp

Near F88 - See drawing for place
where found. Lying on floor level in
vertical position at edge of stone-
paring stone which is not quite in situ
but which probably belonged to floor.

25 23. Trial pit, Street 1 (p. 737)
Looking east before refilling.
Shows rock-hewn trench which
terminates here on north side of
our pit. See also p. 691 and 693
for continuation of this rock hewn
trench to south. L=50 op 12.5 7p 1/40

26 24. Same looking n.w. 7p 1/40

27 25. Place where F85 (p. 787)
found. North room of Doric portico.
Looking south. Meter stick points
to object.

L=50 op 12.5 7p 1/40

21 Nov. 2.40 P.M.

L=50 op 12.5 7p 1/40

29 26. Outside n.e. corner of east bldg.
looking west before removing surface
soil and debris.

L=50 f 12.5 7p 1/40

21 Nov. 3.45 P.M.

27.

FILM 100

30 28. East Bldg. east of east wall, in what is now called the alley, looking north showing fallen wall and other debris [Trench 9, A-Y, north 0-6 meters.

L = 75 op 12.5 7p 1/60
22 Nov. 47, 8.45 AM.

31 29. Same L = 80 op 12.5 7p 1/40 but looking south.

32 30. Place where coin F 87 found Trench 7, E-2 just south of wall. Looking north. Meter stick points to coin.

L = 100 op 12.5 7p 1/60.
22 Nov. 47. 9.45 AM.

33 30. Trench 10, A-E east 16-18 before removing surface soil. Looking north. Dump to left is from Tr. 10, A-2, east 10-12. Note also to right but to left of trench a trench dug before war. Only surface soil was removed [See

L 150 op 12.5 7p 1/100

34 31. Trench 10, east 4-6, F-E (north of drain) before removing stratum 2 (F-E)
op 12.5 7p 1/100 L = 100
24 Nov. 9.00 AM. cont p. 816

FINPS

810

L 1251 90. Lamp frag.

Found near 88+89. Floor level

L 1252 91. Lamp frag

Found near 88-90 near on floor level.

P 2217 92 Bowl

See drawing On approx. ground level, next to piece of pavement. The pavement block doesn't appear to be quite in situ. Bowl lies just below the top of it. Pavement in situ exists at s.w. corner of room. In earth between paving block and stone.

93. Bowl frag.

Lying on piece of pavement near F 92. See drawing (p.)

FINDS
94. Shallow bowl.
sh 1580

812

Found near 92-94 in earth
about 2 cm above paving stone.
Part of it may have rested at
one time on it.

P2212

95. Cooking pot, broken

Lying on piece of pavement
near 92-95 mtl, in earth, and
debris.

P2213

96. Cooking pot, broken.

To east of #95 on n.e. corner
of paving stone. I see now that it
is not lying on pavement but against
it's n.e. corner. Bones found
up against it on s.w. side. It is
not ~~upright~~ ^{upright}. Other pieces of
~~pavement~~ ^{pavement} to east & north of pot
but these are not in situ. Some of
shards found ~~under paving stone~~ ^{not paving stone} to
north. Could this piece of pavement
have fallen from above? (Not pavement
but a marble slab I see now)

FINDS

97. Rim and part of body of deep foot. Found just south of F96 and just off east edge of paving block.
coarse red ware.
-discarded

L1265
98. Lamp fragments. fragments of #106

On paving stone (see drawing P)

99. Broken cooking pot

P2211

To west east of stone paving block. Near #97. In earth. Coming out in many pieces. Found lying approx on floor level or rather at level of foundation for floor. Almost all of paving had been removed before walls fell.

100 Glass frags. On paving stone Tr. T, A-185-E east 80.
top broken to cat.

DIARY

814

of East Building. Continuing to dig Trench 10, A-2 east 10-12, first stratum. Trench 10, E-2, east 4-6 to bedrock and fill in rock hewn trench in sunk in bedrock. Also A-1, 2nd stratum, east 4-6.


Nov. 24

Began removing Trench 10, A-E, east 16-18. Surface soil. See Film 100 #30. Digging north of north wall of east building removing debris. Proper entrance to East Building appears now to have been from this side. Removing all tiles found on surface west of Tr. 10 (opposite 2 last stadia) up on high ground s.e. of temple A. Boy stacking them up there. Began removing Surface Soil Trench 10, A-d, west 10-12.

Nov. 265

Trench 10, A-B, east 22-26, 1st stratum down to foundation of pavement and top of drain. Trench 10, A-E, east 16-18, first stratum down to top of drain and foundation for pavement.
cont. p. 1826

815



Section
Trench 10
East 4-6
East 5-12
See plan P. 773

FILM 100

816

from P. 809

- 35 32. Trench 10, A-Δ west 10-12
before what remains of surface
soil was removed. Surface
soil over wall running north
south was removed here before
war. Line of narrow trench
shows in photo. Looking north.

L=150 op 12.5 ap 1/100
24 Nov. 9.15 AM.

- 36 33. Street, east side, showing
north room of Doric portico
after digging to bed rock on
south part and to floor of
large rough paving stones on
north side. Looking south
from photo tower.

L=150 op 12.5 ap 1/100
24 Nov. 9.45 AM.

- 37 34. Same looking north. Only
south end of room showing.
38 35. Two south rooms of Doric
portico as seen from room with
large threshold immediately to north.
Looking south from photo tower
after digging to bed rock except
where traces of floor appear in
se. corner of far room. and in

817

FILM 100

n.e. corner of rear room

L = 100-150 op 12.5 ap 1/100

24 Nov. 10.00 AM.

did not come out, end of film.

FILM 101

Panatomic X Weston daylight 24

- 17 1. East of East Building. Looking west showing debris in earth probably fallen from roof. Note fence on road left.

L = 200 op 9, ap 1/60

24 Nov. 12.125 PM.

- 17 2. Same looking s.w.
16 3. " " s.w. more sun.

4. —
15 5. Trench 10, A-2, east 10-12 after removing surface soil. Looking north.

L = 150 op 9, ap 1/50

24 Nov. 1.45 PM.

- 14 6. Same looking south
No's 546 show irregular foundation for pavement - probably sub foundation.

- 13 7. Trench 10, A-2, east 16-18 after removing about 2 cms of surface soil over sub foundation for pavement. Looking north. Same exposure.

FILM 101

818

7.8. Same. Looking south.

- 12 24 Nov. 1.45 PM. Same exposure.

- 11 8. Street 1, 2 most southern rooms of Doric portico. Looking north. See also Film 100 #35.
(L = 200 op 9 ap 1/60.)
After digging down to bedrock except in s.e. corner of rear room where a piece of floor has survived and in n.e. corner of far room where a similar patch of floor is extant.
24 Nov. 2.00 PM.

- 10 9. Doric portico, Street 1, room with large threshold. Looking east after digging down to bed rock.
Same time & exposure as #8.

- 9 10. Place where F 119 found. Looking north. Tr. 7, E-2. floor.

L 13, op. 3.5, ap 1/30

24 Nov 3.45 PM.

819

FILM 101

118. Trench 10, A-Z, east 10-12.

Looking south after removing surface soil and earth between stones forming what was once most probably the sub foundation for a paved *plateia*.

25 Nov. 8.30 AM.

L=50 op 6.3 2p 1/40

129. Same. Looking north.

1340. Trench 10, A-d, west 10-12

Looking north - also after removing surface soil. Also west 12-16 before removing surface soil.

Nov. 25 8.45 AM L=150 op 9.2p 1/40

14 H. Trench 10, T-E, east 4-6.

Looking south from wall near 2 after digging between stones forming foundation for pavement. Foundation very irregular here. Note hole to left (A-E) where no stones were found.

L=50, op 6.3, 2p 1/40

25 Nov. 9.15 AM.

15. Trench 10, Same as #11 but looking north.

SH 1575

FINDS

820

101. Frag. of fowl. Tr 7, E, east 0-1. See Draughtsman's drawing. On level of foundation of paved floor.

P 2214

102. Frag. pot.

A little northeast of above. Same level.

P 2216

103. Lid of pot w. knob.

Found w.e. of #102 About same level.

SH 1577

104. Frag of large size pot w. long conical neck - & shreds of cooking ware. - P 2215
Tr. 7, E, east about 80cm just off n.e. corner of paving stone.

105. Sherd including part of flat base. Creamy clay fired same. Found s.e. of 104. - this is castled

L 1265

106. Frags. of lamp. joins pc of #98 Found with 105.

P 2220

107. Frags of plate? a Lid
[See drawing] Tr 7, A-E east about 850 floor.

821

FINDS

L1276 108 Lamp, fragmentary.

Up against south edge of paving stone [See drawing] in verticle position.

Tr 7, A-155-E, east about .80 m

L1277 109. Lamp frag.

Tr 7, A-175-E, east 0.260 m floor.

110. Rim of plate or shallow bowl. Britly orange ware. Discarded.

Near 109 floor. See draughtsman's drawing.

L1278 111. Lamp frag.

Tr 7, A-165-E, east 0.150 m floor.

Sh 1582 112. Piece of large plate.

Tr 7, E-60-2', on east line of trench-floor.

FINDS

822

113. Bronze ^{strip}

M 731

Trench 7 E-2, near south face of wall crossing trench. On floor.

Sh 1579

114. Plate

Tr 7, A-155-E, east 1.30 m. up against north face of wall crossing trench 8 of E floor.

115. Lamp frags (about 1/2 lamp)

L1262

found w. #80

L1280

L1281

L1279

found w. #114, floor

L1282

116. Lamp frag.

Near #115 but up against north face of wall crossing trench 7 south of E. floor. Lamp in verticle position. Tr. 7, A-153-E, east 1.50 m.

L1283-L1284-L1285

117. Lamp frag.

Tr 7, A-153-E, up against south north face of wall south of E east 1.50 floor.

823

FINDS

118. ~~Bronze~~ Iron Nail(?) fr.

M 732

Tr. 7, A-155-E, east 1-48.
floor.

P2210

119. Large shallow bowl, complete
but broken.

Found upside down with part of
it under rough stone - probably
fallen. Lying on floor - that is
what became the floor after the
pavement was removed.
Trench 7, E-35-Z, about E-123-E.
See draughtsman's drawing.

L1286 a-b-c

120 Frogs Brouwer Typee XXII lamp

Trench 10, A-E, east 10-12, strat.
4, near bottom of rock-hewn trench
28 Nov. 47.

L1391

121. Frag rim of lamp Bronze XXII

Same place as 120 but in strat. 3.
Removed from sherd bag.

122. Two figurines - heads

Same place as F121.
cont p.

FILM 101

824

from page 819.

16 13. Trench 10, A-T A-P, east 22-24

3 Looking south before removing surface.
Soil. Note Altar 2 in background.

24 Nov. 9.30 AM.

L=150 op 9 7p/40

1744. Trench 10, A-Z, looking north after

2 removing surface soil showing foundation
of pavement and drain.

L=200 op 9 7p/60 Nov 24, 10.45 AM

1845. Same looking south.

1946. Same looking north - B-T only.
44

2047. Street 1 portico, 2 most northerly
43 rooms. Looking west after digging
to bed rock. From photo tower.

L=150 op 9 7p/40 25 Nov. 11.00 AM

21 4148. Same of room with large threshold
42

22 4149. Same of room to south

23 40 20. Same of most southerly room of
Street 1 portico.

825

FILM 101

- 39 24. Trench 10, A-E, east 16-18
25. after removing surface soil
down to foundation for pavement.
Looking north.

L = 150 op 9 7p 1/40 25 Nov 2:00 PM

- 38 25. Same looking south. Note
drain near E and crossing trench
at T and running along east side
of trench fairly visible.

- 37 26. Eastern extension of drain
leading from *Itateia* between
Altar 2 and S. Bldg. just after
it issues from part covered by
large stone slabs.
L = 150 2p 1/40 op 9. 25 Nov. 4:10 PM.

- 36 27. Trench 10 A-B, east 24-26
before removing surface soil. 22-24
to left already dug down to
foundation of pavement and
top of drain. Looking north.
L = 150, 7p 1/40 op 9. 25 Nov 3:20 PM

- 35 28. Trench 10, A-T, east 18-22
before removing surface soil. Looking
north.
L = 150, op 12-5 9, 7p 1/40
28 Nov. 47 10:00 AM.

cont. p. 830

DIARY from page 814

826

Trench 10, T-Z, east 10-12, after
removing 2d stratum. Trench 10, T-E
east 4-6, removed 2d strat (all but
sample of subfoundation for pavement
between A & E) and strat. 3, E-Z
in rock hewn ditch. Trench 10, A-AB
west 10-12 first stratum (surface
soil) and A-Y, surface soil,
and A-Y, west 12-14, surface soil.

26 & 27 Nov. work called
off on account of rain. Rained
both days up to 10:00 AM only, but
weather looked very threatening

28 Nov.


Fine clear weather. Removing
surface soil. Trench 10, A-B,
east 22-26. Trench 10, A-Y, west
16-18 surface soil down to
Mr. Hill continues digging north,
and east of East Building. Trench
10, A-E, strat 4- (in rock hewn
trench) east-10-12. Tracing
drain system east into Trench 9
system. Dig Trench 9, S-E, south
8-10. Also cleared out part of
drain leading from *Itateia*
between South Bldg and Street 1

827

Trench 10, 4-6 west.

N.

E.



B.

A.

stratum 1, surface soil - loose - dark brown - some stones

2, same with many more stones

3, 4, 5 lighter colored soil with some stones. Does not look like natural accumulation in drain. However the usual things coming out, bones, glass, coins + lamps so it may well be.

FINDS

828

124. Figurine, head of horse.

Trench 10, A-E, east 10-12, strat 2.
See also F123

L1288-L1289
123. Lamp rims

Trench 10, A-E, east 10-12, strat. 2
See also F124, same place.

L1287
125. Lamp rim Roman, probably first century A.D.

Trench 10, F-A, A-F, east 10-12, strat. 2.

126. Coin

Philip I



C 336

Philip I, 244-249

Trench 10, F-125-A, east 17.95m.
in drain leading from Street 1 about 10 cm below top of it lying on clean soil - probably natural accumulation of drain.
See Film 101, #29 for place where found. 28 Nov. 47. Found head's up.


829
scale 1:100

Alley (East of E. Bldg.)
Plan



Trench 9, A-G-Y, south line of
facing north.

See F 133 (coin)
const I
in 3
on Erosion
dune)



x dug June 12,
1948

FILM 101
from p. 825

830

34 29. Trench 10, B-E, east 16-18
after removing surface soil (also
in part 16-19) showing place
where coin F 126 found.

L=150 op 9 7p/40 28 Nov 10 AM.

33 30. North of East Building after
removing debris just north of north
wall. Looking west.

L=150 op 9 7p/60 28 Nov. 47 10.50 AM.

32 31. Fallen wall immediately east of
east wall of East Building.
Looking west.


L=400, op 9. 7p/100 11.50 AM.

31 32. Trench 9 d-e south 8-10
and d-e-78, south 8-10.
Looking south before removing
surface soil to trace drainage
system from Street 1 and
Platelia in front of South Bldg.


L=150 op 9 7p/60 28 Nov 10.50
AM.

831

Trench 10

Trench 10,
Drain leading from Street 1drain at
T-85-Δ

17.00 18.00 m east ST 3



F143 = Conchavus

146 - SE

147 - very thick con

148 - Antennas Piles

DIARY

832

from p. 826
at Trench 9, d-e, south 10-11.

29 Nov.


Trench 10 B-1 east 18-22, surface soil. Many coins turning up in upper part of drain here. Draughtsman (Christofis) drawing longitudinal section of Trench 10, A-2, east 4-6. Digging drain Trench 10, at T, and drain at Trench 10, west 4-6, at T. Finished removing surface soil Trench 10, A-4, west 10-16.

1 December

Mr. Hill continues digging north of north porch of East Building, extending area further north. See Film 102 # 6 and 7. I dig Trench 9 d-e, south 8-10, down to 1.00 m. See Film 102 # 9. Extended trench further west - to 17, also south 8-10. See Film 102 # 10. Continuing digging drain Trench 10, at T, west 4-6.

cont. p. 860

833 Trench 10



FILM 101
from p. 830

834

- 30 33. Place where coins F1274 F128 found. Trench 10, drain at T and at about 19.50 m east. Both near top of drain. See also Film 101th for other coins nearby. Looking east.

L=100, op 9 ap 1/40 29 Nov 9:30 AM.

- 29 34. Place where coins F1294130 Trench 10, B-T, east roughly 19.50-20.00 m east. Near top of drain. Looking east. Nearest coin is F129. Meter stick points to both coins.

Same L + exp. 29 Nov. 10:15 AM.

- 28 35. North of north porch of East Building. Looking n.e. before Mr. Hill Sweets dig of this point.

29 Nov. 11:00 A.M.


FILM 102
Panatomic Weston Daylight = 24

- 24 1. Trench 9, S-E south 8-10 looking S.W. after digging into debris - showing large stones
op 30, 9, ap 1/30


- 25 2. Same op 6.3 ap 1/30

- 26 3. Same looking S.W. 29 Nov
cont p 840 2:15 PM.

835
Tr 9, d-e-3
South 10-12



Section a-a'



stones at bottom of 5.

FINDS

from p. 828

836

127. Coin

C 337

Gordian III, 238-244

Trench 10, Drain, B-148-1, east 19.50m
at 6 cm. below top of drain (0.650 m.
below mark 8). In reddish brown soil forming
probably natural accumulation of drain
is period of neglect.

29 Nov. 47. See Film 101 # 33. It is
the coin to left in photo.

128. Coin

C 338

Gordianus Pius Feb/Aug

Gordian III

Rome, 238-243

Trench 10, Drain, 15-124-1, east 19.44
at 3 1/2 cm below top of drain up against
south side of it. See Film 101
33. Coin is one to right in photo
Meter stick points to coin. See also
F 127. The point on top of drain from
which depth is measured is 0.650 m
below mark 8, Street 1.

129. Coin



C 339

PuPIENUS

238

PuPIENUS, 238 AD

Trench 10, found near F 127 & F 128
Trench 10, 130-1, east 19.52 m
Drain at 0.085 m below top of it
See Film 101 # 34 for place where
found. Nearest coin is F 129.
See also F 130.



FINDS

838

130 Coin

C340

Constantine I, Thessalonica, 320-324

Trench 10, Drain, B-116-F, east
19.82 m at depth of 0.955 m below
top of drain. See Film 101 #29
for place where found. Meter stick
points to both F 129 & F 130.
F 130 is furthest away.
29 Nov.

L 1245

131. Lamp

Under bench, north porch of East
Bodding. See Film 102 #4. #27
5 cm above paved floor in what does
not appear to be fallen stuff but in
a natural accumulation during period of
neglect.

132. Coin

C341

Maximianus, 235-37.

Trench 10, F. 8 cm from south
wall of Drain - in drain at
depth of 19 cm below top of
drain in drain accumulation of
fairly clean soil. (p 827-3)
east west 4.41 m #28
See Film 102 #5 for place
where found. 29 Nov.


839

N
↑


Scale 1:50

Street 1

Plan



Section a-a




1. Surface soil + debris

2, 3, 4 all natural deposit in drain during period of neglect.

No finds in 4.

Scale 1:20 Section b-b



paving block

FILM 102

840

cont. from p. 834

- 27 4. Place where lamp F found under stone bench in north porch of East Building. Looking S.W.

op 6.3 $\frac{1}{30}$ Nov 29, 2:30 PM.

- 28 5. Place where coin F152 found in drain, 19 cm below top of it. Trench 10, T, & west 4.41.

29 Nov. 2:55 PM op 6.3 $\frac{1}{30}$ looking S.E.

- 29 6. Area north of north porch of East Building. Looking in e. before removing debris.

L=100 op 6.3 $\frac{1}{30}$ overexposed

- 30 7. Same looking S.W.

- 31 8. Place where coin F 133 found. Looking in e. Floor of alley


L=50 op 6.3 $\frac{1}{40}$

- 32 9. Trench 9, d-8, south 8-10. Looking S.W. after digging to depth of 1 meter from surface soil in debris - L=50.

1 Dec. 47.

cont p. 844

841



FINDS

842

133. Coin.

Coast I
"Imp Coins"

C 342

Constantine I, 314-317

Alley, (east of E. Bldg.) 2.00 m from large doorway - south from it - (from opening) and 0.45 m west of east of wall. See Film 102 #8^{#31} for place where found. Lying on floor under accumulation of fairly clean brown soil. P. 829-3 (Y)

134. Terr. lamp handle - discarded as too fragmentary


Trench 8, E, south 9, debris, 80 cm. below surface.
1 Dec. 1947.

GL 139

134. Glass fragments, vase handles.

Alley, East Bldg. up against east wall, 65 to 85 cm south of opening of large doorway in East wall. Lying on strat. 3, (p. 829-3)

843

N
↑Scale 1:50
Street 1

FILM 10%

844

cont from p. 840

33 10. Trench 9, 3-11, south 8-10.
before removing surface soil.
Large upper blocks in wall placed
there by me - not in situ -
lower course in situ.
Looking S.W. 2-30 up. 6.37 p/40
1 Dec. 1.50 PM.

34 11. Trench 10 Drain B-135-F
east 19.56 in drain just below top
about 5cm. and up against n.e. side.
Place where coin F 135 found. Meter
stick points to place. Lying flat.
1 Dec, 3.40 PM.

35 12. Place where coin F 136 found
Trench 10, B-60-F east 20.55 m.
and at 11/2 cm below top of n.e. side
of drain. Looking east
1 Dec 3.00 PM

37 13. Open place north of north
porch of East 1310g. Looking
S.W. to W. after removing
surface soil. Not much debris
here. Second strat. begins
about with level of stylobate

845


Section Street 1, K-50-A west 0-6
see plan p. 843

4

6

N

SHERDS & FINKS

H-B, west 2-4 Street, 10
Those identifiable Hellen-
istic & Roman
Coins F 170-173 inclStrata removed before work - Surface soil
1. Same removed Apr. 1948
2. Debris, small stones & some broken tiles

FINDS

844

from p. 842

CARVS

135 Coin

C343

Carus, 282-285
AntiochIn drain Trench 10, B-135-1
east 19.50 just below top of n.e.
side - about 5 cm - and up against
n.e. side of drain. See Film 102
11 (page 844). See other coins
from this section of drain, F 126-130
incl.

Removed 1 Dec 47

136 Coin

C344

Gordianus Pius Fel Aug

Gordian II, 238-244

Drain, Trench 10, B-60-1,
east 20.55 at 11 1/2 cm below
top of n.e. side of drain. See
Film 102 # 12 for place
where found. Lying flat.

1 Dec 47

137 Fish hook in bronze.

M733

East of north end of East Bldg.
alley - just east of it in
debris.

Removed 2 Dec 47.

continued p. 850

13. continued from p. 844

of north porch. Surface soil
is dark with some debris,
and some large cut blocks.

L=200 overexposed

37 14. Same - properly exposed
L=200 of 9 ap 1/100

38 15. Same looking east.

39 16. Place where Fiat found.
North room of portico fronting
Street 1. Meter stick points
to lamp in situ. Looking
south. Lamp in rock depression.

L=100 of 9 ap 1/100,00 probably
underexposed for shade.
Removed = Dec. 47.

40 17. Trench 9 E-L north 24-28
Looking west often digging to
rock. Note depression in rock
now full of water 8 by 8 cm square
25 cm deep - sides slope inward
as they go down.

L=300 of 9 ap 1/100
= Rec.

cont. p. 854

FINDS

850

St 852

cont. from p. 846

138. Man's Shm in marble.

Preserved h., 0.105 m.

Trench 9, B-140 y, South 4.60 m
in debris at about 75 cm from
surface. Near south entrance
to East Side alley. 2 Dec. 47.

L 1291

139. Ter lamp frag. Base of
lamp with part of nozzle.

Trench 10, Drain at T, west 4-6
here west 4.80 m, at bottom of
strat. 5 (p. 827-5). 43 cm.
below top of drain (below
Mark 8, Street 1). Found lying
flat - right side up.
Removed 2 Dec. 47.

GL 140

140 Frags of glass handles.

About 40 cm west of F139 in drain
p. 827-5, same level.

cont. p-852

FINDS

852

141. Bronze lamp.

M 730

North room of portico fronting Street 1. In crevice in rock near center of room. See Film 102 #16. Removed > Dec. 47.

142. Coin

C 345

Clagafalms 218-222

illegible so far

Drain leading from Street 1. Trench 10 F-73-Δ, 18.73 east 0.14 m below top of drain on east side. (0.600 m below top of drain vis mark 8, Street 1.) See Film 102 #22, for place where found. Top of drain from which depth is measured marked with red pencil. In natural accumulation of drain. 74 cm below mark 8, Street 1.

143. Coin

C 346

Gadian III, 238-244

IMP GORDIANVS PIVS FEL AOB

Found with F 142, about 2 1/2 cm n.e. of it at 13 cm below top of drain (73 cm below mark 8, Street 1.)

See Film 102 #22. #1.

2 Dec. 1947.

See also F-128

41 18. Same looking east.

42 19. Rock hewn trench after refilling and before continuing to fill in this area, north end of south section of Street. Tr 9 at about 0, north about 19.

2 Dec. Same land exposure
11:00 A.M. Looking South

43 20. Same looking north

44 21. Rock hewn trench Street 1 opposite north end of north room of portico but on west side of Street. Looking north.

2 Dec. Same time & exposure.

1 22. Place where coins F 142 & 143 found. Trench 10, drain leading from Street 1 to drain crossing it at T and continuing on toward portico of S. Bldg. 142 is nearest coin

L = 150 op. 9 4p 1/60

2 Dec 47 1:50 P.M.

Cont p 856

FILM 102

JS6

- 2 23. Place where F 144 found.
Drain leading from Street 1
looking north. Meter stick
points to coin.

2 Dec 2.45 PM.

L = 150 op 9 2p 1/40

- 3 24. Trench 9, 8-8, south 8-10
looking west after stratum
of fallen stuff, the large stones
being left as found.

L = 100 op 6.3 ap 1/40

3 Dec 8.15 A.M.

- 4 25. Same, looking south -
7-8, south 8-10 looking
down. Meter stick points
to terracotta

- 5 26. Place where coins F 146 & 147
found. Trench 10, Drain, 7-80-A
east 18.00 in. At 23.2 cm below
top of Drain (at 73.2 cm below
mark 8, Street 1). The top of
the Drain from which depth of
finds are measured in this area
shows behind meter stick - Coin
to left is F 146.

3 Dec. 8.30 AM L = 25 op 4.5
ap 1/40

Exp may have been at 1/200
Cont. p. 864

144 Coin
C347 illegible

Drain leading from Street 1
to drain at Trench 10.
Trench 10 T-140-A east 18.05 m
at 16.50 m below top of drain
(76.50 m below mark 8, Street 1).
in natural accumulation of drain.
See also F142 and F143.
Also F126 Film 102, #2.

145. 2 terracotta figurines
man's right shoulder and arm
and a head (not a join) moulded
by hand

Trench 9 5-17, South 10.00 m.
in lower part of debris among
large flatter stone blocks.
See Film 102 #25 for place
where found
3 Rec.

146. Coin
C348

(46)

See p831-3

Elagabalus 218-222

Trench 10, drain
T-80-A east 18.00 m
23 m below top of
drain (73 m below
mark 8, Street 1).
3 Dec.
See Film 102 #26
#5

DIARY from p. 832 860

December 2
Filling in trench 9 E-I north
24-28 (See Film 102 #17; and
rock hewn trench north ~~and~~
south section Street 1, trench 9,
about 0 north about 19. feet
p. 737. Also filled in up to a
few centimeters below pavement
p. 691 and p. 693 areas.
Continuing to dig drain leading from
Street 1, Trench 10, p. 831-2.
Finished digging p. 827 drain
stratum 5. Removing stratum
below stylobate north of north
porch of 8 East Building. This
area, I am calling the East
Building court. Continued
digging trench 9 5-17, east 8-10,
debris. Removed p. 829 2-3.

December 3
Filling in portico, Street
room with large threshold.
Continued digging trench 9
5-17, south 8-10, debris - down
to possible trodden level where
debris ends. Continued excavating
in East Building court. Began
digging p. 835-2.0 in drain
revealed rock in drain at p. 827-6
also drain at p. 831-3. out 866

Finds in alley

F¹⁵³129 - coin - Coast 1 - floor ^{or Papias 2 - 235 AD}
F149 lamp frag "

FINDS

862

147. Coin very thick

C 349
illegible

Found 16 cm south of F146
at depth of 25.8 cm below
top of drain (at 75.8 cm below
mark 8 Street 1). See Film 102
#26 for place where found.
See also p. 851-3.

148 Coin

C 350

Constantinus
Antoninus Pius Cos III

Trench, 10 drain, A-65-E
east ^{17.66} ~~17.66~~ in lying in vertical
position up against west wall of
drain at (bottom edge) 16 cm
below top of drain (26 cm below
mark 8 Street 1). In natural
accumulation of drain. p851-2
FILM 102 #6

149. Ter. lamp frag. L 1392

East Bldg. Alley, 60 cm from east wall
and 1.57 m from south threshold.
About 12 cm below threshold on
troddeu pava. 829-3 (4).

FILM 102 864
6 27. Place where F148 found (coin)
in drain (Drain leading from
Street 1) See p 831-2. Looking
east west. Coin in vertical
position up against wall of drain.

3 Rec. op 6.3. 2p 1/40

7 28. Trench 10, A-B, east 18-22
before digging surface soil. Looking
north. Drain leading from
Street 1 shows in background
to left.

L=200 op 9 2p 1/100

8 29. East Bldg. court. Looking
n.w. from photo tower after
digging to depth of about 15cm
below east wall and below
stylobate of north porch.
This level appears to have
been a trodden level. Note
the pit in center (probably
a late (modern) intrusion).
The soil showing consists of
red earth. The earth in the
pit is very dark.

L=100, op 8 2p 1/40
4 Rec. 8.45 AM.
cont. p. 868

DIARY

866

from p. 860

Dec 3 cont.

Removed surface soil down to foundation for pavement. Trench 10, A-B, east 18-22. Began A-B, east 18-22. Some surface soil was removed here A-B before war. Digging debris in room S.E. of S.E. corner of alley (E. Bldg.)

4 Dec 1947

Trench 10, T-E, east 18-20, surface soil. Finished clearing to what appears to have been a trodden level in court of East Bldg (n. of north porch). See Fl/m 102 & 289, 30. In center of court there is a pit - probably a modern intrusion which we began excavating today. May have been one of Cisterns. Continuing p. 835-4, 3, and p. 831-4 drains. Digging Tr 9, Y-D ^{soil} east 10-12 surface soil over cistern. Trench 10, A-B, east 18-20 - cleaning to foundation for pavement - terracotta water pipes here. cont. p. 870

FILM 102 868

9 30. Same looking s.e.

10 31. Area north east of
court of E. Bldg, looking
north before excavating.

Same time, f & exposure.

11 32. Trench 10, A-β, east 18-20,
after removing surface soil
looking south. Note terracotta
pipes.

L=75 op 9. 40' / 100 - under 47.
4 Dec. 10.30 A.M.

12 33. Same properly exp 1/30 1/30

13 34. East Bldg Court. Same as
29 but looking S.W.

L=100 op 9. 40' / 30
4 Dec. 2:00 PM

14 35. Same looking n.w.

Same exposure 4 Nov. 2:00 PM.

15 36. Trench 10, A-γ, east 18-22
looking west after removing surface
soil.

L=25 op 4.5 40' / 40 5 Dec. 8:00 AM

37.

cont. p. 874

DIARY

870

4 Dec cont. fr. p. 866
Removed p. 835-3 (drain) stones
at bottom of this Stogton, rest
of 2 and three consist of natural
accumulation of drain.

5 Dec.

Half a day only - called off work
at 11:30 on account of heavy rain.
Dug in E. Bldg court and in drains.

6 Dec. + 8 Dec.



Continued digging and washing
over ancient ground level in East
Building court. Cleaned out
mud intrusion in center of court.
Finished digging drains p. 838, 855,
and p. 877. Digging down to
bottom of drain. Drain (p. 855)
has a floor which continues
under the side walls of drain.
Drain (p. 831) has stone slab
across of which served as a
bridge to carry terracotta
water pipes leading from
upper itatia to vicinity of
Altar 2. Terracotta pipes were
found fallen beneath it in struts.

cont p-888

871

Drain leading from Street 1
at Trench 10, A, east 20.

A+



6-25

FINDS

872

St 853

150. Draped female figure in stone

Archaic. Head & feet missing.

P.H. about 0.25 m.

Found 34 Nov. Street 1, debris,
South section.

151. Bronze nail

M 734

Drain leading from Street 1, p831-5
at 60 cm below top of drain (90 cm
below mark 8, Street 1. against
east wall of drain.

5 Dec.

152. Glass bowl, base only

GL 141

Found just under nail, about 1 cm
below it. (F 151). p831-5

5 Dec.

153. Coin

C 351

temple or reverse

Agababius Tripolis
(Phoen) 218-222

Trench 10, A east 20, at 0.25 m
below top of drain (at 152 below
mark 8 (Street 1)) A-25-13
east 19.85
top of drain at A, east 20 = -0.52 below mark

1. Trench 10 drain leading from Street 1 (p. 831) showing stone found in natural accumulation of drain, a stone slab narrow and long with end penetrating into either wall of drain, flat sides approx. horizontal. Under side lies at 0.360 m below top of drain (0.760 m below mark 8, Street 1).

5 Dec. 47

2. Place where coin F 153 found. In drain leading from Street 1. Looking west. See plan & Section p. 871. Stake in trench (in drain) + S A, 20 east (Trench 10 system).

6 Dec. 10.00 AM

3. East Bldg. Court, room in house to east of it. Looking S.W. from photo tower, after removing surface soil showing fallen wall. Court appears in background & columns of S. Bldg.
L-158-20 p. 9, 7P 1/100 10.30 AM 6 Dec.
Cont p. 876

154. Coin

C 352

Antoninus Pius Iasos,
138-161

Trench 10 drain, see p 871-5
 A-39-13, 19.44 east at level
 of 0.375 m below top of drain
 at A, 20 meters east or at
 level of 0.895 m below mark 8,
 Street 1. Film 103, #6.

L1246

155. Ter. lamp

E. Bldg, court, 2.50 m west
 from n.e. corner, about 10 cm.
 from north wall, right side up,
 nose toward n.e., in washing
 at about ground level under
 debris (the debris was over the
 washing, the washing a depth
 of about 15 cm. Complete fat cracked

6 Dec '47

- 6 4. Place where coin F 154 found in drain (Trench 10 A-39-B, east 19.44. Stake showing in drain is A, east 20. String across drain - or running lengthwise to left is A line of Trench 10 system. Looking west
L = 13 op 4.5 ap 1/40
6 Dec. 2.30 P.M.

- 7 5. Place where coin F 159 found. Court of E. Bldg. About 2 cm from east wall of court among chunks of plaster and stones. So very near ancient ground level.

Looking me. L = 150, op 9, ap 1/100
8 Dec. 2.20 P.M.

- 8 6. Stones removed from trench across Street 1, see p. 731, from strata 1 and 2^a looking north across west end of trench.
L = 25 op. 9, ap. 1/40. Should have been ap 1/20. 8 Dec. 3.05 P.M.

- 9 7. Street 1 drain, opposite north end of portico. See p. 837, after removing strata 1. Looking north. Surface soil removed before work. L = 25, ap 1/40 op 6.
9 Dec. 4.50 P.M.

FINDS

888

GL 142

156 ^{Bead} ~~Spindle wheel~~ in glass paste

Drain, Trench 10, at A, east 20.
(very near stake) depth from top
of drain = 60 cm. = 1.12 m below
mark 8, Street 1. Removed
8 December.

157. Coin

Clapasalvo, 218-222

C 353

Drain, Tr 10, at 0.32 m n.w. of
stake at A, east 20. and at
70 cm below top of drain = 1.22 m
below mark 8, Street 1. See
871-8. No photo of place where
found as the drain is too dark
+ deep.

M 735

158. Bronze object

cont. p. 882

FINDS

882


159. Coin
C354

for edge
illegible.

Court of E. Bldg. 2 cm from east wall of court. See Film 103 #17 No. 5 for place where found. Lying among small stones and chunks of lime mortar, with coarse sand, some of which lie lower than coin which shows this fell before washing came in in which coin is buried. Found 9 cm above ancient ground level in mole washing. 1.50 m north of line of stylobate.

8 Dec 47

160. Coin
C355



Hellenistic
bevelled edge
Ptolemaios
75-74 BC,
Cyprus

Trench 10, B-148-1, east 11.29 m, at 10 cm below top of south wall of Strain and up against its outer face. See Film 103 #30.32 in Stratum 2 below upper level of foundation for pavement.

M. 737
161. Bronze finger.

For place where found see Film 104 #4. Narrow

FILM 103

884

- 10 8. Trench 10, A-2, looking north after surface soil removed and before removing foundation for pavement north of drain. Only 1.50 m on east side to be removed here for longitudinal section.

L=50, op 9, 2p 1/40 9 Dec 10.05 AM.

- 11 9. Trench 10, A-E, east 10-12, looking south after removing surface soil south of rock beam trench showing in foreground and before removing moor trench into foundation of pavement (stratum 2).

L=25 op. 6.3, 2p 1/40. 9 Dec 10.10 AM.

- 12 10. Same looking north.

- 13 11. Tr 10, A-E, east 16-18 after removing surface soil and before removing foundation of Street and surface soil, 15.50 to 16.00 east. Looking north.

L=200 op 9 2p 1/200

- 14 12. Trench 9 ^{e-7} ~~A-5~~ north 6-9 before removing surface soil. Looking west. L=100, op 6.3 2p 1/60 9 Dec. 2.45 PM. A small depth of surface soil was removed here before war.

Cont. p. 886

13. Trench 9 & 8, north 9-14
area somewhat east of East Bldg.
court. Looking west before
removing surface soil. [Some of this
was removed before the war].

L=100, op 9, Sp. 1/60
9 Dec. 2.45 P.M.

14. East Building court, fallen tiles
under north wall. Looking in.

L=100 op 9, Speed 1/100
9 Dec. 3.35 P.M.

15. East Building court. Looking in.
east end of court along e. wall showing
small stones in washing over ancient ground
level.
L=50 op 9, Sp 1/40 10 Dec. 8.10 A.M.

16. Trench 10, A- to drain at T,
east 4-6 before refilling.
Looking north.

L=25, op

17. Same of T-E, but looking
south - close up.

L=25, op 6.3. Sp 1/40 10 Dec.
cont. p 890

9 December

Dug trial pit Street 1. See page 837, and dug out drain in it down to rock. Trench 10, A-2, digging 2nd strat. of foundation of pavement down to rock along east half of trench. Widened Trench 10, east 16-18 50 cm to west A-E to beginning of west wall of Street 1, removing surface soil. Trench 10, in section 10-12 east A-E digging down to rock in east half of trench removing foundation of street pavement. Almost completed removing and washing in E. Bldg. court. See Film 103 # 14 showing fallen tiles just under north wall of court. Began digging among debris Trench 9, 4-5, 6-7 north 6-14. Surface soil removed from this area before war. Dug trial pit by piece of pavement, Street 1, see plan & section p. 839 and found section of drain.

10 December

Refilled Trench 10, A-2, east 9-6 all but drain. See Film 103 # 16-18 incl. Removed small amount of surface soil left (except for small sample) at extreme south end of Street 1. Dug 839-2 drain, Street 1.

continued p. 892

- 20 18. Trench 10, T-E east 4-6
before re-filling looking south.

L=25" op 6.3 2p/40
10 Dec. 8.15 A.M.

- 21 19. Same as 18, looking more east
later in the afternoon
L=100 op 9, 2p/60.

- 22 20. Debris just outside n.e. corner of
court. Looking S.W.

L=25" op. 6.3, 2p/40
10 Dec. 3.10 P.M.

- 23 21. Trench 9, E-W north 9-14
looking n.w. Showing dump of
stones. (ancient dump)

Same time & exposure - probably in overlight.

- 24 22. Trench 9 E-W, east north, 6-9,
showing what appears to be a
footing trench for west and
south walls of room here - in
process of being dug out. Surface
soil already removed. Looking
S.W.

L=25" op 6.3 2p/60
10 Dec 3.30 P.M. cont p. 694

DIARY

892

10 Dec cont. from p. 888.

Continued digging Trench 9, E-7¹⁴, north 9-14 down to dump of rough stones. See Film 103 #21. Also Trench 9 just outside n.e. corner of court down to debris. See Film 103 #20. Extending Trench 10, E-7¹⁴, 14-16 north-surface soil. Finished removing surface soil Trench 9, E-7¹⁴, north 6-9, and began digging out what appears to be large footing trench for west and south walls of room here. See Film 103 #22. pug p. 839-5.

11 December

Trench 9, B-7, north 7-9, east of wall from top of good block to bottom of it. Trench 9, B-7, north 14.50 between walls, finished removing fallen mud probably from roof. Filling Trench 10, A-2, east 4-6. all hot drain and pink-brown trench. Found that terracotta pipe is blocked off by pipe 1 stone just before reaching drain at A, 20 east (fr. 10). Finished digging for the time being Trench 9, E-7, north 9-14.

cont. p. 898

FILM 103

694

- 25 23. Drain leading from Street 1 at point where terracotta pipe once led stopping short of it by a few cms and coming from just beyond wall of early stylobate of South Building. See p 87. Looking South. Drain at Trench 10, A, 20 east. Taken just before removing a few of stones of wall of drain on South side to investigate terracotta pipes.

L=100, op 9, sp 1/100 11 Dec. 10.00 AM.

- 26 24. Trench 10 A-2, east 4-6 looking north from photo tower before remove filling. Dog down to rock on ^{both} east sides of trench except for two samples of pavement foundation at A-E.

L=100, sp 1/100 op 9. 11 Dec 10.15 AM.

- 27 25. Trench 10, A-2, looking north from photo tower before refilling. Dog to bedrock all along east half of trench.

L=100, sp 1/100 op 9 11 Dec 10.15 AM

- 28 26. Mr. Hill measures top of portico column to see whether a capital found at east end of South Building will fit. 11 Dec. 10.20 AM.

FILM 103

696

29 27. Same as #24 looking south.

30 28. " " 25 " " 11 Dec. 10.30 AM

31 29. Foundation of pavement just south of Street 1. South end of west wall of street showing in background - before digging to find out nature of worked block appearing in rubble.

L=100, op 9, ap 100

32 30. Place where F 160 found (coin) Trench 10, B-115-T east 11.29, at 10 cm below top of drain on outer face of drain wall (south side) looking north.

L=6.5, op 3.5, ap 30

33 31. Trench 9, 17-8, north 0-6 before removing surface soil. Looking n.w.

L=200, op 9, ap 100, 12 Dec 9.25 AM

34 32. Tr 9, I-A, north 8-10, before removing 2nd str (1st str removed before war)

35 33. Trench 10, A-2, east 10-12 looking south before refilling. Dug to rock on east side, north of drain at T. Still some digging to clear A-T on east side to clear to rock for section.

L=100 op 9, ap 100 12 Dec. 10.45 AM

DIARY

12 December

Began removing surface soil Trench 9
 17-0, north 0-6 m. See Film 102 #31.
 Removing stones & blocks found at
 north end of south section of Street 1
 Began digging trench 9, I-A, north 8-10,
 west of Street 1 where threshold
 occurs in west wall. See Film 102 #31
 Surface soil removed here before war.
 Beginning 2d stratum. Digging
 Trench 10, F-A, east 16-18 to
 find whether rock hewn trench
 of trenches 4-6, and 10-12,
 extends to this point. Dig out
 drain hook which contains from top
 down normal accumulation of drain -
 rather well sifted earth - no stones -
 some shreds & glass. It drained
 water into main drain leading
 from Street 1 just north of
 pipe line. What appears to have
 been an early ground level is now
 appearing just south of the pipe line,
 at about the level upon which the
 pipes are lying.

13 December

Cleaning up mostly. Removing dumps
 in lower plateia. Tracing rock
 hewn trench opposite portico in
 Street 1. Finished removing

FILM 103 900
36 34 Same looking north from
photo tower.

37 35 Trench 10, T-A east 16-18
after removing foundation of
pavement consisting of rough un-
worked stones. Looking north.
Drain block and terracotta pipe
line shows in background. Digging
here to find rock house trench.

L-100 op 9, 7p 1/100. 12 Dec. 47

FILM 104

1. Trench 9, B-E, north 16.50-18 in.
Looking s.w.

22. Same

33. Tr 9 E-50 - E - (E-100-9)
north 14-18

FILM 104

902

4#4. Place where bronze finger
F 161 found. Narrow chamber
east of court, up against south wall.
at about same level as flooring a
little to the west of it. Looking
southwest.

L=50, op 6.3 7p 1/100 13 Dec 2.50 PM.

5. Place where complete terracotta
lamp F 162 found. East of n.e.
corner of ea court, north of narrow
chamber, up against wall. Meter
sticks points to place. Looking
northwest.

L=50 op 9, 7p 1/100
13 Dec. 47 5.10 PM.

6. Street 1, near extreme south
end showing foundation of
pavement before filling in. Looking
north.

L=100 op 9 7p 1/100 9.30 AM 17 Dec.

7. Same. Looking north showing
another bit a little further south.

L=100+ op 9, 7p 1/100
17 Dec. 1947 9.30 AM.

cont. p. 908

L1247
162. Terracotta lamp, complete
unbroken.

For place where found see Fil/1104,
#5. East of n.e. corner of court,
1.12 m. north of n.e. corner of narrow
chamber east of court, in debris up
against wall and 20 cm below it.
end

163. Coin

C 391

Amphipolis before 27 BC

Street 1, drain P 913-3
70 cm. below top of paving
block and 6 cm. north of
south edge under it

AVGUSTUS BEFORE 27 BC.

20 April 48

~~Demetrios Pol.~~

164 Cylindrical seal

St
PP4

Street 1, very near N west 6 among
debris at level of
terracotta water pipe 9 cm
n.w. of its open end. See

905

FINDS

Film 106 # 30 & 31, for the place where found the water pipe, is in situ. Appears to be in marble.

M761

165 Arrow head

Street 1, K-160-A, west 6 debris, Street 1a, See 845-1a, among small stones. See Film 106 # 33 and # 34 for place where found.

St 885

166. Perforated stone object
 cylindrical shape, flat on top & bottom.

Street 1, I-56-K west 6.00 debris among small stones
 See P 845-1a

167. Corn

C 392

Detritus Poliorrhoeas

Street 1, H-155-G, 3.46 west
 in 2d stratum among figurines
 Dem Pol.

168 Corn

C 393

Street 1, O-105-H, west 7.80.
 Strat 1a on fallen stone (debris)
 Ptol. I 305-285

See Film 107 # 6-

DIARY

906

15 Dec. continued from p. 898
 p. 841, Stratum 3, and beginning 4.

14 Dec (Sunday)

15 " no excavations
 on account of rain.

16. Mr. Hill leaves for Nicosia to fly to Athens early tomorrow on Cyprus Airways - a new line. No excavations.

17 December

Digging P. 841-4. (Στερεος)
 Continued removing dump for trench 10, A-2, east 11-12 and 16-18 in wheel barrows to low ground at S.W. limits of precinct. Continuing to trace rock-brown trench outside portico, Street 1. Removed rock late wall on edge of pavement, Street 1, opposite portico. See Film 104 # 10-15 incl. 12, 2 shreds found in or under wall although dug very carefully. These were under block 5 (see G. Raftoyiannis's working plan). Directly on pavement in loose soil. All blocks being

907

FINDS

169. Coin C 394
illegible

Street 1, A-134-H, west 1/62
 lying over stratum 2 in strat. 1a
 among fallen stuff
 See Film 107 #6.

illegible

170. Street Coin C 395
Alexander

Street 1, H-125-B west 6.00
 lying among debris in strat. 1a.

Alex. IAN

171. Coin C 396
illegible

Street 1, H-86-B west 6.00
 lying among debris in strat. 1a
 on stone

*More Deer with suckling foal
 Curium? 4 1/2 S. Chert. A-B.C.*

172. Coin C 397
Antigonos I

Street 1, H-102-B
 west 7.50 m

lying among debris in
 strat. 1a. I found some
 Antigonos I. p 936

FILM 104

908

88. A little further north in Street
 1, than #7 looking north.
 Showing section of round wall
 appearing in foundation of pave-
 ment. Opposite south end of
 portico

L-25 op. 6.3 ap 1/40 10.00 AM.
 17 Dec.

99. Trench 10. A-1 east 10-12
 after digging to rock on east side
 of trench. T-2 has been refilled
 except for drain and rock. In
 ancient trench. Looking north.

L-13 op 6.3 ap 1/30 11.00 AM
 17 Dec.

1010. Wall on edge of pavement, Street 1,
 running north-south, opposite
 portico. South half of wall.
 Looking west

111. Same of north half.

12 12. Same of entire wall. Looking west.

13 13. Same looking east

14 14. Same looking north

15 15. " " South.

17 17. North porch of E. Bldg. and court north of it. Looking S.W.

18 18. S. Bldg. from Temple A, looking S.W.

19 19. Stairway, partly restored, of Temple A.

20 20. Street 1, south end looking north showing drain.

21 21. S. Bldg., central room, looking north

22 22. Same looking N.W.

23 23. " looking N.W.

cont. page 911

FILM 104

- 24. 24. S. Bldg. 2d room fr. east.
- 25. 25. S. Bldg. looking west from east end.
- 26. 26. Alley, east of E. Bldg. looking north.
- 27. 27. Same looking n.e.
- 28. 28. Same " "
- 29. 29. N. porch E. Bldg.
- 30. 30. Square room e. of court of E. Bldg. Looking w.n.w.
- 31. 31. N. entrance to alley looking s.
- 32. 32. Same
- 33. 33. N. porch E. Bldg. close up looking s.w.
- 34. 34. Area between S. Bldg & Street 1 looking w.
- 35. 35. N. end Street 1 looking n.
- 37. 37. Statue found s. of square room w. of court of E. Bldg.

DIARY

912

removed to upper Tdateia immediately to west. Digging trench 10 ft. to west wall of Street 1 east 12-16 down to foundation of pavement.

End Autumn Season

19 April 1948

Began cleaning certain area of great growth of grass made this year. About 12 men. Joe Last and Christofis drawing stones as they appear in plan on site of Temple A. At south end of Street 1, examined drain under pavement. Found usual accumulation of silt which shows that drain was in use after the construction of the pavement.

20 April 1948

Continued cleaning site of old grass, thistles, etc. Cutting grass between Street 1 and Temple A with power mower. Began digging trench 9, cont. sp. 5914

Weston FILM 105
light meter (colored slides)
on 8 Kodachrome

12. Trench 9, looking east
from a point a little east
of point of E. Bldg. 7-K,
north 10-15
L=200 op 8 7p/50

13. Same looking north

14. Same as 12 after removing
grass. The line separating
the area where grass has been
cut from where it has not
been further to east represents
a trench line before the war
[10-9, c(10-15 north)].



15. Trench 9, 7-0, north 10-15
after removing soil among
fallen stones. Looking north
21 April 48 9:00 AM.

16. Trench 9, c-3, north 6-15
looking north of removing
surface soil
22 April c=250 op 8 7p/40

17. Same looking east 10-15
north
L=200 op 6 + 7p/40

913 Street 1
Drain under pavement at
south end.

N
↑ Scale 1:20
PLAN



F162 coin
August 27 B.C.
no finds
strat 4

Shells - many but scarcely any ribbed ware
probably all later than 155 Cent A.D.

DIARY 914
cont. from p. 912
7-K, north 10-15. See Film
105 12-15. Corn No. 163
in drain (See p. 913).

21 April 1948
Removing surface soil trench,
6-K, north 6-15. Digging
in drain Street 1, under
paving block opposite See
entrance to E. building. See
plan, section P. 839, section
6-6'. 47 cm in from south
edge of pavement. Also dug
out drain below another
paving block (See p. 837).


22 April 1948
Began 2nd stratum (cleaning
large stones in general debris)
Trench 9, 25 E, north 10-15
and 6-K, north 6-10.
See Film 105 # 16417.
Extended pit in Street 1,
as shown on p. 691 to paving blocks
to east to find north extension
of drain. Drain found
leading from rock below to
ancient pit which appears to

915 Street 1, near north end
of South Section. See also
plan & section p 691


N Scale 1:20



Plan



Section c-c'



DIARY 9/6
have destroyed it. Looking
for continuation on other side
of pit (west side).

24 April '48

Began removing 2d stratum
of Street 1, K-A west 0-8 side.
See Film 105 #18 (colored slide).
1st stratum here removed before
war up to 8 west. Continued
removing 1st stratum, trench
in same area, as yesterday.
Continuing cleaning temple A of
growth of grass & cleaning up
sanctuary in general. Joe last
is making catalogue of archi-
tectural pieces from Apollo.
See Film 106 #1-21 incl
Removed second stratum of drain
p 915-2. Usual accumulation of
neglected drain.

26 April 48

Removing 3rd stratum of drain
p 915-3. These drain strata
are not actual strata but
levels only arbitrarily chosen.
Began removing 2d stratum
Street 1, I-K, west 0-2 and
continued p. 922

FILM 105 918
cont from p. 912

18. Street 1, K-1 west 0-8
looking west. 1st stratum
removed here before the war
but not removed beyond 8 west
where tall grass in background
shows.

L=300, op 9 ap 1/40
24 April '48

19. Drain (see p 915) looking
S.W. Showing fill in drain
after 5 cm of it removed. Drain
here is interrupted by rock brown
pit which removed a section
of it.

24 April 48 L=300 op 9 ap 1/40

20421 Alley, looking south showing
fallen wall

L=300 apert. 12 speed 1/200. 24 April
3:30 PM.

FILM 106 920
Kodak PlusX
Weston meter 50 L = 500
aperture for following pictures 11
Speed 1/200

Architectural
No Object No.

- | | | |
|-----|--------|-----|
| 1. | 11 | ✓ |
| 2 | 102 | ✓ |
| 3 | 101 | ✓ |
| 4 | 82 | ✓ |
| 5 | 101 | ✓ |
| 6 | 20 | ✓ |
| 7 | 43 | ✓ |
| 8 | 21 | ✓ |
| 9 | 84 | ✓ |
| 10 | 85 | ✓ |
| 11 | 52 | ✓ |
| 12 | 14 | ✓ |
| 13 | 10 | ✓ |
| 14 | 6 | ✓ |
| 15 | 5 | ✓ |
| 16 | 15 + 4 | ? ✓ |
| 17 | 3 | ✓ |
| 18 | 13 | ✓ |
| 19) | | |
| 20) | 47 | ✓ |
| 21) | | |

Exposure 1:100

✓ 22. Trench 9 0 - 5 north 6-15
after removing stratum 2
Looking east. 24 April
L = 500 aperture 12 ap 1/200

FILM 106

922

23 Same, looking north. Cave under part of debris here found before war. Now partly collapsed. Was full of winter washings.

24. Street 1, I-M west 0-2 & K-A west 0-8, 2^d stratum Looking west.

L=200 apert. 12 sp. 1/100
26 April, 1.45 PM.

25. Alley showing fallen wall. Looking South from photo tower.

L=400 aperture 11, speed 1/200
7.45 AM. 27 April

26. Same looking north.

27. Street 1, I-M, west 0-4 looking west
L=400 apert. 11 Speed 1/200
9.45 AM.

28. Same looking east

29. speed 1/100

30. Place where F. 164 found
Street 1, M west 6 Meter
sticks points to cylinder seal
9cm. W. of open end of pipe.

Trench 9

east
north

18

16

14

12

11

a - Section a-a' see page 225 - - - 0 - - a'

DIARY
west 6-8. See Film 105 # 18
showing this area before removing
2^d stratum. 1st stratum was removed
before the war.

27 April 48

Extended Trench 9 north to 20
west and east to P, removing
surface soil only on top of
mound over cave. Began
clearing to debris Street 1.
H-I, west 0-6 stratum, a
Mr. Hill removing fallen wall
in alley east of E. side.

April 28, rained most
of day. Work called off at breakfast
time.

No excavations April 28.


April 30

About 17 men

Street 1, H-I, 0-8 west.*
Finding many figurines, some
grogs, & some corns in Stratum
12, all at about same level.
Among things which look like
building debris. Began digging

* See F2058, 2059

Trench 9, north 12-16, 0,



FILM 106

Cont. from page 922

926

35 30 (cont.) Looking S.E.
L=150 apert 9, sp. 1/100
27 April 4.45 PM

36 31. Same L=400 sp 1/200

(34) 32. Street 1 H-I west
0-6. Looking west before
removing Stratum 1 & over
debris of Stratum 1 removed
before the war.

32. Showing terr. pipe in situ(?)
33. Ditto

FILM 107

1. Street 1 west
before removing Stratum 1a.
Surface soil removed here
before the war.

Looking west

L=

30 April

2. Same Looking north

3. "

sun

FILM 107

4. Trench 9, E-II, east 12-16
after removing surface soil.
Looking south.
L = 300 aperture 9-1/100
30 April, 9.10 A.M.

5. Street 1, place where
Find, coin, #167 found at
H-153-O, west 3.46 over
stratum 2 among figurines
and stones which appear to be
building debris.

Looking south L=200
30 April 2.53 PM top 12.5
sp. 1/100

6. Street 1, place where
F 168 & 169 (coins) found.
Looking south.

30 April 48.

7-18 Architectural Blocks

7.	Block 34	sp/100	ap 12.5
8.	25	"	"
9.	26	"	16
10.	2	"	"
11.	33	"	"
12.	23	"	"
13.	181	"	"

cont. p. 930

DIARY (from p. 924) 928

here also M-I west 0-8.
stratum 1a. Surface soil
removed in this area before
the war. Also digging
Trench 9, E-II, north 14-16
intrusion after removing
surface soil. See Film 107 #4.
Mo Hill showing fallen wall and
windows in alley east of E. 18/16.
In Street 1 area, H-I, west
0-8 stratum 1a is the
soil among the fallen stones
& general debris.

Saturday, Sunday, & Monday
no excavations. Greek Easter
holidays. May 1-3 incl.

May 4

11 men only as a number of the
Christians picknicking at
Ayios Epiphany.
Street 1, H-I, west 4-6
stratum 1a. & M-I west 4-8

929

see also
P. 845

Street 1, N, west 0-8



Scale 1:100

Street 1 N-P, west 6-8
sharp hook not later than
Helfenstein also O-P, west 8-12,
in some places

M-E, west 8-12 mostly Creek but
some thin blown glass

O-I west 4-6 Street 1a Roman lamp

#0 west 10-12 Hel, those that can be recognized readily
street 10, stamped amphora handle

A-M west 8-12 very few visible
Street 10 mostly Helfenstein

FILM 107
(cont. from p. 927)

930

14. Block 1	1/100	F 16
15. " 22(6)	"	"
16. " "	"	op 12.5
17. " 32	"	"

18. 24

19. Street 1, M-E west 10-12
before removing surface soil.
Looking north.
L=300, op 12.5 speed 1/100
5 May 8.15 AM.

20. Same looking south.
pen disappears
within an hour after writing this

DIARY 5 May 932
Street 1, H-M, west 8-10
strat. 1 (Surface soil)
Z-H, west 4-8, strat. 1.

6 May 1948
Street 1, E-H, west 6-8
Strat. 1 (Surface soil)
H-O, west 10-12, O-K, west
K-I, west 8-12, Strat 1
All this completed today
dig to fallen tiles in E. Kido.
(1 bench 9, 1-A+) north 5-6.
See Film 107, # 31.

7 May
Stones lying on modern ground
level Street 1 H-I, west
8-10, removed to Z-H,
west 8-10, same level.
Today dig Street 1, O-K, west
8-10, strat. 1, west 8-12, west 6-12
Stratum 1 (Surface soil). Cutting
grass this vicinity up to precinct
wall.

Continued p. 944

21. Place where coin F170
found. Looking south.
Meter stick points to coin.

L = 200 sp " 7p 1/100
5 May 1.40 PM.

22. Place where coin F171
found. Looking south

23. Place where coin F172 found.
Looking south.

24. Place where coin F173 found.
Looking south.

5 May 1.45 PM.

25-27 Architectural blocks

25 Block #30 7p 1/100 sp 15

26 " 103 " 16

27. " 83 " May 5
3.40 PM.

FILM 107
28. Street 1, H-E, west
8-12 after removing
surface soil.

Looking south

29. Same looking north

30. Same, looking south
but with better exposure

6 May 2:30 P.M.

31. East Bldg. trench sunk
north of large threshold
leading to west porch.
Trench 9, T-A, north 5-6
approx.

Looking northwest. Styrium
lying just below top of threshold.
Little more than surface soil
removed here before war.

L=400, aperture 12, speed 1/100
7 May 48 9:35 A.M.

32. Same aperture 16,

33. Street 1, M-E, west 0-10
after removing strat. 1a
and before removing any debris
looking east from photo tower
7 May 11:00 A.M. L=300 ap 12.5 f/100

FINDS
(cont. from p. 907)

936

173. Coin

C398

Street 1, H-116-0

west 7.75

DEM
probably

lying among debris in Street 1a

See 9180

F199

SAMOS 394-365 BC

CURIUM 395-389 BC

174. Coin

C399

illeg.

Street 1, 0-98-L - core

west 1.89

among debris in Street 1a.

5 May

C400

Same Coin
Fragmentary

Philip I
244/9

Same place as F. 174
about 1 cm. so north of it.

C401 176. Coin

illeg.

Street 1, 0 west 11.10

Strat. 1 2.4 cm. below
modern ground level.

6 May 1948.

illegible

FINDS

938

177 Coin

C402

Street 1, H-90-0 west
11.18. In surface soil at
24 cm. below modern ground
level

6 May 1948. Ptol 1 305/285

st 870

F78. Stone head of man with
Achaean smile.

P.H. 0.035 m.

Street 1, 0-60-I west 9.76
surface soil. About 20 cm below
modern ground level,

6 May 1948.

P 2221

F 179 Inscribed rim of
a pithos.

Trench 9, 0-60-i north
15.12 m. Surface soil.

6 May 48 (removed)

Δ	Ο	Μ	Σ
Σ	Χ	Ο	Υ

FINDS

180. Coin Ptolemy I, Cyprus
 c403 Street 11 - p west about
 11 m. S. Surface & soil.
 Exact position not known.

8 May 1948 Pto 11 267
 69.441

M 752 Arrow-head

Street 1, E-180-2 west 7.70
 on strat. 2 in 1 @

8 May 1948.

M 827

182. Bronze fibula

Street 1, E-110-2, west 11.38.
 in strat 1 about 20 cm below
 modern ground level in loose soil
 near bed rock.

M 511

183. ^{white Paste} Stone head, neck with horns &
 eyes painted black - a'

street 1, G-170-I, west 10.20
 strat. 1 @ in brown soil.

cont. p. 948

FILM 107

940

34. Same looking west from
 street, also from photo tower.

Same light & exposure
 2.10 PM 7 May.

35. Place where trefoil juglet
 removed by Youngs. Stake
 showing in picture is G west 6.
 Looking South. Street 1
 strat 1 @

7 May 1948 3.20 PM.

L = aperture f, sp 1/100

36. Juglets & figurine removed
 by Youngs - in situ. Stake
 showing in photo, Street 1,
 14, west 4, strat 1 @.
 lying on 2.
 Looking South
 Same time & exposure.

cont 942

FILM 108
Kodak Plus X
Weston 50

942

1. Showing figurines etc. removed
by Youngs in situ. Stake in
foreground is Street 1, 2, west 6.
Finds in street 12. Looking
South. 7 May 3.30 PM.
L=150 op. 9 Speed 1/100.

2. Showing finds removed by Youngs
in situ. Stake showing is
Street 1, 2, west 8. In stratum
1 (A). Looking west, repeat
west.
Same time & exposure 1/60 9
underexposed

3. Same w. exposure 1/60 op 6.3
L=25

4. Finds removed by Youngs in situ.
Stake showing in background
is Street 1 D, west 4.
Looking west, repeat west.
L=150, aperture 9 Speed 1/100
7 May 1948 3.40 PM

5. E. Boring Trench 9, F-A to wall
north

cont. p. 943

FILM 108

5. Finds removed by Youngs
in situ. Stake in background
is Street 1, H west 8
Stratum 1 @ Looking west.
7 May 48 3.45 PM.

L = 25 aperture 1/100 op 9.0
underexposed

6. Same stake O west 8
showing figurines in situ further south.

7. Same as 5 properly exposed
op 6 7/10

8. Same as 6 " "

9. Street 1, M-P, west 8-12
after removing surface soil or
Stratum 1, showing top of debris.
L = 200, aperture 12.5 Speed 1/100.
8 May 8.15 AM. Looking north.

10. East Bldg. Trench 9, F-A,
north 6-8. After removing sur-
face soil (before work before
digging down to roof debris.
Looking n.w.

L = 400 op 12.5 rp/100 should
have been op. 16. 6-8 May.

cont. p. 946

DIARY

944

8 May 1948

Continued digging in n.w.
corner of E. Bldg. Trench 9,
F-A, north 4-8, down to
roof debris consisting of many
types, about 2 1/2 feet to
the square meter. Shards
coming out of Stratum 1a west
of Street 1 very mixed. For
instance O-I west 2-4 has
shards ranging from classical
period to 3rd or 4th Century A.D.
including some ribbed ware.
Remnants of floor tiles in debris.
East Building Trench 9, F-A to wall
north 6-8. Stratum below level of
threshold. See Film 107 #8 and
Film 108 #10 #11. I note that
shards from Street 1 H-O west 6-8
Stratum 1a appear to be all Hellenistic
and earlier. I see now that coins
F 170-173 (uncleaned) from this
area. Figurines here too.
Dup Street 1, E-H west 10-12
Strat. 1. I-K west 10-12
Strat. 2. M-P, west 10-12,
2 strat.

Cont page 945

10 May 1948 (Monday)

Am plating the entire area west of Street 4 (both north and south sections, between street, Plateia and Temple A, in Street 1 system. Before war, Street 1 became Trench 9 after [?] but only surface soil was removed west of street and on a restricted scale only. Meters west will indicate always meters west of the west inner line of the Street. Near the central section of the Street, its orientation changes slightly; the orientation of trench lines change accordingly.

Began Street 1, E-Θ, west 10-12, strat. 1a, I-K, west 8-12, strat. 1a* Began P-Y west 10-12, surface soil. Removed Fins 187-205 incl. g.v.

* See F2026-2044

11. May 1948
Street 1, finished E-Θ, west 10-12, strat. 1a, I-K, west 8-12, strat. 1a, K+P-Y, west 8-12, strat. 1. Began O-Π west 6-12 strat. #2. 1 +

11. East Building, Trench 9, T-Δ to wall; north 4-8, showing fallen tiles below level of threshold. Some already removed in narrow trial trench. See also Film 108 #10, #31 (small trial trench)

8 May 1948, 1.55 PM

Looking west

12. Same looking S.W.

13. Place where stone head F183 found. Street 1, Θ-170-I, west 10-20, in Street 1a. Note great quantity of juglets in fore ground. Looking south

L=200 ap 12.5 speed 1/100

8 May 2.10 PM.

14. Same looking S.W.

15. Street 1, P-Y, west 10-12, before removing surface soil. Looking northeast. L=200, aperture 11, Speed 1/100.

10 May 10.30 A.M.

cont. next page

FILM 108

16. Street 1, 0-P west 4-12
after removing stratum 1a
showing gravel debris before
any of this has been removed.
Looking west from photo tower.
L=200 op 11, speed 1/100

10 May, 1:40 PM.

17. Same looking east from
photo tower. L=400 op 16
speed 1/100

18. Same looking south.

At Place where Coins F187-191 (incl)
and gold F 192 found, and
pegs in ground mark place
beginning left to right.

Stake in background is Street 1,
I west 8. Top of stratum 2
(debris) showing.

Looking south.
L=200 op 11, speed 1/100
10 May 2:20 PM.

cont. p. 954

FINDS
[Cont from p. 939]

948

St 861
184. Scarab.

Street 1, E-65-Z, west 10.60 m.
In stratum 1, surface soil, 17 cm.
below surface.

8 May 1948.

St 866
185. Scarab
54-28-14

Street 1, E-98-Z, west 10.98
stratum 1, surface soil,
depth 0.15 m.

8 May 1948.

186.  stone

Street 1, E-50-Z
west 10.60 m.
depth 15 m. in
surface soil.

illegible

FINPS
187. Coin C 404

Street 1, O-160-I, west 8.06m
among debris top of strat. 2.

10 May See Film 108 #19
illog. 6le

188. Coin C 405

Street 1, O-175-I, west 8.18m
on strat 2 among debris

10 May See Film 108 #19
(4th cent. A.D. or later) illeg.

189. Coin C 406

Street 1, O-152-I, west 8.26m
on top of 3rd strat. among debris

10 May See Film 108 #19
7000 early Curium 4th cent.

190. Coin C 407

Street 1, O-I-8.03-K, west 8.39m
top in surface soil

10 May See Film 108 #19 Note
that this coin is lying higher
than others.

Alex. 400

FINPS

950

191. Coin C 408

Street 1, O-175-I, west 8.47m
lying on strat 2 among debris

10 May See Film 108 #19
10 May 48 Curium 4th cent.
more fool

192. Gold ^{earring} in core - P.W. apothecary

Street 1, I, west 8.47m
lying on strat. 2 among debris

10 May See Film 108 #19

193. Coin C 409

Street 1, O-175-I, west 8.62m
lying on second stratum among debris

10 May See Film 108 #19
Curium more fool 4th cent.

194. Coin C 410

Street 1, I, west 8.78m
top of 3rd stratum, among debris

10 May See Film 108 #19
Curium 4th cent. B.C.

FINDS
(195) Coin C411

Street 1, I-48-K, west 9.00 m.
in strat. 1 @ among debris

See Film 108, #19
Curium 4th Cent B.C.

M 821

196. Bronze bracelet
O. diam. 0.056 m.

Street, O-190-I, west 9.33 m.
in strat. 1 @ among debris
See Film 108 #20,
10 May.

197. Scarab (in rare green paste)

Street, O-106-I, west 9.36 m.
among debris also in strat. 1 @
10 May 1947 See Film 108 #20.

St 865

198. Scarab opaque crystal.
54-28013

Street, O-60-I, west 9.35 m.
On strat. 2 among debris.
See Film 108 #20
80 May.

FINDS 952
(199) Coin C412 illegible

Street 1, O-61-I, west 9.07 m.
in strat. 1 @ among debris
SAMOS 394-365 BC

200. Coin C413
CURIUM ^{OV} 395-389
See also F. 174

Street 1, O-62-I, west 9.25 m.
on strat. 2 among debris
Curium 4th Cent B.C.

201. Coin C414

Street 1, O-43-I, west 9.28 m.
on strat. 2 among debris
illegible Curium 4th Cent B.C.

202. Coin to Nail + frag. of nail
- not catted

Street, O-33-I, west 9.14 m.
on strat. 2 among debris

203. M 742 Brasses M 741 arrow head
Street 1, O-32-I, west 9.17 m.
strat. 1 @
among debris

953

FINDS

204. Coin



C 415

Northwest corner of East Bldg.
Trench Δ -15-E north 0.68 m.
lying under fallen tiles among
broken pieces of painted plaster
in earth at level of face of
plaster which is lying flat with
painted side up. Looks as though
plaster had fallen before coin.
This is Mr. Hill's view.

"11/6g." early

Thrown away by man place on
told to by
for jumping over
initiative

205. Broken pieces of painted
wall plaster. Two deep red

stripes. A trace of
green field below horiz-
ontal stripe as shown
in sketch to left.
Yellow traces further
down. Usual lime

plaster with many
small pebbles mostly
gray in color. The yellow paint
below the blue-green too Beattined
to have been a stripe. For
place where found see F 204
and Film 108 #22.

11 May.

cont. p. 956

SW.
↑

red
pale blue-green
yellow & green

← 16m. st

→ N

FILM 108

954

(Cont. from page 947)

20. Showing where Fink 196-
found. Pegs in ground indicate
places where found (beginning
left to right. In square
Street 10 & E, west 9-10.
Looking west.

10 May 3.00 PM.

L=200 op 11 sp 1/100

21. East Building showing north
threshold white being excavated
by Mr. Hill. Looking north.

L=400 op 16 speed 1/100

10 May 3.25

22. Northwest corner of East
Building showing place where coin
F 204 found among fallen pieces of
broken painted plaster with decoration.
White plaster moulding behind.
The painted plaster is of usual type -
lime mixed with small pebbles,
mostly gray. Looking n.w. Coins and
plaster were all under fallen roof
tiles. Stake showing is Tr 9, Δ , north

L=400 op. 18 sp 1/100

11 May 9.20 AM.

next page

FILM 108

23. North end E. Building.
Same time & exposure as
previous photo. Looking north.

24. Fallen stuff southeast of
E. Bldg. and south of alley.
Looking northwest before
this is removed by Mr. Hill.

L=400 op 16, speed 1/100
11 May 8.30 AM.

25. Street I-K west 8-10
showing place where combs
were found. Peps
indicate place 2. Looking east

L=200 op. 11; speed 1/100.
11 May, 3.50 P.M.

26. Same looking north from photo
tower.
Same exposure 12 May 9.25 A.M.

27. Same looking south. Peps indicate
places where combs occur. Removing these
beginning from right to left. E 10 west
toward 8 west & then from I toward K.
F 212 - cont p. 984

FINDS

206. Piece of white plaster ⁹⁵⁶
moulding. 8 cm. north of
F 205 in N.W. corner of
East Building found under
fallen roof tiles. About same
level as F 204 & 205.
See Film 208 # 22.

207. Iron nail (iron?) - not cat.
L. 0.05 m.

North end of E. Bldg. at 0.33 m
west of west threshold block
at 8 cm below its tread. Under
fallen roof tiles.

11 May

M 743
208. Iron(?) nail.

L. 0.05 m.

N.W. corner of E. Building
82 cm south of north wall and
1.06 m east of west wall. Under roof
tiles.

FINDS

M744

209. From 2 Bronze Nails, 1 of which only a head frag.

East Building, under roof debris 1.04 m south of north wall and 0.95 m east of west wall. At about same level as F204-208 which see.

11 May

210 Iron nail - not cat.

Lying between F205 and F206 at same level under roof debris. 45 cm south of north wall and 45 cm (also) from west wall.

SH211

211. Rhodian stamped amphora handle

Street 1, taken from shelves from H-O, west 10-12 & O-M, " 8-12 strat. 1 (5) debris 11 May

cont. p 960

DIARY

[Cont from page 945]


958

12 May 1948
F212-C416 C421 Curium
F213 C417 Curium F219 C422 Ptolemy I
F215 C418 12 May 1948 F220 C423 Ptolemy II
F216 C419 Curium F221 C424 Ptolemy XII
F217 C420 Curium F222 C425 Ptolemy III
Removed coins F212-228. Paphos, c. 350-332 BC
Street 1, O-M, west 6-12, strat. 2, debris, leaving large stones and all worked stones. Men cleaning site in general and removing earth tumbled in in recent years from some of early trenching along m.w. pericinct wall. Mr. Hill digging south of alley and S.E. of East Bldg.

F223 C426 Paphos, c. 350-332
F224 C427 Antigonas I

13 May 1948
Removed finds F207-237 incl. from Square I-K [Street 1] west 10-12; strat. 1 (5) See Film nos #31. H Aug II-P [Street 1] west 6-12; stratum 2 [See section, page 959].

14 May 1948
Finished digging Trench Street 1, E-O, & O-M, west 6-12, strat. 2. Began II-P, strat. 1 (5) which goes to greater depth here than further north. Top of 20 strat were at 0.70 m below surface cont. p. 972



FINDS

960

212 (Coin) C416

Street 1, T-18-K, west 9.50 m.
on Stratum 2 among debris
Removed 12 May. See Film 108 #27.
Curium 4th cent. A.D.

213: (Coin) C417

Street 1, I-9-K, west 9.20 m.
Strat 1 (C) govt obs
See Film 108 #27 Apollo obs fine
Curium 4th cent.
M745

214 Bronze ring, plain
missing from envelope July 6, 48

Street 1, 0-192-I, west 8.58 m.
Strat 1 (C) on 2.
See Film 108 #27.

215 (Coin) C418

Street 0-195-I west 8.52 m.
Strat 1 (C) on Strat. 2.
See Film 107 #27.

216 (Coin) C419
obs. Apollo
vs wave & sucking foil
Curium 4th cent

Street I-15-K, west 8.47 m.
Strat 1a on 2.
See Film 108 #27

FINDS

217. Coin C 420

Street 1, I-18-K, west 8.54
Strat. 1 (a) on 2. Curium 4th cent.
See Film 108 #27.

218. Coin C 421

Street 1, I-47-K, west 8.51
Strat. 1 (a). Curium

12 May
See Film 108 #27

219. Coin C 422

Street 1, I-65-K, west 8.56
Strat. 1 (a).
See Film 108 #27 Ptol I 305-285
12 May.

220. Coin C 423

Street 1, I-98-K, west 8.33
Strat. 1a among fallen stones.

See Film 108 #27 Ptol II, 285-272
12 May 48.

FINDS

962

221. Coin C 424

Street 1, I-137-K, west 8.05 m.
Strat. 1 (a). Higher than other
coins in this area (F212-220)
in loose soil a little above debris.
Film 108 #27. Ptol XIII 80-51 BC.
12 May.

222. Coin Ptol C 425

Street 1, K, west 8.82 m.
Strat. 1 (a). among fallen
stones. See Film 108 #27
12 May. Ptol II 275 B.C.

223. Coin C 426

Street 1, I-20-K, west 7.32 m.
Strat. 1 (a).
12 May. See Film 108 #31.
Peplos 350-352 B.C.

224. Coin C 427

Street 1, I-164-K, west 11.24
Strat. 1a
Antigonos I

963

FINDS

225. Piece of iron-rod

M 776

Street, I-18-K, west 11:32

Strat. 1②

12 May. Found w. Coin F 223

226. Iron frag - knife

M 820

Street, I-52-K, west 11:40,

Strat. 1②

12 May.

St 883

227 Stone head of bearded

man w. Anchora smile

found with F 226.

Street, I-50-K, west 11:45

Strat. 1②. approx. depth 0.40m.

M 755

228. Bronze ^{sheep} ~~foot~~ & arrow head

found together.

Street, I-46-K, west 11:33

Strat. 1②

Removed 12 May

229. Figurine - (y/indian) body -

hand made head.

Street, I-45-K, west 11:12

Strat. 1② among debris

FILM 108

964

Cont. from p. 953

28. Alley, east of E. Building. Looking west from photo tower north of large threshold. Showing fallen wall & window frames.

L=400 op. 16. Sp 1/100

12 May 10.00 AM.

29. Same taken looking a little more to the N.W.

30. Street, II-P west 6-12, after removing strat 1②. Note also 0-II where strat 2 has been removed - all but large worked blocks showing in trench. Looking east.

L=180 - op 11 Speed 1/100 12 May 2:20 PM.

See also Film 108 # 16-18 incl.

31. Street, I-K west 10-12

before removing objects [

at bottom of strat 1②]

Looking west. 2 pegs point to

corners F & J

L=90 op 9 speed 1/60

12 May 1948. 3.40 PM.

over

FILM 108

32 Same, looking north. Note many ripples in back ground
[O-I]

Same time and exposure.

33. South end of alley east of East St. Looking north.
Taken for Mr. Hill

12 May '48 at 3:00 PM.

L=90 op 8 speed 1/100

34. Showing fallen column after it has been set up in situ. See Film 108 #24 for column as found in debris looking N.
14 May 1:30 pm

35. Showing debris south of column in previous photo. Looking S.E.

14 May L=400 op. 16 Speed 1/100

36. Street, P-E, west 6-12. Showing debris (2nd str.) before removing looking east

14 May 9:10 AM L=200 op 11 sp 1/100

37. Same of 0-12 looking west from Street in photo facing

14 May 9:15 AM L=400 op 16 sp 1/100

cont. p. 970

FINDS

966

M 891

230. Bronze stirrer

Street, I, west 10.41 m. strat. 1a.
13 May 1948.

231. Iron, frags. - not cat.

Street, I, west 10.22
Strat. 1a

13 May 1948

232. Iron frags. - not cat.

Street, I-30-K, west 10.08.
Strat. 1a.

M 746

233. Bronze ring.

diam. 0.016 m.

Street, I-56-K, west 10.05 m.
Stratum 1a.

13 May

M 775

234. Iron frags of rod in poor condition

Street, I-48-K west 10.07 m
Strat. 1a. 13 May.

967

FINDS.

235. ^{M 776} Iron frags - knife

Street 1, I-68-K, west 10.44
Strat. 1 @.
13 May.

^{Mi 514}

236. Piece white decorated paste?

Street 1, I-1.06-K west 10.18 m.
Strat. 1 @. 13 May.

^{M 777}

237. Iron frags - rod

found with F 236, just a little
to south,

238. Figurine Man with beard
Lower part of face and part of
neck only.

H., 0.111 m.

Trench 9, A-120-B, south 10.50 m.
debris; depth 0.40 m.

South of alley.

14 May 48 -

FINDS

968

^{L 1293}

239. Terracotta lamp
fragment of rim

+ Bronze type 22, early example this
type with narrow rim traces
of red paint.

Removed from shed bag marked
Street 1, I-K, west 10-12;
Strat. 1 @.

^{St 876}

240. Marble finger.

L., 0.09 m.

Street 1, I-O, west 8-10,
Strat. 2. See p 89 959-2.

^{St 871}

241. Frag. marble statue of
woman. Shoulders only with locks
or tresses fallen over them.
Halter below for fitting probably
into loose missing member.

14 May 48

H. 0.17 m Diam. tenon 0.070 m

Same place as F 240.

14 May 48

over

969

FINDS

I 142

242. Mould inscribed slab; frag.

Gr. Dim., 0.132 m Th., 0.021 m.

Street 1, $\overline{\text{I}}-\text{O}$ west 10-12;
stratum 2; debris.

15 May 1948.

L 1428

243. Terracotta lamp

Former Type $\overline{\text{X}}\text{FII}$
Circa: 1st half 1st Cent. A.D.
Diam., 0.062 mnarrow rim, raised leaf design on
slightly depressed discus. Nolet
do not encroach upon rim. Wide
nozzle.Street 1, T-90-Y, west 10-40 m
in strat. 1 (2)244. Terr. lamp fragments from
Street 1, T-1, west 10-125 pieces Types 25-27. Discarded. Too
fragmentary to catalogue

cont p. 974

FILM 109

970

cont. from page 968

Kodakchrome
colored slides



Weston 8

1. Street 1, N-II west 8-12
after removing $\overline{\text{I}}-\text{II}$ 2d strat.
but before removing 2d strat.
N- $\overline{\text{I}}$. Looking northwest.L=200 op. 63 Speed $\frac{1}{60}$
15 May 1948. 9:10 AM.2. Same looking north including
west 0-12. Debris of many
stones is N- $\overline{\text{I}}$ west 0-12.
Only part of $\overline{\text{I}}-\text{II}$ showing.

Same time & exposure.

3. Street 1, $\overline{\text{II}}-\text{Y}$ west 6-10-12.
Showing top of 2d strat. before
removing looking north.L=200 op 63 Speed $\frac{1}{60}$
17 May 8:45 A.M.4. Street 1, $\overline{\text{M}}-\overline{\text{I}}$ west $\frac{4}{6}$ -12
just after beginning to remove
many stones of strat. 2 See
section P. 971. Looking NW.L=400 op 9. $\frac{1}{60}$ cont. p. 976
17 May 9:00 AM.

→ N Street 1, E-Y, west 11 m. Facing west Scale 1-100 ft
 T road line T E R P T Q N M




— Spot 8
 1. Surface Soil
 10. 10 ft part debris — clay-Hd. red waves = (T-Y)
 2. Debris - many stones & worked blocks

DIARY 972
 [Cont from page 958]

Stones in debris here are very much smaller though a great many of them. Hardly any large stones or worked stones at all [II-P] west 8-12
 Top of 2d strat. here nearly flush with bottom of orthostate course in wall running east-west. No tiles

17 May 1948
 Removing Street 1, M-Z, west 4-12
 Stratum 2. Great amount of fallen stones. Earth found among them does not appear to have been either from bricks or mud floor. No straw. Reddish. Some All where darkened by vegetation. All worked stones being left is found until sparrow is left - as usual. Tiles from 10. piled up and labelled. near marble floor. n.w. corner. Tiles west 8-12: none found. Tiles west 0-2 piled up on Spot 1 & labelled
 cont. p. 975

973



2. Ribbed ware, red ware, variegated

FINDS

974

M 753

245. Bronze object. Looks like large fibula.

G. Dia 0.092 m

Street 1, E-110-T, west 10.20, just up of wall + lying on strat. 2. in 1(2). p 971-1(2)

17 May 48.

SH 165

246. Rhodian stamped Amphora handle.

Taken from shards for Street 1, E-110-T, west 6-12, strat. 2. See p 959-2, 15 May 48

247. Vase? Frag. 8 lines head at top - hole in neck.

Taken from shards Street 1, H-2 west 6-8; strat. 1(2)


Cont p. 977

975

Scale 1/50

Do P 45

Street 1, west 0-6



strat. 3 Clean earth, no debris, no shanks
and very few tiles. 2 coins
found. F-508 and 328.
Notes A-M west 0-4
few I-X " " placed in street wall & marked.

[Cont. from page 970]
FILM 109
colored slides

976

5. Street 1 I-M west 0-4
looking west after removing
strat. 1 (C) before removing
2. L = 400 op 6.5 speed 1/100.

17 May 48, 10.08 AM.

6. Street 1 H-I west 0-4,
looking south. Note one large
fallen pan tile. Note also
tiles removed from Street 1
in pile.

Same time & exposure.

FILM 110
Kodak Plus X Weston 50

1. Room South of E. Bldg.
before removing Strat 2
[Trench 7, E-H, west 0-2+]
First strat. of surface sqt
here removed before war. See
Section p. 973 N.W. corner of
room looking in.w.

L = 400 op 1/100 op 16.
17 May 48 2:00 PM.

cont. p. 982

977 FINDS FILM 110

Sh¹⁵⁸⁹ 248. Joffet - unguent bottle -
two handles (amphoriskos) black
paint on outside. Part of
shoulder, neck & mouth only.
Rest not found.

Taken from Sherks Street I, I-K,
west 8-10. Strat 1 (C).
11 May

249 Coin Paphos 350-352 BC.
C 428

Street I, O-700-I, west 150m.
Strat. 2, debris. About 85cm
below surface.

17 May 1948.

250. Bronze ring & piece of lead
Street I, O-I, west 0-2,
Strat 2.

17 May 1948

DIARY

Cont. from p. 972
Removing Street I, O-I west 0-4
Strat. 2. Much of soil here
very powdery and grey in color -
could this be result of fire -
not at all characteristic of
soil which has been darkened
only by vegetation. Few stones
only from 0-2 west. Began
removing 2d strat west side of
room south of E. Bldg. See Film
110 #1 and section p. 971.
First Stratum here removed
before was. West side of room
would be Trench 7, E-H+, west
0-2+ to wall.

18 May

Mr. Hill continues working in north
end of alley, East of East Bldg. I.
See Film 159 #2 and 3. Removed
I 253-60 incl.

cont. p. 986

979

Street 1, 0-100-I, west 0-4 scale 1150 facing South



strat. removed before 1948
 " 19 " May 48
 " 2 " " 31/4/48
 red wires (early perhaps) cl.

(cont from page 977) 980
 251. Corn.

Street 1, 0-75-I, west 2.79 m.
 in strat. 2, consisting here of
 darkish brown earth, a good number
 of small stones, and many shreds.
 Very few tiles. About 0.40 m below
 modern ground level.

252. Frag of Bronze arrow head.

Same place as F151. Found beside it
 p 973-2 [room south of E. Bldg.]
 and began strat. 3. A small
 amount of tiles, shreds, and
 small stones in strat. 2.
 See Film 109 #1, 4, 5, 9.

M 923

+ 253. Bronze deer, fine workmanship -
 54-28.2

Street 1, 0-88-I, west 2.00 m
 lying on strat. 3.

981

FINDS

ST 874

+ 254. Seal stone

54-28-9

0.040 x 0.035 m.

Street 1, Θ -50- Θ I, west 2.28 m.
lying on strat. 2 in 2.

255 Coin

Antigona 1

C 429

Street 1, Θ -33-I, west 3.15 m.
in strat. 2 about 13 cm above
strat. 3.

256 Coin

Alexander

C 430

Street 1, Θ -32-I, west 3.65 m.
in strat. 2, 10 cm above strat. 3.

FILM ~~110~~ 110

982

2. North end of alley, showing
fallen wall. Looking northeast.

L=400 aperture 16, Speed 1/100
18 May, 9:15 AM

3. Same looking northwest
Same time and exposure.

4. Same as #1 after removing
stratum but leaving tiles &
fallen stuff as found on top of
stratum 5. See section p. 973.

L=400; aperture 16, speed 1/100
18 May, 1:40 PM

5. Same; close up showing debris
in n.w. corner.
Same time and exposure.

6. North end of alley, east of East
Building. Looking down from
east wall of alley near n.e. corner
showing fallen tiles
L=800 sp 1/200 aperture 16 18 May 1:45 PM

983

FILM 109

110

7. Street 1, 0-1 west 2-4,
after removing 2nd stratum.
Showing finds in situ including
coins, bronze deer (F) and
vas-es. Looking west

L=200 op 11 speed 1/100
18 May 3:00 PM

8. Same, looking south

9. Same as #4 after removing
tiles and fallen stones, showing
top of 2nd stratum. Looking NW.

L=

18 May 3:20 PM.

10. Coin Trench 9 n. 0, north
10-14. Looking North after
removing about a dozen worked
squarish blocks in place forming
lower part of 1st stratum. See
section page 187.

L=200, apert. 11, sp/100.
19 May 9:00 AM

FINDS

984

257. Coin

Alexander
C 431

Street 1, 0-96-I west 0.96 m
repeat 0.96 m. on stone slab.
See section p. 979. In strat. 2

258. Coin

Alexander
C 432

Street 1, 0-66-I west 3.55
lying on strat. 3. in 2.

259. Coin

Ptolemy (uncertain)
C 433

Street 1, 0-150-I west 3.60
in 2nd strat about 3 cm above
3rd strat.
18 May

MI 536

FINDS

260. Vase in white plaster
amphoriskos?

Street 1, O-107-I, west 270m.
in strat. 2 about three cm. above
strat. 3. In brown earth.

18 May.

261. Coin

Very thick
Th. 0.007 in. C434
Alexander

Street 1, P-100-E, west 1110
bottom of strat. 2. See Section
page 971.

262. Bronze frag.

L. 0.045 in

Found just north of F 261

263. Man's face figurine

Street 1, O-99-I, west 2.00 m
on strat. 3.

19 May.

DIARY

986

May 19

Digging trench 7 strat. 3
2-O to wall west 0-2 to wall
See section p. 973 Street 1
K-M west 0-12 finished removing
strat. 2 and began 3. Few
stones or tiles found in 2. Reddish
loose soil. See Section page
975 and 995. Finished removing
Street 1 P-E, west 10-12,
P-T strat 2 and began
strat. 3. Began digging trench 9,
2-O north 10-14 strat. 2.
Worked stones on top of this strat.
removed by draughtsman after
being thrown in situ. Myhill
digging in north part of alley -
removing fallen wall. Lamp
immediately south of south end
of alley. See Hill 109 nos 12 & 13.


May 20

Dug trench 7 2-[2-100-H] west 1-2
stratum 4. See Finds 280-284 incl.
Tracing course of precinct wall
on eastern periphery of site
removing old dump east side temple A
Stairway. Digging Street 1 P-T
west 10-12. 2nd strat contained few
number of stones. 3rd strat very
few except near wall at 1 (Section p.
971) int p. 987

Scale 1:50

Facing north

Trench 9, Section at A-Θ, west 12



FILM 109 110
[Cont from p. 985]

988

11. Street 1, K-M west 0-4
looking west after removing
Stratum 2. See Section p. 975 and
945.

12. Alley E. of East Building - north
end showing fallen tiles in fore-
ground and fallen wall beyond.
Looking south.

L=60 aperture 15 speed 1/100

19 May 10.30 AM.

13. South of alley looking north.
(from Mt Hill resumed excavations
in this area. L=

L=400 f. op. 16, speed 1/100

19 May 1.30 PM

14. Alley east of E Bldg. north end
looking south. Peg points to
what Mt Hill calls "red vase".

L=400 (Shade: 200) op. 12.5 sp/100

20 May 2.55 PM.

15. Place where F 284 found. Trench 7
E-150-Z west 1-12 in looking W.
20 May 3.20 PM C=300 op. 12.5 sp/100

DIARY

(from p. 986)
Trench 9, n-o (between walls)
north 6-10, strat 1. Many
worked stones. Tiles from
10-14 here (2d strat. See section
p 985) placed on east wall near
O line of trench 9, and marked
with tap in ink. Some marble
fragments placed on wall by them.
Tiles from n-o, north 5-10, placed
in pile on north wall just east
of O line, marked with tap in
ink - near 17 - north 6 m. stake.
Many large worked blocks in strat 1.
not very large - only average about 52x40
x12.

FINDS

[Cont. from page 985]

MI 513

264. Base in white paste,
neck broken; doubtful whether complete

Street 1, O-75-I west 1.72 m.
lying slightly embedded in strat. 5.

P 2537

265. Juglet; neck missing

Street 1, O-100-F, west 2.30 m.
lying on strat. 5.

P 2506²

266. Juglet, complete

Street 1, O, west 2.82 on strat. 5

267 head figurine, wheeled made
head finished - no paint visible.
H. 0.055

Street 1, O-40-I, west 3.00 m.
slightly embedded in strat. 5.

991

P2506 a

FINDS

267. Juglet much like previous complete unbroken. H. 0.057 m.

Street 1, 0-42-I, west 2.95 m
slightly embedded in strat. 3.
19 May.

Mi 537

268. Juglet in white paste
amphoriskos - rounded bottom. neck
broken off.

Street 1, 0-148-I, west 3.80
lying on strat. 3

M 747

269. Bronze arrow head and frag
of another bronze object, found
together. Other object appears now to
be in bone. - on iron eye inset. - B 7

Street 1, 0-25-I, west 3.60 m
in strat. 2 about 9 cm above 3.
19 May -

M 915 a

270. Lead stone (for sling?)
- all

Street 1, 0-100-I, west 2.50 m
on strat. 3.

St 877

FINDS

992

271. Figurine - standing male
figure - head + arms missing

Street 1, H-180-0, west 2.80 m
lying on strat. 2. See 979-3

Mi 510

272. Frags of amphoriskos in
white paste

Street 1, 0-175-I, west 0.10 m
on strat. 3 p 979-3

273. Shards + frag of juglet.
- not cat.

Street 1, 0-40-I, west 2.90.
found around juglet # 267. on
strat. 3.
19 May.

274. Frag large animal figurine

Street 1, 0-38-I, west 3.00
in strat. 2.

P 2536 a FINDS

275. Juglet

neck and mouth missing
P.H., 0.062 m

Street 1, 0-190-I, west 3.60m
in strat. 2. about on 3.
19 May.

276. Bronze arrow head

A little north
in 2 south of #275 on 3
19 May.

277. Iron frags. - too frag'y to cat.

Street 1, 0-140, I, west 3.80m
lying on 3 p 979-2,
19 May.

P 2218
278. Frog, juglet

Street 1, 0, west 3.50 in strat. 2
979-2
19 May

FINDS

994

279.



Antigonas I

C 435

Not sure whether in Soto - but
probably from Street 1, 0-I,
west 0-2, on strat. 3
Removed 19 May.

P 2504

280. Juglet

Trench 7, 2-96-H, west 1.55
lying on strat 4 in 3. next to
south face of wall running east-west.
20 May.

P 2503

281. Juglet

10cm south of #280 also on 4.

282. Figurine - man mounted on horse

Trench 7, 2, west 2.00.
in strat 4. p 973-4

92505
283 Juglet

Trench 7, 2-15-H west 1125 m.
Bottom of strat. 4 on stone slab
paving block.
20 May

@
284. Bearded head of man - mold made
figurine. There are two 284's,
one being a coin.

Trench 7 E-150-2 west 1112 m.
in strat. 4. See p 973-4
near wall to east running north-south
See Film 110 #15 for place where
found. Meter stick marks place.

284. (Coin)

Demetrius Pol.
C 436

Street 1, E-120-T west 11150 m
lying on strat 3 (p 971-2).
22 May.

cont. p.

0 A
2 B
4 Y
6 d
8 e
10 S
12 7
14 8
16 L
18 K
20 1
22 W
24 V
26 S
28 0
P
Q
R
T

122
911100
I
20
18
20

There is a

635, 23

36

672

1 stade, + 12 fathoms

Ay. Epm foot
0.3387 m.

671, 23

$$\text{foot} \cdot 339 = \begin{array}{l} 72 \text{ ft} = 24.44 \\ 672 \text{ " } = 227.8 \end{array}$$

Ay. Epm. foot of .339

stadium


$$\begin{array}{l} 72 \text{ ft (12 fathoms)} = 24.44 \text{ m W. of arena} \\ 672 \text{ ft (1 stade + 12 fath)} = 227.80 \text{ m L " " } \end{array}$$

223.5

-1121


→ N

Trench 10, 4-6 east



Trench 10, A-Z
east 10-12

Trench 10, 10-12 east



scale 1:100

all levels from mark (6) Street 1

