APOLLO

BOOK

XVI

3002

Kalorizikj Tomby f P. 3040 fi..
For other tombs see Kalorizikc
Note Book i


Apollo

APOLLO 3002

INDEX

SAH

3007 Section at 0.75 m w. of w. face of e. wall of S. Bldg. Looking east
Scale 1:25



S. Bldg.

0-50-1.00 w. of e. wall as 2 1.00 n. of s. wall 2953-3

"

00-1.00
00-1.00 2953-4
3007-4

DIARY 3008

15 JAN. 52 Cont. fr. 2986


Removed 0.50-1.00 m w. of w. face of e. wall of S. Bldg. and 00-1.00 m n. of s. face of s. wall 2953-3, hard whitish mortar with few stones averaging less than fist size, a bone, 1/2 bucket sherds. No other finds.

Removed q/s same area 00-1.00 n. of s. wall and 00-1.00 w. of e. " 2955-4, much like 2955-3 but whiter and harder - only strong small sherds. No other finds save frag figurine which have placed in sherd bag. See also 3007-4

16 Jan. 52

Removed 7.50-9.00 m n. of s. face of s. wall of S. Bldg. 7.50-9.00 m and 00-0.75 m w. of e. wall of S.E. Bldg. 2955-5 moderate amount of rough stones ranging from stone to foot in size resting upon leveled compact soil. Small sherds. No tile frags or other finds.

3009 Between S and SE. Bldgs
Section at 1.10m S. of N.E
corner of S. Bldg. Looking North
Scale 1:50



DIARY

16 Jan. 52 cont

Between S+SE Bldgs

1-3.00 S. of N.E. corner of S. Bldg.
S. of N.E corner of S. Bldg.

3009-1

F1989-90

2957-5

F1991


Removed 1.00 - 3.00 m S. of N.E. corner of S. Bldg. between S. + SE Bldgs. 3009-1 reddish brown soil - almost all stones left which look as tho' they are like a fallen wall. Some Film. Bucket of shards, bone, small tile frags which I am throwing out. frag 1989 Roman lamp disc and some glass frags. F 1990 No other finds.

0.20 - 1.90 n. of n. of S. wall of S. Bldg
Removed 0.20 - 1.90 m N. of S. face of S. wall of S. Bldg between S + SE Bldgs 2957-5 hard brown soil with many stones averaging from fist to foot in size. handful of sherds + 1 frag. Roman frag F1991 + tile frags which I am stacking in foundation of W. wall of S. Bldg. No other finds.

00 - 0.50 n. of N. wall of S. Bldg
00 - 1.00 W of E wall
3007-5
Removed 00 - 0.50 n. of S wall of S. Bldg and 00-1.00 W of E wall. 3007-5 hard red soil without stones larger than walnut size. Half a sherd only - no tiles - no other finds.

301

Section at 2.15m S. of S. Building looking north
Scale 1:50



FINDS 302

1990. Glass frags. - Some clear thin & blown

Same provenance as previous
16 Jan. '52

1991. Tin fig frag. Horses head

Between S + SE Bldgs
0.20 - 1.90 m. of S. wall of S. Bldg. 2857-S

16 Jan '52

DIARY

16 JAN. 52 cont

1.60-2.50 on 1.60-2.80 m
S. of S. 15168

Removed S. of S. 15168 1.60-2.80 m, 40.00-43.00 m e. of w. wall 3011-5 loose dark greyish soil with very few stones 10 sherds only no tiles & no other finds. Darkness of soil possibly due to fire.

40-43 e. of w. wall

3011-5

Removed same area 3011-6 compact red soil with rubble & ancient stone averaging not much more than egg size but some up to fist size & about 1" thick tiles. Many tiles; 7 frags. Glazing F 1992: No other finds.

3011-6

15 etc. S of SE 15168

0.20-1.50 N. of E. S. of wall of S. 15168

Removed 0.20-1.90 m N. of S. wall of S. 15168. Between S. & S.E. 15168 2 E-7-6 hard reddish fill with few stones none larger than fist size - average egg size. No finds.


2 E-7-6

17-25 JAN

E. of S.E. Bldg. court

Cleaning E. of court in S.E. 15168. No trenches dug. Quite few very small pits & one whether well found at various parts. 5 men.

0 – 1.50 S. of S. Bldg. at 1,00 m. east of N. wall Looking east Scale 1:25



FINDS

Cont. fr. P. 3012

1992 Coin

C 3613

Constantine I

3.00 m. e. of S.E. corner of S.E. Bldg. at 0.90 m. below highest stone (Top of stone) in N. wall of room e. of S.E. Bldg. in loose debris

Removed 7 Feb 92

1993. Coin

C 3614

Hephthalite Imit.

See Film 166-10

On foundation of E. road at 0.44 m. S. of S. Bldg and at 27.30 m. E. of S.W. corner. About 0.30 m. below top of early wall. At 0.09 m. below bottom of ~~course~~ orthostate forming 1st course in wall N. wall of S. Bldg.

11 Feb 92

S. of S. Bldg. DIARY 3018

Duo intermittently between 25 JAN & 14 Feb with from 3 to 5 men.

14 Feb 52

S. of S. Bldg.

between S. wall & early wall

25.00 – 32.40 e. of w. wall

Finished cleaning foundation of S. wall of S. Bldg. to depth of approx. 0.10 m. Surface of foundation between S. wall and early wall from 25.00 – 32.40 m. E. of W. wall – practically up to store room door. Large brown soil removed only – no stone. A boot, 1 bucket sherds of which I have thrown out 1/2; no tiles; 1 Cypriot character incised on sherd F.1994, and 1 proto-Ionic piece pierced with 3 slits. No other finds.

Hellenistic & later

14-18 Feb

Same 32.80-37.80 e. of w. wall


Same Finished cleaning same but only down to foundation of S. wall & over foundation. A few descript coarse were thrown out. No other finds. Removed from 0.05 to 0.10 m of soil.

Cont. p. 3022

309

Section at 1.69 m N. of S. wall of S. Bldg LOOKING NORTH

Scale 1:25



nothing late
1 prob Hel

FINDS 3020

1994. Sherd with incised cypriot character.



Between S. wall of S. Bldg. and early wall
00- 0.10 m below top of foundation of S. wall
14 Feb 52.

1995. 3 4 figurines + 2 sherds

00. 1.20 m S. of S. Bldg.
2615-3 at 21.00-25.00 E. of W. wall
18 Dec 52


cont. from p 3018

Removed same from
21.00-25.00 21.00 - 25.00 m e. of w.
e. of w. wall wall and 00 - 1.20 m
s. of S. wall + also to
depth of 0.25 m below
top of foundation of
S. wall. Sq. 26.5-3.5
26.5-3 Loose reddish soil with
few rough stones and
flavor than walnut size
Su 8 Film 166-23. Retained
3 fragments & 2 sherds
placed all in one bag.
Plan 1985. No other
finds.

Removed same 00-0.52
S. of S. wall, between wall
13.00-21.00 and ancient road. Same
e. of w. wall from top of foundation
of wall to depth of
00-0.50 0.20 m below. Fill
S. of S. Bldg. piece removed same
soil over foundation.
13.00-21.00 m e. of w.
wall. Loose clean soil
without stones - brown
to dull reddish soil.
2623-2 Su. Film 166-24. Di-
1 lot section p 2623-2. Re-
moved 12 small sherds
only. No other finds.

00-1.40 Removed 00-5.00 m
e. of w. wall S. of S. Bldg. + 00-1.40 m
e. of w. wall 3015-1.
3015-1 Loose reddish brown soil

3023



DIARY 3024

3018-1

with good number of grogg sherds averaging fr about fist size but up to foot in size - probably all filling in about 1/2 bucket sherds. NO other finds. NO Finds Illus 165-85

1.60-2.50 n. of s. wall s. of w. of w. wall of s. 1510 3017-1

nothing late 1 prob Hal

Removed 00 - 0.47m w. of w. wall of s. 1510 and at 1.60 to 2.50 n. of s. w. corner P 3018-1 reddish loose soil with few sherds not larger than quart size. About 2 to 3 handfuls of sherds. NO other finds.

S. of S.E 1510 00-4.40 south 11.10-17.60 e of w. wall 3023-1 4th cut A.D

Pit 00 - 4.40 m South of S.E. 1510 to 11.10 - 17.60 m east of west wall. 3023-1 all debris. Between 2 walls running north south. See Illus 166-87 many stones but unworked rough pits removed from pit to bucket. Size of top - fourth bucket. Sherds & animal bones. About 1 bucket full of sherds. Coins P-1196 P-1197. All 4th cent. 1/2 bucket. Tiles about 1/2 bucket stacking at top

3025

DIARY 3026

S. of S. wall and on wall running north and south at 11.00 m E. of S. wall of S.E. Bldg. Worked blocks not yet removed 2 figurine heads E 1998. Sherd other finds

14-18 March '52

Due intermittently with steam pt. 5 hours from 14 March. 18 March rain interrupting work

14-18 S. of S.E. Bldg debris

South of S. wall of S.E. Bldg. - debris only - many rough stones collapsing between East & West at 5.25 but some larger - loose dark surface soil. Area cleared between S. wall & fence - No tiles or two hard sherds - as surprising factor

19-21 March

Finished removing

S. of S. Bldg. 5.00-5.00 39.00-43.60 e. of w. wall 2633-2

5.00 - 5.00 m S. of S. Bldg. 39.00 - 43.60 east of west wall 2633-2 Loose darkish soil, very few stones - more larger than just side - apparently all fill - no definite floor - 4 tiles 12 flakes - 4 sherds - 4 tiles 12 flakes which I am throwing out. 5 bone pins E 1999 No other finds

E 1999

FINDS 3028

1996 Coin

C 3615
Volusian
Sestertius

15:00
3.90 m e. of w. wall of S.E. Bldg.
0.18 m S. of S.E. Bldg.
0.80 m below top of top step
in 3023-1 in S. wall 18 Feb 5L
Ex. Film 165

1997 Coin

C 3616
Probably
Copper

17.45
2.35 e. of w. wall
2.45 S. of S. wall
1.47 below top of top step

Same provenance in 3023-1
as bedrock

1998 2 terra figurine fragments

in 3023-1
Same provenance
18 Feb 5L

FINDS 3030

1999. Coin

(= 3611)


Constantine II

5.05 m s. of S. Bldg.
40.50 m e. of W. wall
at bottom of 2633-2
level: -2.15 below
threshold block main door
room 4.
22 March 52

2000. Lamp
Bronze type XXVIII

S. Bldg. cor. 3, 0.10 w. of e. wall
0.60 n. of S. "
in 3031-1
at below top of restored
e. wall of corridor
29 Mar 52

3031


S. wall
Edge 3
Curve 4
Curve 5
Foundation
wall
Trigger facing
3034
Entrance
3034
3035
3035
3035

5033

DIARY

3034

March 28 + 29

S. Bldg.
C5-3
0.0-0.60
n.f.s. wall

Removed 00 S. Bldg.
corridor 3 (gully 3) 00-0.60m
n. of S. wall, 3031-1,
not have but stratum of both
compact stratum of both
reddish + dark soil mixed
throughout, moderate
number stones averaging
between walnut + fist size.

3031-1

Small tile frags -
throughout - 1/4 sherds -
Brewer type XXVIII
lamp (F 2000) No
other finds the dark -
patches in the soil I
see now is due to
charcoal - quite a bit of
it.

"

Removed same area.

3031-2

3031-2 more homogenious
stratum than 3031-1
about four strata first
size the last - left
very many averaged about
walnut size, small brown
soil 2 handfuls of tan
sherds - 1 pipe stem
F 2001 small fox -
thin flat glass F 2002.
No tiles. See Film 166-65
films.

FINDS 3056

2001. Ter. pipe frag.
Given to J.L.

S. Bldg. corridor 3 00-0.60m
N. of S. wall in 3031-2
29th March 52

2002. Small thin blown
glass frags.

Same province
2003. Ter. lamp frag decay
Roman.

Same prov. but 0.60-1.60
in 3031-2
31 March 52

DIARY 3038

31 March 52

Removed same place
303/-3 Loose slightly
3031-3 reddish brown soil fair
number of stones increasing
between 1.00 and 1.50
size handful of sherds
1 fragment of flint no
worked - no tiles - no
other finds.

Removed same area but
0.60 - 1.60, 3031-1
3031-1 Same as 0.60 - 1.60 but
0.60 - 1.60 with fewer stones
1 class A stones. Handful sherds.
2 bones (animal) - sheep
placed in store box -
2 tile frags thrown out.
F2003 1 clay lump frag.
F = 2003.

1 April 52

Removed same area
3031-1 like that
3031-2 removed from 0.00 - 0.60
0.60-1.60 p.f.s. well. About 1/8
bucket sherds, small
roof tile frags, thrown
out - 2 iron frags
placed in box for sherds. No other finds.

(Sub) Mycenaean tomb 3040
Kalorizíki

Tomb 40

Pencil refers to publication nos.

FINDS

P 2205 ✓ 1. Jug/et - .43m from datum line complete, and unbroken. Above bench
Tomb 40 -6

P2204 2. Amphora, neck broken - T40-5 - 0.67m below datum standing on bench
Daniel Tomb 26A-39 LC III A (1225-1100)
25-2746z

P2205 ✓ 3. Amphora - probably complete but broken on bench - .71 below datum line.

P2200 ✓ 4. Small cup, complete broken, lying upside down on bench Tomb 40-1 at same level

P2201 ✓ 5. Similar cup - also on bench - same level - broken but nearly if Tomb 40-2 not complete.

Kalorizikè 3042
Tomb
FINDS

P2202 V 6. Larger cup - broken - possibly incomplete - on bench at same level - a little over - 0.73 m.

Tomb 40-3

Kylix

P2207 7. Pot with narrow neck - broken - probably incomplete in many pieces - same level - on bench.

T40-8

P2203 V 8. Large cup with stem. loop handle - broken - about complete - on bench at level - 0.71 m.

Tomb 40-4

Lenticular flask

P2209 V 9. ~~Pot~~ nearly complete neck broken - level - 0.67m; over bench.

T40-10

Juglet

P2206 V 10. ~~Conical stopped pot~~ pinched lip handle missing - nearly complete F/pot level - 1.09 m below datum line.

T40-1

2 pieces in lip missing.

Kalopsidha Tomb 5 44

FINDS 40

M1022 11. Bronze bowl - broken - many pieces. Level -0.72m on bench. full of earth

See Film 166.

M1000 12. Bronze bowl - full of earth broken, incomplete 2 handles many pieces

See Film 166. including lid

M1023

over bench at level -0.55m

Finds within bronze bowl are nos.

M1001 Gold pin 12 (a)

M1499 Bead 12 (b)

St. 518 fruit stone (c)

many bits of burnt bone inside bowl. Possibly human remains 12 (g)

M1002-1011 bronze safety pins (d) (e)

12 no bronze pendant. M1012 frogs. (f)

M1013 13. Bronze spear head. complete - in two pieces.

Point about 0.06m above floor. Level -1.03m.

Kalorizikí Tomb 3046
Finds 40

✓

M1019 14. Strips of bronze 0.025 m width (width with holes probably for rivets) 2
M1018 12 nobbed discs about 2
M1014-16 0.035 m in diam 2
larger discs ¼ inch.
pieces of bronze

All found together at same level of −1.09m below datum line.
The strips were lying flat as were the discs the knobbed side being on the up side one strip was lying directly under rough stone 0.28m to east of this.

M1020 16 bronze pendant

M1021 15. Bronz. iron ? frag. in 2 pieces

On bench at level

31-2 April.

Kalopsidha Tomb #40 "Gold Sceptor" tomb

At work as digging with teams of two men set by Apollo Christo with Lymeir supervising. Started out crop at Kalopsidha in search of tomb from which gold sceptor now in Cyprus Museum is said to have come. One Savvas passing, also aided by Socrates this tomb about 45-1 years ago (Christ's computation) for their attempt to sell the find at Larnaca for which it was seized by the Police. Socrates and Savvas fined by name of Savvas Marko Socrates indicted approx Jocotish £ Christo. The Museum about same time 45 years ago Soon after the tomb had been rifled reported to Christo that very possibly some finds had been left behind. Draughtsman's plan will show location of tomb which I am placing the tentative name of X. The tomb was found full of

Socrates Marco (dead) Savvas (dead) Our tomb 45 years ago 51- Kenil boy at time watched. He indicates place to us. Socrates too ill to come down.

Kalorizeki Tomb of Gold Sceptre No. 40

loose sandy soil - all of it the same - quite homogenious - No remains of fallen roof what so ever. The chamber is hewn out of "awno-xaBapa". Possibly there never was a roof - just an alcove in the rock with an entrance at the north side - still undug. See Film 166 - 1 and 12. For tomb in general & finds as found see Film 166 - 6-12 incl. See also Sections & plan of finds as found in W. end of the room.

Curious thing about all is that there is no trace of any intrusive pits for clearing the tomb & finds not cleaned out in as much as we found some whole pots and good bronzes - age of tomb, contents &c. The gold needle pin. There was the discernable stratification. I think the reason for not finding any trace of intrusive pit is that the soil is very sandy and everywhere the same from surface to bed-

cont'd p 3051

DIARY 3052

S. Bldg. 2 Apr. 52
cor 3 Apollo cont.

Removed S. Bldg. cor. 3
0.60 - 1.60 m. w. of S.
wall 3051 - 3, Foto
0.60 - reddish brown soil with
1.60 m w. of S. wall few number of stones.
3052-3 Soil rough crs. averaging not much more than egg size but two up to fist size. No tiles only 1 piece charcoal unlike 1st & both of which contained charcoal in this area. About 1/6 bucket sherds - some ribbed. 1 flint - 1 piece lead placed in Sherd bag. No other finds.

3 Apr. 52

00 - 1.60 Removed same area
17. of S. wall 3031-4 @ loose stone
reddish brown soil stone
dark brown - no charcoal -
3031-4c relatively more stones than in 3031-3 - rough crs - larger than 3 have ~~average~~ ~~size~~ many two buckets of larger stone first size - fist size, majority egg size. about 3 bucket sherds - no other finds.

DIARY 3 Apr 52 305-6

Removed same area
as 3031-4G -
3031-4G Same as 4.a except
no foot & size stuff -
Left all small unrecog
size sherds
only. No other finds.

4 Apr. 52

Stratum 3031-4G
truncates with layer
consisting almost wholly
of charcoal - fills E
side wall this sq.
and foot of foundation
at west wall of room 3.
3031-5 From floor to foot of
wall found 3 sherds

Kalwizaki Tomb X cont. Tomb 40

Kalwizaki Tomb X 3058

cont. from p. 3050

rock. Thus an ancient fill would hardly appear different than that of the undisturbed fill of an intrusive pit. There were practically no finds anywhere, save at the S.W. corner. I believe and think it almost certain that no previous excavations or tomb robbing in modern times ever took place in the S. end. There is a place in the centre of the chamber where someone has dug into the rock-hewn floor. One Socrates who dug tomb 45 years with Clarence, who died, and Spence, also dead, says that he made this hole in the floor in order to assure himself that he had reached the bedrock - that is the rock-hewn floor. It appears that with a fork the side of the pick in the unstooled fill for the S. side of the chamber. Hence they have sunk the top of the bench or two further S. into the less shorter face. Thus the SW corner was remained uncleared. - Suspect

that the Cyprus Museum never had this long in an effort to find the one containing the gold Sceptre for else it they should have found the bench. It is likely to believe that both the parties knew of the tomb and failed to try uncover the bench. Socrates told Christo that the tomb was a very shallow one, like mine, and on the line of the rock outcrop. The evidence seems pretty conclusive that our tomb is the tomb of the gold sceptre. I am told now by our foreman, Christo, that the old villagers agree that the tomb was not only in the edge of the outcrop but also between a fig tree and a carob tree with 3 trunks (pines) and right by a "μοσφιλα tree. The place indicated by Kamal (the boy-guru and his uncle) who watched Socrates + Co. dig the tomb 40 years ago also confirms this evidence. the place where we found Tomb 4. We have found

the roots of a μοσφιλα right alongside of this tomb.

For cont. see Kalavrizika note book

FINDS

2004. 4y. 3 bags of broken lamps

00 - 6.50m S. of S. Bldg
49.80m E. of Sw. end of
Southeast Jamb

P. 2641-3
16 May 52

cont. p. 3063

S. Bldg.
0-4.50m
S. of S. wall
49.80 east
of S.E.
corner

P2641-3

P. 16 May 52 3062

Removed 00 - 4.50 m
S. of S. Bldg. from 49.80m
E. of W. end of S.E.
corner structure P2641-3
moderately loose gathering
great amount of blue &
pebbles, good quantity of
rough stone from
fist to foot in size on
surface - soil mostly
reddish, pieces of burnt
brick, pieces of
decomposed building
material. Removed 1st
foot 3 inches by rows
and of roof tiles and
about 5 buckets of
shards. From 4.50m
S. of S. Bldg. to fence
removed 1 foot 3 more
more buckets of shards
and colored glass. Lots of
roof tiles. Here the soil
was not so red and there
was very little gravel
(blue pebbles) and fewer
stones. 3rd and 4th
level 0.00 - 6.50 m
S. of S. Bldg. removed
also 3 bags of
broken lamp frags. F 2004
F 2004 and 2 bags
of black frags F 2005-
F 2005 and 12 coins F2006-17.
F2006-17 Have stacked roof tiles
close to wire fence
opposite door of guard

cont. A.D.

Class A

G2

FINDS


2005 2 bags of Crotch s/less.

Same provenance 16 May 12

GL 288
GL 289
GL 291
GL 292
GL 293
GL 294
GL 295
GL 296

GL 297
GL 298
GL 299
GL 300

2006. Coin




C 3618

Constantius II

Same provenance - found by shovel.

FINDS.

2007. Coin



C 3619

Illegible (Alexandria)

Same provenance found by shovel

2008. Coin



C 3620

Constantius II (?)

Same provenance found by shovel

2009 Coin



C 3621

Elagabalus in San Alexander

Same provenance

FINDS.

2010. Coin

C 3622

Claudius
or Nero Alexandria

Same provenance - found by shovel.

2011. Coin

C 3623

Hesperia 4, 37-44 A1

0.23 m S. of S. Bldg.
50.00 m E. of S.W. corner
level - 2.59 below
also p2641-3 16 May '52

2012. Coin

C 3624

Constantius Chlorus
Caesar

1.00 m S. of S. Bldg.
4.60 m W. of S.E. corner
in P. 2641-3
level - 2.69 m below
16 May '52

DIARY 16 May '52 3066

hinge near gate. Fza4-17 were found at bottom of stratum. The stratum has not changed but I am now using as just are now below the level of the foundations of the S.E. Bldgs. See File 167-19

17 May '52


S. of S.E. Bldg.

P3071-1

3 men - 3 hours only as rained lightly almost all day.

Removed 00 - 2.90 m east of S.W. corner of S.E. Bldg. 0 - 4.35 - m S. of S. wall, P3071-1 (same as P2641-3 in level) loose reddish soil with many rough stones averaging first to foot in size, no gravel here about 1½ inches. Layer full of red tiles and ½ bucket of sherds. This stratum appears to consist mostly of

FINDS

2013. Coin 

C 3625

4th cent AD, uncertain

3.80m S. of S. Bldg.
4.60m W. of S.E. corner
level -2.44m below
datum point 2641-3
16 May '52

2014. Coin 

C 3626

Uncertain (probably Ptolemy IV, Type
A series/Commagene)

0.90m S. of S. Bldg.
6.25m W. of S.E. corner
bottom of 2641-3
level
0.20m below top of foundation
course of S. wall.

FINDS

3068

2015. Coin 

C 3627

Elagabalus

5.80m S. of S. Bldg.
49.80 E. of S.W. corner
bottom of 2641-3
level
16 May 52

2016. Coin Thick 

C 3628

Commodus

5.70m S. of S. Bldg.
also 49.80m E. of S.W. corner
bottom of 2641-3
level
16 May '52

FINDS

2017. 

C 3625
Ptolemy II

2.50m S. of S. Bldg.
0.06m W. of S.E. Bldg.
Straight just S. of S.E. corner of S. Bldg.
In P 2641-3 bottom level
16 May 52

2018. Two lamp frags - rims. of probably Brauron type XYVII or XXVIII.

0.0 - 2.90m E. of S.W. corner of S. E. J Bldg.
0 - 4.35 S of S. W wall
in 3071-1
17 May 52


DIARY 17 May 52 3070

F2018 of debris. From here came F2018 (lamp) and plain frags (glaze) There placed in lot with other finds. Hard stacked tiles at 2.50m east of S.W. corner of S.E. Bldg. See Film 167-20

26 May 52

0-4.00m S. of S. Bldg. 44-48.60 E of W. wall 2613-3

Removed 0 - 4.00m South of South of S. Bldg 44.00 S - 48.60 N. under East of W. wall P. 2613-3 Good number of stony area. Going down flat and took size from amount of small pebbling - gravel - slightly reddish brown soil - Probably debris but might be late fill - about 1/3 buckets of shards 2 buckets of roof tiles. Lots of pieces fresh. F2019 and lamp frags F2020 Stacking NO edge at 48.60m east E/W wall up against S. wall of S. Bldg. See Film 167 nos 21 & 22.



Section at optrench 1.40m east of S.W. corner of S.E. Bldg Facing south
Scale 1:50

S. Bldg. DIARY
Excav. 4 10 June 52
between E. platform + N. wall

Removed below level of fallen stone facing (F114 165 - 19) fill of debris between north wall S. Bldg. and E. platform of excav. 4, 3075-1 and 2021.

p3075-1

Clean stratum 1 throughout. Fairly large pieces red brick brown soil with hardly any stones larger than medium size. Small tile frags which I am stacking in bucket. Small pieces of lime concrete which I am stacking with tiles.

F2021 2022

Frags. of Roman type XXIIII lamp F 2021, 2022, coin F 2023.4 and glass frags. which I am placing in box in stud bag.

14-18 July

S.E. Bldg. + E. portico

Mr. Hill repairing S.C. + N.E. corners of S.E. Bldg. Stylobate. Retaining fallen wall blocks + dumping round fallen in east portico.

F2023.4 Finds 2 coins. F 2023.4.

3673 FINDS

2019 Box of glass frags.

GL 199 GL 302
GL 202
GL 211
GL 220
GL 284

0 - 4.00 m. S of S. Bldg.
44 - 48.60 m E. of W. wall
in P 26 B-3 J
26 May 52

2020. Bur lamp frags

Same provenance.
26 May 52

3674 FINDS

2021. Coin
C 3630
Constantius II

S. Bldg. exedra 4,
0.12 m S. of N. wall
1.62 W. of E.
near bottom of debris at sprung floor level between E. curb of E. stylobate & N. wall.
Level -0.17 m
Film 168-21.
9 June 52
Found under Arch. block 40. showing in Film 168-18


2022. Coin
C 3631
Constantius Gallus Caesar

S. Bldg. exedra 3 at 1.00 m S. of the S. face of the N. wall and 1.53 m E. of the E. face of the west wall at level of 0.13 m or same as concrete floor.
Film 168.
12 June 52

0.15 m S. of N. of threshold block

3075

S. Bldg. Trench 4, between E. Platform + N. wall



FINDS

3076

2023. Coin

S.E. Bldg.

C 3632

Pollentinus Maximianus

top of east wall at 5.45m n. of S.E. corner, under deposits.

17 July 52

2024 Coin

C 3633

Constans

S.E. Bldg.

0.20m e. of E. stylobate
1.05m n. of S.E. corner of stylobate
0.52m below top of stylobate
under fallen wall

17 July 52.

S. Bldg. Pedera 4, Centr. N. end
Section at 0.90m E. of W. face of W. 25 Y/6 face wall
Looking East Scale 1 : 25 Film 165-28

FINDS

2025. Marble inscription complete. Broken in 3 pieces I 14b

For provenance see Film 171 - 24:
Under debris near east wall of room immediately east of S.E. Bldg / near S.E. corner
For text see Film 21 - 25

X.42 X 0.22 X 0.043

ΠΟΠΛΙΚΟΛΑΝΠΡΕΙC ΚΟΝΝΕ
ΠΟΔΙC ΠΕΡCΗΟC ΑΓΑΛΜΑ
ΚΟΙΡΑ ΝΟΝΑΓΝΕΙΑC
CΤΗCΑΤΟ ΠΑΡΤΕΜΕΝΕΙ

3079

3080

F2026-F2044 19 Bronze coins

Recorded 28 Mar. 54. From box labelled in Greek: "Apollo, 14-5-48. Coins from the sieve. From Θ-K West, 8-12, stratum 1 a."
Closest reference seems to be p. 945, entry of 11 May 48. (GRE)

F2026 C4156 Ptolemy II, Cyp.

F2027 C4157 Ptolemy II, Cyp

F2028 C4158 Ptolemy II

F2029 C4159 Unidentified, Greek

F2030 C4160 Ptolemy I, Cyp

F2031 C4161 Ptolemy II, Cyprus

F2032 C4162 Alexander the Great Cyp.

F2033 C4163 Antigonus I Cyp

F2034 C4164 Curium 4th cent

F2035 C4165 Alexander the Great, Cyp

F2036 C4166 Demetrius Poliorcetes

F2037 C4167 Antigonus I Cyp

F2038 C4168 Curium, 4th cent

F2039 C4169 Ptolemy I

F2040 C4170 Illegible

F2041 C4171 Illegible

F2042 C4172 Curium, 4th cent

F2043 C4173 Paphos, c 400 BC

F2044 C4174 Illegible

F2045-2047: 3 Bronze coins
Recorded 28 Mar. 54. From box labelled in Greek: "Apollo. 30-5-48. Street 1, E-H, west 0-4, stratum 2 coins from sieve." Reference seems to be to p. 1052, 29 May 48. (GRE)

F2045 — C4175 Ptolemy I Cyp

F2046 — C4175 Illegible

F2047 — C4177 Demetrius Poliorcetes

F2048 Bronze arrowhead

In same box with F2045-2047
L. 0.03 Triple

7 Bronze coins
Recorded 28 Mar 54. Found in unlabelled box in Apollo apothekee. Probably picked up in Apollo from time to time by guards. (GRE)

F2049 — C4179 Ptolemy III

F2050 — C4180 Unidentified rev. obliterated

F2051 — C4181 Ptolemy III

F2052 — C4182 Arcadius Cyzicus

F2053 — C4183 Ptolemy VIII 170-116 BC

F2054 — C4184 Julian, C


F 2055

C4185 Illegible
V cent AD?

F2056 Bronze lamp-cover(?) in form of shell.
Max. d. 0.045
Found in box with F2049-2055 + F2057.



F2057 Bronze bezel of ring (?)
Max d. 0.016
Found in box w. F2049-2055+F2056



F2058 - Bronze coin.
Recorded 28 Mar 54. Found in envelope labelled "Street I West H-O 4-6 STRAT. I.A. p.29 marked x on plan. coin. V/F/~~28~~ 48."
Best ref. seems to be p. 924, April 30, 1948. (GRE)

F 2058

C4188 Ptolemy II
Cyprus

F2059 Bronze coin.
Recorded 28 Mar 54. Found in envelope Labelled "Street I West H-O 2-4 p.29 marked x. coin STRAT. 2. V/F/48"
Best ref seems to be p. 924, Apr. 30, 1948 (GRE)

F2059

C4189 Illegible
Demetrius Poliorcetes?

F2060. 1 Bronze coin.
Recorded 28 Mar 54. In envelope labelled in Greek: "Apollo. 11.6.48 coin found outside the Excavations."

C4190. Illegible
rev/obv. head?
Tyche. Imp. times

F2060

F2061 1 Bronze coin
Recorded 28 Mar 54. In envelope marked "31 May 50. In vicinity of St. Anne. Found by Forest guard."

C4191
VALERIAN
254/60 AD
Corycus

F2061

F2062 1 Bronze coin
Recorded 28 Mar 54. In envelope marked: "Z-H W. 4-6 at 15 cm. St. 1 WEST. ON 1 WE of H at St. 1 15 cm. below surface."

C4192
Licinius

F2063-2065 3 Bronze coins.
Recorded 28 Mar 54. Found in envelope on which ~~writing~~ writing (of G H III C F) is almost totally invisible. only "May 19, 38" can be distinguished.

C4193 Carinus

F2063

C4194 Illegible

F 2064

F 2065 C4195 "Vandal"? Illeg.

F2066. 1 Bronze coin
Surface find 24 Mar 54. Partly excavated area N. of Street 1 + East of Room w. marble pavement (G RE)

C4196
Curium, 4th cent?

F2067 Inscr. fr., white marble

I 49. surface outside Apollo baths Aug, 1951.

H. ~~0.03~~ 0.053. W. 0.08
Sl. frag. pres. part of top edge + plinto of 3 lines of ? writing.

ΤΕΔΑΝ
ΙΛΗΝ
ωΦΡ


F2068 Inscr. fr., marble

With tag in Greek: "Apollo 18/3/1937. Trench 9 H-Θ North 16-18. ἀπὸ πανὸ ἀπὸ τὸ δευτερ.ον στρωμα"
Not recorded ~~in~~ among finds in Notebook, but see p. ~~147~~, note of Mar. 18, 1937. (GRB) ~~I 78~~

I 145

I 153

PW. 0.10 PH. 0.075. Th. 0.014
IF, lower edge + back pres.
L.H. 0.04? 4 letters of 1 line pres.



Recorded 7 Apr 54.

F2069 Inscription, limestone

I. 150 Found by Christos Gregoriou near road entering Apollo from main road ca 1950. It apparently had been brought there to be used in building P.W.D. hut. ×

W. 0.57 PH. 0.26 PTh. 0.33

IF, L + R edges + perhaps top surface pres. L.H. 0.04.


Parts of 2 lines legible. Probably there were 3 or 4. Stone badly weathered + worn.

× M.H. Ford says "Copied by me in the summer of 1936 on the wall of a dosshutt that now demolished which stood beside the modern highway and some 200 yards south of the Sanctuary of Apollo..."

F2070 Inscription, white marble

I 149 Recorded 7 Apr 54. No tag, no NB ref. Stated by Christos Grigoriou to have been found at Apollo in Exc. after the war and to have been stolen by visiting school children & later returned

Pw 0.243 Pth 0.21 Th. 0.015
Lth 0.033.
1 F, back, top + L edges pres. 1 large fr + 1 small fr joining below. Fresh break on lower left.



F2071 Inscription fr, marble

I 93 Stated in inventory to be no 17., from Apollo Trench V, 29/11/35. No record of this find found in NB's.
#17, p.309 is I 86, #17, p.664 is an inscribed handle., #17, p.236 is I 54.
"17" appears in pencil on the backs of the 2 frs.

Two joining frs. I F + back only pres. Pth 0.112, Max w. 0.055. Th at left 0.025, at r. 0.017. Lth 0.023

July 1962: NB ref now seen to be p.458 no. 83, q.v.



F2072 Inscription, hard pink limestone

I 161 Recorded 7A/p 54 (GRE). No NB. ref. found. Possibly recorded by Mrs. Hall?

Built into threshold of entrance for Street I & room to west of court of East Bldg.

H. 0.33 + (not poss. to measure accurately)
W. 0.79. Th. ~~0.05~~ 0.67. Lth. 0.02

ΑΠ⌣ΙΙΩΝΙ ΥΛΑΙΗΙ
ΜΕΝΤ ΣΙ ΚΑΙΚΛΕΟΝΙΚ
ΗΝΕΑΥΤΟΝ ΑΓΕΡΑ
ΙΛ

Badly worn.

M. Hood says: "Copied by me in 1948"

3093

F2073 Inscription, hard pink marble

I 162

At Capolla, adjoining F2072 at south.
Recorded 7 Apr 54 No NB ref found.
Possibly recorded by M.L. Hall?

Inscribed face hidden by F2072, but see Film 113, #1: F2072 removed. Squeeze made by Mitford?

W. 0.41 Th 0.67 H 0.26+

Mitford says: "Copied by me in June, 1948"

Back-up Film 113 #1 + 112 #36

3094

F2074 Inscription, stone

I 156

~~Th~~ vol IV, p. 692, 30 Oct. 47 (no #): "on west face of east wall of Street 1 in situ (a second hand block, however)

W. 0.52 H 0.29+ Th. ca 0.63. + H 0.03

ΦΙΛΙΝΟΣ ΜΕΝΤΟΡΟΣ
ΤΗΝ ΕΑΥΤΟΥ ΘΥΓΑΤΕΡΑ
ΤΙΜΩ

IN wall ca 1.00 m. south of F2073.

F2075 Inscription, stone

Recorded 7 Apr 54. No NB ref. found.

I 163

At Apollo. Street 1, on S.W. edge of gate.

W. 0.50 H 0.30 + Th. 0.60 LH 0.03

Upper part + left edge of IF broken away. 6 letters only visible as placed.

TONEAY

Mitford says: "copied by me in 1948"

F2076. Inscription, columnar base, limestone.

Recorded 7 Apr 54. No NB ref. found.

I 164

H. 1.10 D. 0.50 LH. 0.03 (4 lines), 0.02 (bottom line).
Mouldings above + below and around middle between 2d + 3rd lines of inscr. Inscr. badly worn.

ΤΟΛΛΩΝΙΥΛ
Ι Ο ΛΩΝ

ΘΥΓΑΤ
ΟΥ \ ΣΙΛΟΥ
Ο ΛΑΤΗΝΕΙ

3097

F2077. Ancient impression of inscription. LATIN.

× See vol VI p 1100, bottom + 1108

I 165 Film 112, #37 (8 June 1938 "West ends, Stratum I, center"

Said to be still at Apollo, covered w. earth.

No reading available

× See also BHH diary, II p. 116 - plan showing location of inscr.

3098

F2078 Inscription, on limestone orthostate block, Temple B.

NB IV p684 + 690 29 Oct 47

I 159 Max. W. 1.10, Max H. 0.50, P. Th. 0.35 L. H. 0.09.

ΛΘΗΝΑΙΚΟΥ

F2079 Inscription, on Doric epistyle block.

NB IV p707 1 Nov 47

I 160 W. 0.98, Th. 0.43 - 0.48; H. 0.41 L.H. 0.03

Built into a wall of the East Bldg. Inscribed on upper surface 3 ll. of which 2d is illegible (Rome)

ΝΤΙΟΧΟΣ ΝΙΚΑΝ

ΟΛΛΩΝΙΥΛΑΤΗ

F2080 Limestone relief fr.

SE 953

Recorded 7 Apr 54. Stated by Chester Gregerson to have been found on the surface at Apollo some years ago, "East of altar 2" [within the area of the fence]

original lower edge + back surface pres.

PH. 0.32 PW. 0.25 Th. 0.08

Low relief, chariot with part of 2 horses proceeding to right. A winged figure kneels on his right knee (or archaic running posture?) on chariot.

F2081 Green glass base fr.

20 May 49 Cistern 2 1369-2

GL 332

D. 0.063 PH 0.108

Ring base w. rising center bevels. Complete except for small bit, with bit of wall attached.

F2082 Rim fr. of ?beaker, pale green glass

Bath, Room 1, hypocaust debris

GL 314

PH. 0.05 Est D ca. 0.07

Ca 1/2 of circumference preserved. Low, flaring lip grooved bevels. Wall tapers downward and has applied blobs of blue ca 0.03 below rim

F2083 Glass bowl rim fr.

2 June 49 Cistern 3 p 1369-8

Max. dim. 0.05

GL 319

Plain vertical rim 0.01 high. On wall remain parts of 2 heavy vertical ribs spaced 0.01 apart

Pale green glass, thick, with bluish green iridescence.

3101

F2084 Glass, wall fr.

Cistern 3, 1369-2

GL 318 Max dim 0.032

The wall was decorated with contiguous long petals in low relief, above was a horizontal line in relief. Pale green glass, v. v. blue green undercurrent

F2085 Glass bowl rim fr.

21 May 49. Cistern 1369-3

GL 317 P.Ht. 0.045 Est D. ____

Plain except for 2 grooves, 0.015 + 0.04 respectively, below rim. The wall flares expands outward
Pale blue glass

F2086 Glass ?beaker fr., rim + wall

26 May 49, Cistern 3 1369-5

GL 315 PH 0.074

Wall nearly straight, plain rim. 2 horizontal grooves, 0.020 + 0.053 respectively, below rim. Pale green glass

3102

F2087 Glass rim fr.

21 May 49 Cistern 1369-3

GL 313 Max dim. 0.083.

Section of plain, flaring rim + attached wall. Pale green glass

F2088 Glass bead

24 May 49 Cistern 1369-4

GL 312 Max dim 0.025.
Ca 1/3 of circumference preserved.
Vertically pierced.
Blue glass with 2 circular designs outlined in white on exterior

F2089 Glass bottle neck)

24 May 49 Cistern 1369-4(6)

GL 311 PH 0.05

Complete height of neck + plain flaring lip preserved; with bit of shoulder. Pale green glass

F2090 Glass rim fr.

30 Apr 49 Bath, west of room 5.

GL p1255-2(b), p1277-2

316 Max dim 0.04
Section of flattened-tubular rim with ribbon decoration applied to exterior. Green glass

F2091 Glass base fr

17 May 49. Bath, room 3, hypocaust 1285-2a

GL 309 PH 0.023

ca 1/5 of widely ~~flaring~~ spreading foot pres. + attached floor. Thick greenish brown glass

F2092 Glass bowl fr

11 Apr 49 Street I west 0-2 depth 0-30 cm.

GL 333 Max dim 0.068
Section of rim and most of profile of wall preserved. Red glass. Wall decorated with two heavy vertical ribs, spaced 0.013 apart. Pale green glass

F2093 Glass wall fr

2 June 49 Cistern 3 1369-7

GL 308 Max dim 0.05

Fr. of thin yellow glass with white iridescence preserving parts of 5 lines of rubbing in relief.

F2093 Glass wall fr

GL 307 2 June 49 Cistern 3 1369-7

Max dim 0.05

Fr. of dark blue glass w. patches of white iridescence preserving parts of 3 ~~ribs~~ ribs on exterior + horizontal groove on interior

F2094 a-b Non joining sections of glass bowl

9 Apr 49 T-Y west 6-9.
S. of wall at T. 2nd strat. to rock, Early ———.

GL 310 a. Max d. 0.07 b. Max d. 0.075

Frs. of rim + wall of shallow bowl with rim 0.01 high, plain. Ribs 0.02 high, vertical. Complete profile preserved on b.; concentric circles around center of floor

F 2095 a-b 2 non joining sections of glass bowl (plus 6 non joining frs)

Apollo center 1369-8

GL 330

a) Max d (rim) 0.09 b max dim (rim) 0.05

Frs. of hemispherical bowl of brown glass w. white iridescence a horizontal groove 0.01 below rim and 2 more ca 0.03 below

F 2096 a-d 4 non-joining sections of glass bowl (plus 16 non joining frs.)

GL 331

7 June 49 Cistern 3 center 1369-9; 1467-9

Max dim at Rim: a) 0.085; b) 0.105; c) 0.075; d 0.115

Clear, slightly yellowish glass

Sections of a bowl of Nastos shape

Plain footed with 3 horizontal grooves just below rim & interior

For F 2097 see p. 3103

F 2098 Terracotta head

"Apollo Provenience unknown"

F 91

Mold made, probably female. curly hair parted in middle & falling to below ears. Back only crudely finished. Nose broken. Buff clay

P.H. 0.04

F 2099 Frag'y marble statuette of Aphrodite

JL 95

Said to have been brought in by a shepherd and to have been found below the cliff at the East end of Triphiti beach which is called Μουτσούκας τους Τουρκους

P.H 0.25 Preserved fr. neck to lower thighs. left arm & breast missing. White marble

Nude except for bit of drapery which she holds with her right hand raised to level of upper left thigh. Vertical hole in neck for separate attachment of head. Lead (?) pin in right leg for attachment of lower part of legs

F3000 Fragl limestone statue standing male.

Said to have been brought in by shepherd & to have been found below cliff called ΜΟΥΣΟΥΡΑΣ TOUR TRIPICOS

St 956

PH 0.37. Pres. fr. neck to hem of garment.

54-28-22 Figure relatively flat w. arms held straight down against sides. Wears short sleeved shirt w. band 0.02 wide around Round neck. Broad vertical band on sleeves and horizontal as cuff. Over this is a short cloak hanging fr. left shoulder and drawn diagonally down across body to right thigh, a row of triangles in relief along its edge. Below appears a fringe or a pleated garment. Stubs of legs below.

F3001 Marble drapery fr.

"Apollo 31 Oct 47 693-2"

St 957

Max dim. 0.11 white marble

Part of 5 folds, 2 receding from each side of a large central fold

F3002 Limestone horse fr.

"Street 1 West H-8 2-4, STRAT 1A V-2-48 p29. No.8."

St ~~958~~ 959

Tho' apparently from Apollo the page ref. does not fit. Perhaps excavated by the Younger & recorded in their notebooks?

PH. 0.12 PL 0.24.

The body of the horse & the supporting strut are preserved A blanket its ends incised as for fringe over its back. A human hand holds the bridle at the nape of the horse's neck. The hand presumably belonged to a figure standing on the ground beside the horse.

F3003 Male head fr, limestone

Stated by Christos Gregorion to have been found by him in the trench at Agha Anna when trench was filled in after Excavation.

St
960

Pres. H. 0.16

Face only pres. fr just below chin to front part of hair above forehead

Curly hair w. laurel? leaf fillet.
Nose preserved, only shallow bridge
Slight smile.

F3004 Male head fr, limestone

As. F3003

St
961

Pres H 0.175

Face fr just below chin to front part of hair above forehead preserved and right side of face to behind ear. Nose badly damaged, deep gouge in center of forehead + underlying parts of both eyes.

Spiral curls. Laurel leaf fillet

F3005 Marble head of dog (?), fr.

Stated by Christos Gregorion to have been found at Apollo outside the area of the Excavations

St
962

Max dim. 0.13

Pres. fr. eyes to back of ears.

Short ears laid back along back of neck. Groove down center of skull. Pronounced brows. Left eye missing.

F3006 Marble fr of foot on base

As F3005.

St
963

Max dim. 0.10

Left foot, front half, toes pres. resting on base ca 0.035 thick.

F3007 Limestone hand + forearm

Provenance unknown.

St
964

Max dim 0.14

Forearm broken below elbow. Hand holds ~~spherical~~ cylindrical object. Fragment of part of body on inside of forearm.

F3008 White marble tip of nose

Found at Apollo, outside area of excavations

ST 967

Max dim 0.038

Includes most of right nostril + part of left.

F3009 Limestone female head

Picked up near top of St. Anne valley.

ST 968

PH 0.13

Intact to neck except for chipped nose, left cheek + chin

Protuberant almond shaped eyes, circular earrings, raised line representing necklace. Pointed cap or bandeau revealing hair in front

F3010 White marble torso of male statuette

Picked up along ridge called Kouzoes along boundary between Gera Karka + Montanous

ST 969

PH 0.09


Pres. from upper neck to ca. navel. Left arm preserved to just above elbow.

Nude save for garment hung on left shoulder. attached to ~~right~~ left arm is ~~part~~ which appears to be part of a thin club + the head + part of the body of a snake Right arm was separately attached: pin hole preserved. Strongly marked musculature

F3011 Limestone small ?base, possibly inscribed

I 166 Apollo, outside Excavations

H. 0.07 D. bottom 0.052, top 0.043
Central part cylindrical with rounded mouldings at top + bottom.
Around central part are dots may possibly be incised letters ca 0.045 high:



F3012 TC fig fp: centaur

SE Bldg Trench 1, Extension, Layer 2
GRE p24 July 8, 1954

F95

PH 0.09 Hard, gritty buff clay.

Torso preserved + long triangular beard

F3013 Grazing deer, stone

L.0.043 Pale blue stone. Legs missing. A hole on each side of head for separate insertion of horns and one in center for insertion of stone ornament (?)
St 931 Flat incised fw. chevron design.

Area W. of Street I, Area B.
July 13, 1954. GRE p46

F3014 Stone scarab: bull (?) + lion.

St 932 L.0.015 W.0.01 H.0.01 Intact
Mottled brown + white stone

Wadi Complex NJ Votive Deposit
July 14, 1954. GRE p37

F3015 Stone scarab: Heracles + Hydra

St 933 Area W. of Street I, Area B
July 13, 1954. GRE p41

L.0.022 W.0.018 H.0.015. Intact
Black stone.
Heracles stands in center grasping Hydra by its neck. The body of the Hydra encircles the scene.

F3016 Bull's head, grey stone

St 934 Area W. of Street I, Area B.
July 13, 1954. GRE p41
H. 0.018 Intact
Small boukephalon, frontal, flat back. Holes in eyes for insertion
Forehead circumscribed with incised lines
Hole for suspension at top.

F3017 Blue paste jar; form alabastra

Mi 558 Area W of Street I, Area B
July 13, 1954. GRE p41

H. 0.045 W. 0.045.

Egyptian head on one side, protome branch on other. Broad short handles + spreading lip mostly missing.

F3018 Bronze finial

M 1051 Apollo, Area W. J Street 1, Area B
July 13, 1954 G.R.E. p. 41

H. 0.055 D top 0.043 Intact.

Cylindrical foot surmounted by sphere. ~~Pierced~~ Sphere pierced by 4 arrowhead shaped cut outs. Small circular holes in foot for attachment to shaft.

F3019 Bronze bowl fr.

Apollo, W. J Street 1, July 14, 1954
M 1052 a-c G.R.E. p. 46

a) Rim + wall fr. max d. 0.10
b) " " " 0.09
c) " fr. " 0.08

Apparently fr. hemispherical bowl. Surface very corrupted but probably w. ruled decoration. Traces of dependent concentric semicircles on b) c) in pierced by 3 small holes

F3020 Bronze fr. eye-shaped object

Apollo, Area W. J Street 1
M 1053 July 14, 1954 G.R.E. p. 46
(with F3020)

L. 0.052 H. 0.025 Probably intact.

Possibly eye for insertion into statue. Flat surface, bevelled edges. Bronze pin in center. Hinge (?) on lower edge

F3021 Inscribed parapet block
of Street One

I 190 Apollo, laid ca W-E at right angles to the direction of Street One, its east edge ca 2.70 fr the inner face (west) of the west wall of the room N. 1 The Doric Portico T = Tr. 9, H-Θ, N. 16-18

L. 1.65 W. 0.53, Th. 0.21. Letters h. ca 0.20 + Gray limestone (?), hard.

ΕΥ_ΤΟΧΙC

ΑΝΕΘΗΚΕΝ

The inscription appears on the top face of the stone as it is set on the pavement. The traces of the letters which remain consist of closely spaced circular cuttings or drill holes each ca 0.02 + 0.03 in diameter

so closely spaced as to suggest inlaid dicks (lead?) rather than holes for the attachments of metal letters.

First noted July, 1962 (apparently)
No NB ref. located.

F3022 Inscription: marble plaque

I 191 H 0.19 P.W. 0.235 Th. 0.33m
Letter h. 0.01-0.015m. "Local white marble" 1F, top, bottom & left edges preserved; back roughly picked. 8 ll.

"Picked up by visitors in the early summer of 1918 from the western side of the Sanctuary of Apollo"

ΑΥΤΟΚΡΑΤΟΡΑ ΚΑΙΣΑ[
ΑΥΡΗΛΙΟΝΑΝΤΩΝΕΙΝ[
ΕΥΣΕΒΗΕΥΤΥΧΗΣΕΒΑΣ[
ΥΙΟΝΤΟΥΚΥΡΙΟΥΑΥΤΟΚΡΑΤΟΡΟ[
ΚΑΙΣΑΡΟΣΛΟΥΚΙΟΥΣΕΠΤΙΜ[
ΣΕΥΗΡΟΥΕΥΣΕΒΟΥΣΕΥΤΥ[
ΠΕΡΤΙΝΑΚΟΣΣΕΒΑΣΤΟ[
ΚΟΥΡΙΕΩΝ

7.70
32.80
40.5

14.70
13
27.30

12
13
25