

St 305 - St 615

St 305

SADDLED HORSE

Near "Altar Two," surface

PH 0.058

Head, lower legs, most of tail  
& of columnar support missing.

Fringed saddle-cloth, breast-  
band with pendant bell or  
tassel. No trace of rider.  
Conceivably was made separately  
as in Terracotta horsemen.

Limestone.

Votive Deposit

Another netherless horse, Myrus CCC  
1913; may have had groom with  
it (CMC 3301-3).



St 306

HORSE AND RIDER

Near "Hitar Two," surface

PH 0.173

Back of base, central support  
preserved, horse lacking head,  
tail & most of legs; rider lacks  
head.

Rider wears short pleated tunic  
with pleated trousers to above  
knees, over this cape & fastened  
draping as St 272. Stalped  
square saddle-cloth. Horse  
has breast-band with tassels.  
Rectangular flat basis  
oval prop in center of horse's  
body.

Limestone.

**FLOOR**

Vogel Deposit



St 307

HORSE AND RIDER

Near "Altar Two", surface

PH 0.143

Right rear part of horse with  
rider's body, his left leg,  
left arm, head, & right arm  
mostly missing.

Plain square saddle-cloth.  
Rider wears cape fastened  
shawl-like on breast with  
ring through which loose ends  
are drawn. Under this, plain  
tunic.

Soft white limestone.

FLOOR

Votive Deposit

ST 308

RIDER ? TEMPLE BOY ?

Near "Altar Two" surface

PH 0.095

Head, arms, right thigh & leg,  
left leg from above knee missing

Nude figure, heavy and swelling  
parts, rudely modeled. Genitals  
(male) shown. Marks of attach-  
ment on left breast as if  
something were held there.  
Left upper leg at right  
angle to body as if figure  
were seated.

limestone.

*Apuleia missa.*

St 309

STANDING DRAPED VOTARY

Apollo, surface find

PN 0.225

Head, left hand, part of right  
hand, and lower body missing.

Wears short-sleeved chiton,  
over which mantle. Left arm  
at side, right on breast slung  
in fold of mantle. Flat back,  
cut with knife.

Limestone.

Apollo miss.



St 310

FRAGMENT OF STANDING FIGURE  
Apollo, surface find

PH 0.163

Preserves middle body from waist  
to just above knees, left arm  
and part of right missing.

In "Egyptian" stance, left leg  
advanced, arms at sides, hands  
clenched. Represented as if  
nude, but probably male figure  
wearing close-fitting "Cypriot  
belt" or loin-cloth. Roughly  
finished behind.

limestone.

*apollo musc.*

St 311

FRAGMENT OF CHARIOTEER (?)

Apollo, surface find

PH 0.054

Head and body below waist  
missing.

Right arm bent and hand  
rests on breast; left at side.  
Flat back sliced with knife;  
no indications of drapery. Might  
be driver or passenger of chariot.  
limestone.

*Apollo mess.*

St 312

FRAGMENT OF CHARIOT GROUP?

Apollo, near "Altar Two," Surface

Max. dim. 0.082

Bit of finished surface with "wing"  
from which rises rounded shaft  
with parallel ridges.

May be part of chariot-wall with  
base of occupant.

Limestone.

Apollo msc.

St 313

## HORSE AND RIDER

Apollo, near "altar Two," surface

PH 0.103

Body of horse minus legs, head,  
central support; body of rider  
minus head & part of right  
arm. Surface battered.

Plain saddle-cloth. Rider  
grasped horse's neck with  
both hands.

Limestone. Traces red on horse's  
body, saddle-cloth, foot &  
leg of rider.

**FLOOR**

Vol. 10, Dep. 10



St 314

SCULPTURED FRAGMENT

APOLLO, surface find

Max. dim. 0.157

Three edges broken.

Fragment finished front & back, projecting molding along one edge. on one flat surface, rounded relief, possibly part of animal in profile.

limestone.

*apollo misc.*

St 315

# FRAGMENTARY CHARIOT GROUP

Apollo, near 'Altar Two' surface

PH 0.277

Chariot-car with much of left wing missing, preserves lower bodies of both occupants. \*

Car with central partition on high base, hole for axle. Incised lines mark off base of wings, another line in flat curve like festoon on each wing and on front & from this vertical line cutting each surface in half.

Occupants wore long chitons with vertical parallel drapery folds faintly indicated. Passenger rests both hands on chariot-rim, mark of driver's ~~right~~ left hand on rim.

\* upper body at one time joined to driver stemould, as it was a dubious join (now St 316).

## FLOOR

Votive Deposit

St 316

FRAGMENT OF DRAPED FIGURE

Apollo, near 'Altas Two', surface

PH 0.148

upper body, head & left arm  
missing.

Draped in short-sleeved chiton  
with himation over left shoulder  
and under right. On himation  
oblique parallel grooves for  
drapery-folds. Right arm at  
side, fingers curled around  
small object, left arm (missing)  
was also at side.  
Back somewhat modeled.

Limestone.

\* was once, wrongly, joined to St 315.

Apollo mic.



S+ 317

FRAGMENT OF DRAPED FIGURE  
Apollo, near "Altar Two" surface

PH

Missing from somewhat above  
waist, upper surface much  
damaged.

apparently wears long chiton  
with broad shallow folds,  
long fold of himation (?) falls  
down left side. Sock + shoes  
with tongs. Feet apart,  
weight mostly on left leg.  
High roughly rectangular  
base. Back smoothed off  
by knife.

Limestone.

Apollo miss.



St 318

BASIS ?

Near "Altar Two," surface

(P) H 0.074

Ten-sided polygon with square  
setting on upper surface for  
metal (?) inset. At top, narrow  
rounded molding, below this  
one wider, and below this again  
three narrow fillets.

Limestone.

Apollo miss.

St 319

SCULPTURED FRAGMENT

Apollo, Near "Altar Two," surface

Max. dim. 0.151

Broken away at one end & above.

Long narrow basis with three divisions marked at one end. On this unintelligible parts of sculptured scene.

Possibly triple mattress with one large reclining figure and one small seated figure.

Limestone.

apollo misc.

S+ 320

FRAGMENT OF LIMESTONE

Apollo, near "Altar Two," Surface

Max. dim. 0.066

Fragment probably broken all round, although one surface is rounded & smoother than others, suggesting may be bit of a sculptured figure.

On one broken surface clear impression of fluted shell.

*Apollo mass.*

ST 321

STANDING DRAPED FIGURE

Found on shelf in E. apotheca  
with sculpture from Apollo,  
no tag.  
PH 0.265

Head & feet missing, arms,  
and vase offering chipped.

Dressed in short-sleeved  
chiton with stippled surface,  
over this himation with  
broad folds draped over left  
shoulder. Right hand on  
breast, left holds animal(?)  
against side. Back roughly  
modeled.

Limestone. Traces red paint  
on drapery.

Apollo mus.



ST 351

FRAG. OF LIMESTONE STATUETTE

STADIUM, TRENCH 7 W. EXT.

IN EARTH FALLEN IN WHERE  
EUTH. BLOCKS WERE REMOVED,  
JUST ON LINE OF EUTH. & 2.20 M  
W OF LAST PRESERVED BLOCK.

24.X1.47

NOTEBOOK p. 160

SOFT LIMESTONE; THE ROUGH  
SURFACE WAS GIVEN A THIN  
COATING OF FINE STUCCO, PRESUMABLY  
TO TAKE PAINT (NOW GONE)


MAX DIM OBJECT: 0.088  
" " HAND: 0.091

R. HAND OF A FIGURE, C. 1/3 LIFE SIZE. BROKEN OFF  
AT WRIST. FINGERNAILS ROUGHLY SHOWN. THE HAND  
WAS IN SOME WAY RAISED, PROBABLY FORWARD, &  
CRUTCHES TIGHTLY AN OBJECT, CYLINDRICAL IN  
SHAPE, & BROKEN AT EITHER END.


FLOOR

TO LITTLE REMAINS TO DETERMINE EXACTLY WHAT IT  
IS, BUT MOST LIKELY A "TRAMP BOY" WITH A GOOSE HEAD  
BY THE NECK.

OTHER POSSIBILITIES: HERAKLES HOLDING PAN OF LION'S  
SKIN; VOTARY WITH BIRD OR SACK; OPAON WITH LACONCELOS.



St 352



AV-69

LIMESTONE AEDICULUM (?)

(WITH 4 PERSONS)

Sheet on wall 2-H, 6-8 stat.  
1 A; notebook (J.Y.) III p. 27  
No. 4

PH 0.105

Fragment broken off above,  
finished below.

On side A, couch with female  
figure reclining to R., bearded  
male figure seated before, hands  
on knees, draped in chiton with  
parallel vertical folds; filler.

On side B, two figures seated  
side by side, the one to L. large-  
browed, wearing double necklace  
with pendants, long tight chiton  
sympanon held with both hands  
on lap; the one to R. (also female?)  
in long chiton holding long  
object like double staff with  
loop at top in R. on lap.

Apollonios. (Over)

Below on C, two parallel grooves,  
for attachment?

Above, finished at D and two sides  
curving in over head as if to make  
a hollow niche.

On one side a very regular small circle  
as if an "o".



ST 353  
t

LIMESTONE QUADRIGA

fragments found scattered about  
"Alvar Lugo" area.

L. 0.192; PH 0.125

Assembled from four fragments,  
gaps & much of base restored  
in plaster; most of horses'  
heads & occupants' heads  
missing.

High car with hole for separate  
axle, two compartments  
occupants bent both hands  
on rim. Yoke-poles extend  
from front corners of chariot  
& indicated double-hands  
attached to them shown  
around horses' necks.  
Horses head heads down.  
Have protruding chests  
like deer.

Faint traces red on yokes.

**FLOOR**

Volume Deposit

AV-62

St 401



Film V9 3

1:18

figure of priest  
limestone, fine-grained

back rough-hewn, flat  
under surface of base slopes toward  
back  
remains of red on central portion of  
headdress  
mended from 2 pieces

H 0.463

W 0.136

*Apoll.*  
Archaic Altar  
just south of  
stone slab  
⊕ east 2



Film V9 3

1:18

ST 401

Film VG 3. 22-224  
AV-76

<sup>St Kibit</sup>  
STANDING MALE VOTARY

Archae Altar just south of  
stone slab O East 2

H. 0.463; W. 0.136

Complex, chipped.

Beadless.

Right arm in mantle knots  
on chest, left arm at side,  
hand clenched. Wear short-  
sleeved under-garment to  
ankles, mantle draped  
with V-neck over this.  
Soft pointed cap with  
up-turned ear-flaps.  
Hair to shoulders behind.  
Ear-rings. Bare feet.

Back flat, cut with knife.  
Not well smoothed. Base  
rough & rounded below so  
that figure could never  
have stood.

Traces red on cap. Fine-  
grained limestone. (over)

Archae Precinct



cf Myres, CCC, No. 1002, pp.  
141 f., fig. on p. 143 - "700-650  
B.C."

SCE Kition Nos. 166, 551 - <sup>style IB</sup> ex  
stylistic grounds "Early or middle  
of Cyprio-Archae II" i.e.  
600-550 B.C. Not so close  
as parallel above.

Myres, Leptouko, BSA XL1, pl. 12,  
5. (1-3) ring close, still later  
"7th cent."




St 402 ✓

head of priest  
limestone

back sliced off

PH 0.079



1.4

26/3/37  
Apollo  
Trench 9  
A-E  
North 30-32  
Surface soil  
McF. St.23

*not taken for  
note book  
total exposed*

St 402

HEAD OF MALE VOTARY

Apollo, Trench 9 Δ-E,  
No. 30-32, Surface Soil,  
MCF. St. 23

Film Vol. 2, 41

AV-119

PH 01079  
Head only, features battered.  
Head of companion - piece  
to St 401, q.v.  
Limestone.

Archaic Precinct

St 403 ✓



1:8

beardless head, low headdress  
limestone

traces of red paint on brow at and  
just below edge of turban  
head much battered; left side mostly  
gone  
has been set on a plaster base

L front to back 0.117  
greatest W (hair at back) 0.098

20/4/37

Apollo, Street 91

K.78.Λ

East 9-12

on top of 2nd  
stratum

McF. St.56

St 403

AV-30

21.27-27.4  
(pore)

## BEARD LESS HEAD

Apollo, Street 1, East 9-12,  
K-78-A, on 2nd stratum;  
mcf. St. 56

PH 0.131; L. front to  
back 0.117

Head and neck only;  
bottomed nose + left side  
gone. Digs in chin and  
forehead.

Smooth Egyptian beardless,  
hair in wig-like mass  
behind

Limestone. Traces red on  
forehead.

**FLOOR**

Archaeic Precinct



See Myers, C.C.C., p. 198, No. 1265, fig.  
(1650-550 B.C.)  
= SCE Queso Style III, Pl. CLXXXIX,  
p. 587 f. No chronology. Period  
of earliest limestone sculpture of Cyprus  
is hybrid Egyptian style, which  
is followed by period of Cyprian  
Greek influence. (ca. 550 B.C.?)

St 404 ✓



1:4

beardless head, low headdress  
limestone

rough-finished behind  
face mostly gone

PH 0.10 W 0.067  
PT 0.066

Joined to upper torso (from Apollo,  
Street 1 East, found on surface 1946  
at approx. K, East 4).

As joined, PH 0.22

6/5/37 ✓  
Apollo  
Trench 9  
Z-H  
North 26-28  
on top of 2nd  
stratum  
McF. St.70

St 404

AV-66

MALE FIGURE: FRAGMENTARY

Head: Apollon, Trench 9, Z-H, No. 36-38  
on top of 2nd stratum, NEF. St 70

Body: Apollon, Street 1 East, found  
on surface 1946 at approx. K,  
East 4).

PH 0.201

Head (most of face gone) + body  
to waist, arms and upper shoulders  
missing.

Low flat band with two incised  
lines at edge holds wig-like hair,  
falling in mass to shoulders  
behind ears. Upper body either  
nude or in very close-fitting  
tunic. Trace of Cypriot belt or  
loin-cloth at waist. Arms were  
not at sides. Body oval in section,  
back plain.

Limestone. Remaining red paint  
on front of torso.

FLOOR

Archaeic Precinct

Perhaps a blue-flower? Cf.  
Niles (CCG p. 198, 1264, +  
201, 1269-70); Niles "Mixed  
Quadrangle Style" - 650-550 B.C.



St 405 ✓



Film Vg 3

1:5

beardless head, low headdress  
limestone

back sliced off flat  
has been set on plaster base

W 0.063

H chin to top 0.087



Film Vg 2

1:5

"Film 15, no. 29"  
(McF)

13/4/37 ✓

Apollo

Street 1

A-7-M

5.20?

East 15-20

on top of 2nd  
stratum

McF. St.45

*bring up, not in  
note book*

St 405

AV-30

Film VG 2, 34  
(VC 3, 40-poor)

## BEARLESS HEAD

Apollo, Street 1, N.?-M, E.  
5.20 (?) on top of 2nd  
pratum, mcf. St 45 (find-  
ing place not in notebook)

PH 0.111

Head & neck only, much  
battered.

Low flat plain headdress,  
lock of hair falling to each  
shoulder. Bulging pap. ls. long  
nose, narrow oval face.  
Flat back.

Limestone.

Archaeic Primit

For headless of SCE Kition 429,  
Style IB, called "veil" (600-540  
B.C.).

Here features & modelling of  
them exactly as St 401 in which  
it must be contemporary.

St 406 ✓

Film vq 2



beardless head, low headdress  
limestone

flat behind, rough finished  
has been set on plaster base

PH 0.09 gtest W 0.066  
W 0.055

1:5

Film vq 1



1:4

82  
9/4/37  
Apollo  
Street 1  
A-195-M  
East 4-60  
in earth of 1st  
stratum  
McF. F.347



St 406  
AV-30

Film VG 2, 36(?)  
(VG 1, 27 A, poor)

### BEARLESS HEAD

Apollo, Station 1, A-125-M,  
E. 4-60 in earth of 1st  
stratum, M.F.F. 347

PH 0,09

Head and part of neck only.


Apparently bareheaded, plain  
mass of hair curving over  
forehead. Pulling straight  
down behind ears in Egyptian  
w.g. fashion. Sharp in-cutting  
around eyeballs. Flat back.

Limestone; faint traces red  
on lips, & hair(?).

Archaeic Portrait

q. SCE, Kition No. 566, Pl. VI, ca.  
540 B.C. for modelling of features.  
+ no. 534, Pl. X, Style II-540-500.

St 407 ✓



1:7

bearded head, headress high in back  
limestone

much battered surface  
top of right shoulder preserved

FH 0.132

17/4/37 ✓  
Apollo  
Trench 9  
K-  
North 28-30  
on top of 2nd  
stratum

McF. St.62

St 407

AV-30

Film V6 2. 24

## BEARDED HEAD

Apollo, Trench 9, K-A, No. 25-30  
on top of 2nd stratum; MCF.  
St. 62

PH 0.132

Head, right side of neck, & bit of  
right shoulder, surface much  
battered.

Pointed helmet, profile swelling  
out below & narrowed where it  
fits head (cf. Myus. CCQ, 1266 -  
beardless). wig-like hair in  
swelling mass on shouless be-  
hind. Bit of shoulder preserved  
suggests shouless very narrow  
in proportion to head. Smooth,  
wedge-shaped beard; large bulging  
eyes; sloping forehead.  
Limestone.

**FLOOR**

Archaic Period



cf. Blumhagen, Ludo, nos 690, Pl.  
69, almost replica, presumably  
before 550 B.C. Cypriot import to  
Rhodes.

St 408

BEARDED HEAD

Apollo, Street 1, West 2  
O-37 (1st shatum), E-65-2,  
Tmcf. F 54

PH 0.055

Head only, of rider or character  
(?) like St 409.

As St 409, but filler replaced  
by wuark of leaves.

Limestone. Many traces of  
color" (mcf. p. 73).

Perhaps 408 + 409 represent  
a pair of characters?

cf. Myres, CCC, # 1017

Apollo misc.

Film Vg 1, 30A

St 408 ✓



bearded head  
limestone

twin of head of St 409

has been set up on plaster base

PH 0.055 W 0.037

1:4

"many traces of colour"  
(McF. p. 73)

12/12/35 ✓

Apollo

Street 1

E 65 Z

West 2

O-37 (not shown)

McF. F.54

St 409✓



Film Vg 1

1:5

top of statuette of bearded draped fig.  
limestone

head, twin of St 408

arms (missing) were bent forward at  
elbows

note the carefully finished back, less  
weathered than the front  
at base of neck in front, rust stains

PH 0.127 gtest T 0.043



Film Vg 1

1:5

12/12/35

Apollo

Street 1

E 75 Z

West 2#65 (n. 6)

1st stratum

0-35

McF. F.55





SE 409

TOP OF STATUETTE

Apollo, Street 1 west 2.65,  
E-75-2, 1st stratum 0-35

MCF. F. 55

Wt 0.127

Rider or charioteer? Broken off  
at waist, forearms missing.

(?)  
Short beard, long hair put up &  
held by fillet. Draped in long-  
sleeved high-necked chiton, over  
which is short mantle dipping  
in U-shaped fold over breast  
& two ends hanging nearly to  
waist behind. Back carefully  
carved.

Limestone. Traces red on mantle  
& neck behind, & on face.

See St. 408.

Film VG 1, 2 A. 4 A

Apollo misc. (over)

Cf. SCE Kilian, Nos. 104, 432,  
456, Pls. XVI & XVIII, Style III A =  
End of Cyprio-Archae II = ca.  
475 B.C.; also Merunaki No.  
866, Style II A, late Cyprio-  
Archae II; also Vouni, Style II,  
must be after 490-80, before  
450-40 (paleo building periods)

Cf. Myres CCC # 1017

St 410 ✓

draped male figure, fragmentary  
limestone


back roughly modelled  
top, bottom, right hand, missing

PH 0.138 gtest T 0.05



Film V61

1:5



Film V61

1:5

9/4/37  
Apollo  
Street 1  
M-30-N  
East 3#25  
on top of 2nd  
stratum  
McF. F.348

"Film 15 m. 20"



St 410

DRAPE MALE VOTARY

Apollo, Street 1, M-30-N, E. 3.25  
on top of 2nd stratum; M.F. E  
348

P4 v. 138

Head, Right hand, & <sup>lower</sup> body from  
above knees missing.


Standing figure in kimation  
draped over left shoulder and  
under right arm; drapery folds  
indicated in hanging end.  
Both arms at sides, slightly  
bent, right may hold only  
drapery but appears to have  
held some small object now  
missing. Figure round in section.  
Waist-line indicated behind.  
L. leg was slightly advanced.  
Limestone.

Film V6 1, 1A  
(V6 1, 31A poor)

Apollo Musc.

Nearest drapery is of Vouni style  
II A (490/80 - 450/40 B.C.), cf.  
also Kilian 144 (style II A - after  
475). Ca. 460 B.C.?

St 411 ✓



Film V91

1:12

draped male figure, fragmentary  
limestone, fine-grained

finished all round  
top, bottom, right forearm, and left  
hand missing

PH 0.346 W 0.168  
T 0.091

5/12/35 ✓  
Apollo  
Street of  
Pronaos  
A-B  
South  
1st stratum  
McF. F.34

"Street 1, south of  
and against  
standing column"  
McF. p. 51

St 412



Film Vg 1

114

frag. male figure with lion(?) skin  
limestone

top and bottom broken away  
the animal skin is represented as  
worn over a long garment and  
girdled round; girdle shown also in bac.


PH 0.099 W 0.048  
T 0.034

Herakles. cf. Myres, Cat. Cesn. Coll'n,  
No. 1092, fig. p. 161; "ca. 600 B.C."

*no reference  
found*



St 413 ✓



Film 491

1:4

frag. semi-nude male fig. with garland(?)  
limestone

top, bottom, hands, gone  
chlamys over raised left shoulder  
garland(?) carried under raised l. elbow

PH 0.095 gtest T 0.043

3/12/35  
Apollo  
south of the  
temple

McF. F.29

St 414



Film VQ 2

118

fragment of chariot group  
limestone

head and forequarters of left outside  
horse, with part of chariot shaft and  
of barrel of next horse  
scale, modelling, harness, match those  
of Young's more completely preserved  
St 214; head better preserved in this  
example

greatest dimension of  
fragment 0.16

Part of St 250, g.v.

Apollo  
26/3/37  
Trench 9  
Δ-E  
South 0-2  
In earth of 1st  
stratum

(no ref found)

St 415 ✓



Film Vg 1

1:8

fragment of chariot group  
limestone

most of the actual chariot, double type  
like Young's St 214, with traces of two  
riders: 1) charioteer(?) to right in  
long skirt, arms forward over rim of  
car; 2) passenger with feet indicated  
separately, left foot advanced  
cf Young's St 215

mush worn surface; side pieces of char.  
chipped away

W 0.15 PH 0.14  
large axle perfora-  
tions, diam. ca. 0.016

6/5/37 ✓  
Apollo  
Trench 9  
M-N  
North 26-28  
On top of 2nd  
stratum

St.  
McF. 74



ST 415

FRAGMENT OF CHARIOT GROUP

Apollo, Tr. 9, M-N, No. 26-28  
on top of 2nd stadium. M.F.  
ST. 74

PH 0.14

Chariot-car with passenger,  
head lacking; chariot entered,  
wings missing, wheels gone. Of  
driver, remains of striding feet,  
left foot advanced. Chariot pair-  
yoke.

Passenger rests back hands  
on chariot-rim. Hole for axle  
+ attachment of chariot-wheel.  
In nestone.


Film VG 1, 11A  
(copy)

FLOOR

Votive Deposit



St 416



Film Vg 2

114

wheel from chariot group  
limestone

plain double convex with no moulding  
round axle perforation

gtest. diameter 0.074  
T 0.02

23/12/35 ✓  
Apollo  
Street 1  
E 84 Z  
West O-124  
1st stratum  
O-25

*no ref. found*

St 417✓



Film V93

1:12

torso of horse  
limestone

elongated body nearly square in section;  
peculiarly small neck; both left legs  
were advanced

rough but finished surface back and  
sides, no sign of attachment; hind part  
chipped, removing any sign of tail  
mended from two lengthwise pieces

PL 0.305 PH 0.112

T 0.093

*Now joined to head  
of deer from "Asian  
Tomb"*

11/5/37 ✓

Apollo

Street 1

N.110. W

East 6.05

On top of 2nd  
stratum

ST  
McF. 77

St 417

## VOTIVE DEER

Body: Apollo, Street 1, N. 110. E.  
E. 6.05 on top of red shatum;  
MCF. St. 77

Head: 'Altar Two'; near-surface

AV-137

PH 0.234

Legs, right hindquarter, horns,  
ears, missing.


Long body, long neck, head  
curving back. Slight modelling  
of head & muzzle. Left foreleg  
was advanced. Traces of rings at  
base of broken horns (2).  
Limestone (Head has weathered to  
different color from body).

## FLOOR

Votive deposit



St 418✓



Film v91


1:8

forequarters of harnessed horse(?)  
limestone

right foreleg was advanced

W 0.098

same scale and material as St 419  
and probably part of same object:  
note on 418 start of ivy decoration  
along backbone of 419, and on belly in  
each fragment part of a central strut,  
also that in both cases left side of  
animal is better finished.



Film v91

1:12

7/4/37 ✓

Apollo

Trench 9

£.60.

South 14-90

on top of 2nd  
stratum

McF. St.59



St 419



Film V91

1:8

hinder half of horse(?)  
limestone

left hindleg advanced  
the thick tail(?) continuous with a  
decorative treatment of the back bone:  
a grooved "spine" is flanked by ivy  
leaves along the back, then by oblique  
lines to give effect of tail, and ends  
at a series of dentellations at the edge  
of the break

FH 0.14 PL 0.21  
T 0.10

probably part of  
same object as  
St 418, which see

7/4/37

Apollo

E-50-8

South 15-10  
on top of 2nd  
stratum

McF St.59a

St 420✓

forepart of lion  
limestone



right side gone

greatest dimension of fragment 0.234

same scale and material as St 421,  
may be part of same object

Film Vg 2

1:10

6/5/37  
Apollo  
Trench 9  
Z-H  
North 28-30  
in earth of 1st  
stratum

*"surface soil"*  
McF. p. 364  
McF. St. 73

ST 420

FOREPART OF LION

Apollo, Trench 9, Z-H, No. 28-30, in earth of 1st stratum; met. p. 364, St 73

Max dim. 0.234

Legs, hindquarters & right side of body & head gone; battered.

Mouth open, teeth were indicated. Small ears, within slightly raised mane. Limestone.

May go with St 421, but probably broken from a relief.

Apollo num.

dim 192, 157

St 421 ✓



Film 49 2

1:10

hindquarters of crouching lion on base  
limestone

tail curls round left haunch

right surface broken away

greatest dimension of frag. 0.144  
W of base near back ca. 0.08

see on St 420; may be part of same object

11/5/37 ✓

Apollo

Street 1

N.95. W

East 5.20

on top of 2nd  
stratum

McF. St.76



St 421

HIND QUARTERS OF SEATED LION

Apollo, Street 1 N. 45 E. 520 on  
top of 2nd stratum, Mt St 76.

PH 0.116

Battered.

Seated on long oval base  
large paws, tail curled around  
right haunch. Trace of end  
of tail on top of back.

May go with St 420.

Limestone.

Apollo misc.

St 422 ✓



Film Vg 1

1112

gryphon, fragmentary  
limestone, coarse-grained

head and forequarters  
mended from two pieces which have lain  
apart and discolored differently  
wing tips broken away

PH 0.24 W 0.11

|       |                              |       |                          |
|-------|------------------------------|-------|--------------------------|
| head: | 18/3/37 ✓                    | body: | <sup>27?</sup> 23/3/37 ✓ |
|       | Apollo                       |       | Apollo                   |
|       | Trench 9                     |       | Trench 9                 |
|       | H-θ                          |       | I-K                      |
|       | North 10-12                  |       | North 16-18              |
|       | 1st stratum,<br>surface soil |       | on top of<br>2nd strat.  |
|       | McF. St.24                   |       | McF. St.43               |

43

St 422

GRIFFIN

Head: Apollo, Tr. 9, H-O No. 10-12  
1st stadium, surface soil; MCF. St. 24  
Body: Apollo, Tr. 9, I-K No. 16-18  
on top of 2nd stadium; MCF. St. 43

Ends of forelegs, hanches tips  
of wings missing. Gallinid.

Feathers of wings oval & overlapped  
regularly toward back. Incised  
ridge down back ending in crest  
on top of head. Incised locks on  
shoulders and neck representing  
locks fur or Eagle feathers.

Limestone. Traces red on back of  
head.

Film Vol. 1, 46 A

Apollo misc.

Q. Sali, 302, Pl. CLXVI, Style II B.  
for type.



St 423 ✓

hawk or eagle  
limestone

slice off top of head?  
otherwise intact

H 0.047 L 0.038 W 0.018



Film V9 2

1:3




Film V9 2

1:3

11/12/35 ✓  
Street 1  
E-Z  
West 2-4  
1st stratum  
O-20

McF. F.49

St 424



Film V9 2

1:8

hawk or eagle  
limestone

bird with spread wings carved in relief  
as hanging by its throat from just  
below hawk's beak

hawk's beak broken off, also feet and  
tip of tail, with base?

PH 0.136 W 0.076



Film V9 2



St 425✓



Film V9 2

1:8

dove  
limestone


feet and tail rest on base  
beak and part of base worn away

H 0.14 L 0.146 W 0.063

(no date given) ✓  
Apollo  
Street 1  
Z-H  
West 2-4  
on or near  
crude wall

McF. St.78

St 426 ✓



Film Y42

1:8

fragmentary dove(?) on base  
limestone

head missing

PH 0.094 L of base 0.118

✓  
17/3/37  
Apollo  
Trench 9  
θ-I  
North 10-12  
1st stratum  
McF. St.10



St 427 ✓



Film Vg 3

1:10

frog(?) for fountain(?)  
limestone, coarse-grained

a hole ca. 0.03 in diam. in the base  
passes up through the body of the ani-  
mal ending in an opening ca. 0.026 in  
diam. in its mouth

H 0.137 W 0.114 L 0.21



Film Vg 3

22/4/36 ✓

Apollo

South bldg.

Room 2

Z-60-H


opposite East

peristyle 50

McF. St.7

McF. p. 139: "lying  
on 3rd stadium"  
q. also p. 107, no. 3

St 428 ✓



Film V9 I

1:5

miniature altar  
limestone

table top has raised edge  
foot rough-finished underneath  
both top and foot grooved round edge

half rim of top chipped away

H 0.083 diam. of foot 0.068  
of top 0.088

5/4/37 ✓  
Apollo  
Trench 9

E - S  
South 14-16  
on top of 2nd  
stratum

McF. St.80


St 429 ✓

fragment of uncertain object  
limestone


finished and decorated on all surfaces  
save the one broken edge  
apparently represents part of piece  
of furniture or architectural member  
but uncertain which way is up

W 0.05 T 0.02  
PL 0.07

Film V9 2



Film V9 2




Film V9 2

*(opposite edge  
much damaged;  
seems like edge here shown)*

7/12/35  
Apollo  
Street 1  
Z-H  
East 2-4  
O-10

McF. St.81

St 430 ✓



Film V9 2

1:4

lamp?  
limestone

bowl with trough hollowed into a  
rather flat river stone

L 0.087 W 0.079  
T 0.025

The shape suggests that this object might  
possibly be a miniature oil press or bowl  
for pressing some sort of  
liquid - (S.A.)

13/4/37 ✓

Apollo

Trench 9

B-1

North 26-28

on top of 2nd  
stratum

McF. St.66



St 430

MINIATURE OIL-PRESS?

Apollo, Trench 9, B-F, No. 26-28  
on top of 2nd Stratum.

Intact.

Flat round - stone with top  
hollowed out in bowl with  
trough leading out of rim.


Limestone.

For similar native oil-presses,  
all periods, cf. Macalister, Excav.  
of Gezer (Palestine) pp. 411 ff. No  
exact parallel.

Apollo misc.

Film VG 2, 42

St 431 ✓



Film Vg 2

1:4

fragment of uncertain object  
alabaster

from a flattish piece with preserved two  
rounded edges at right angles to each  
other, and start of return of 3rd. In  
incomplete edge, three uneven holes  
worked in a row ending at the break

T 0.032 PW 0.068

\* left, in place.

✓  
/3/37

Apollo

Cave 1

McF. F. 462 and

St. 49

St 432 ✓



Film V9 3

1:12

middle of nude(?) male figure  
white marble

belly to thighs  
left knee was drawn somewhat forward  
but right leg shows marked curve at hip:  
figure leaned against a support to its x  
right?  
on right thigh traces possibly of paw  
of lion or panther skin

greatest dimension of  
frag. 0.24

6/5/37 ✓  
Apollo  
Trench 9  
Z-14-H  
North 24-70  
on top of 2nd  
stratum

McF. St.71



Film V9 3

1:12

St 433 ✓



File V9 3

1:12

fragmentary torso of nude male figure  
white marble

right side, from waist to thigh;  
gluteal muscle chipped away

greatest dimension of fragment 0.277

27/3/37 ✓

Apollo

Trench 9

K-^

North 24-26

1st stratum

McF. St.69



St 434 ✓



File V93

1:13

frag. male standing figure with chlamys  
white marble

finished all round  
right arm was raised?

mended from 3 pieces  
total PH 0.337

a) middle:

Apollo

Street 1

N-H

East 6-8

surface soil

b) top:

Apollo

Street 1

N-H

East 2-4

c) r. thigh

Apollo

Trench 9

Δ-E

North 30<sup>32</sup>

lying on

2nd strat.

McF. St.58

*all right for n. d. i;  
no labels*

St 435✓



Film V9 2

1:5

fragment of human foot on base  
white marble

front of foot, well modelled, with  
indication of toenails  
incision above big and second toe is  
possible indication of sandal strap

big toe, little toe, much damaged

greatest dimension of fragment 0.10

*T of base*

Apollo ✓

23/3/37

Trench 9

A-E


North 20-22

From among  
stones on top  
of second strat.

St.

McF. 82

St 435 ✓



Film V91

P.3

frag. finger  
white marble


tip and second joint of bent finger

L of fragment 0.069  
(life size or a little larger)

42  
2/4/37 ✓  
Apollo  
Trench 9  
I-K  
South 4-6  
on 2nd stratum

McF. St.52

St 437 ✓



Film v9 1

113

frag. finger  
white marble

broken off nearly at knuckle  
little finger of left hand?

L of fragment 0.073  
(life size or a little larger)

*Handwritten: Trench 9*  
✓  
/4/37  
Apollo  
Trench 9  
K-A  
North 26-28  
on top of 2nd  
stratum

McF. St.50

*2.6 (McF. p. 315) given  
date "March 37"*



St 438 ✓



Film V91

113

frag. finger  
white marble

tip and second joint

L of fragment 0.082  
(a little over life size)

23/3/37 ✓  
Apollo  
Trench 9  
I-K  
North 28-30  
in earth of 1st  
stratum

McF. St.51

St 439 ✓



Film V9 2 1:3

frag. finger  
white marble

second joint

L of fragment 0.057  
(large for life size)

7/4/37 ✓  
Apollo  
Trench 9  
K-^  
North 26-28  
from second str.

McF. St.48

St 440 ✓



fragment of hand  
white marble

one finger and part of another to  
right of it (perhaps index and middle  
finger of right hand)

mended from 2 pieces  
gtest dimension of whole fragment  
0.097 (large for life size)

23/3/37 ✓  
Apollo  
Trench 9  
E-Z  
North 4-6  
in earth of 1st  
stratum

McF. St.11

St 441 ✓



Film V9 1

1:3

fragment of hand  
white marble

parts of two fingers at the upper  
joint (bent)

greatest dimension of fragment 0.071  
(over life size)

24/3/37

Apollo

Trench 9

I-K


North 26-28

in earth of 1st  
stratum

McF. St.11;



St 442 ✓



Film V63

1:12

fragment of large head (human)  
white marble

part of neck with hair falling beside it  
from head made to set into separate statuette  
well-marked "collar of Venus" e

flesh, fine smooth matt finish; hair,  
impressionistic; rounded surface to be  
inset, rough-finished with chisel; in  
center bottom, tenon hole of depth 0.055

part to be inset was ca.  
0.05 deep; gtest dimen-  
sion of whole fragment  
ca. 0.25; head was over  
life size

30/3/37

Apollo

Trench 9

Λ-M

North 30-32


In earth of

1st stratum

St.

McF. 67

St 443 ✓



Film Vg 3

1:12

fragment of head (human)  
white marble

part of neck, from head made to set  
into separate statue


flesh, fine smooth matt surface;  
surface to be inset, rough-finished with  
chisel; in center bottom, tenon hole  
of H 0.042 and inner (gtest) W  $\phi$ .052

PH 0.154  
(including depth  
of part to be inset  
which is 0.084)  
about life size

11/5/37 ✓  
Apollo  
Street 1  
stratum 1  
McF. 75  
A

McF. p. 368: "found  
among tiles around  
- 1936 "

St 444 ✓



Film V9 2

1:3

fragment of nose

white marble

greatest dimension 0.054  
(about life size)

21/11/35 ✓  
Apollo  
Trench 4  
east of  
Temple B  
surface soil

McF. F.12

McF. p. 19: "just  
east of mound of  
Trench 4"

St 445 ✓



Film Vg 2

1:5

fragment of human face  
white marble

right eye with part of brow and nose

greatest dimension of fragment 0.137  
(at scale large for life size)

23/11/35 ✓

Apollo

East of temple

1st stratum

McF. F.14



St 446 ✓



Film Vg 2 ca. 1:40



Film Vg 3 (#24) 1:10  
(#25, 26, with  
different  
exposure)


draped female figure, separate head  
white marble, the body weathered red

in the convex under-surface of the  
head piece, a dowel hole stained with  
rust; in the concave receiving  
surface at the top of the body, iron  
dowel still in place; horizontal ~~had~~  
holes in body immediately below  
shoulder projections, and another to  
take the projecting right toe;  
back of head, concave rough-finished  
surface; back of body, upper part  
toward left rough-finished, otherwise  
folds of both chiton and himation  
shown in the back

H of body piece 1.00  
H of head " 0.225  
H combined 1.18  
W of head 0.14  
gtest W of body 0.336

19/3/36  
Apollo *South bldg.*  
Room 2  
on substructure  
of floor  
(head found  
under body)  
McF.St.1  
*from n.b.  
no label*

St 447 ✓



Film v9 2

1:8

cone of Aphrodite  
white marble

hole drilled in lower part of side,  
not quite on axis, 0.033 deep

for the cone, cf coins of Cyprus in  
Roman times, cult object represented in  
Paphian temple, where however the  
carved ornament on top of this piece  
is not indicated (from G.McF.)

H 0.205  
base diam. 0.09  
top " 0.034

30/11/35  
Apollo  
Tr.6  
Γ-E  
surface

McF. F.18

SEB109

(see index)

St 448



Film V9 4

1:18

(only larger frag.)

2 fragments of large basin  
veined marble, white with red and blue

simple thickened rim  
no base fragments preserved


estimated diam. sl. less than 0.80  
PH 0.194

T of wall 0.025, thicker toward rim  
gtest diam. of larger frag. 0.53  
" " " smaller " 0.31

nb.



St 449 ✓



Film V9 2

large flat plate, fragmentary  
white marble

under-surface within rim finished with  
claw chisel, and flat except for narrow  
low base ring (which falls just within  
inner moulding on top of plate)

*\* not very clear on photograph*  
total diam. 0.668

diam. of flat under surface 0.565

" " base ring 0.445

H ca. 0.024

T toward middle 0.01

3 non-joining pieces,  
of which gtest dimen.  
0.195, 0.165, 0.102

22/9/36

Apollo

South bldg.

Room 2

0.70 S of main  
threshold, 1.55


W of E perist.  
on 3rd stratum

McF. St.8

*(checked  
against 5 and  
2nd pt)*



St 450



Film V9 3

1:12

temple boy, top gone  
limestone, fine-grained

back flat, roughly finished  
left forearm was raised; dove (? head  
gone) in right hand

PH 0.212 W 0.18  
gtest T 0.088

St. Anne's

St 451



Fig. Vg 3

1:12


temple boy, head missing  
limestone, coarse-grained

back roughly finished  
right forearm (gone) was raised  
wears ornamental bandolier over shirt

PH 0.17 W 0.154  
greatest dimension (front to back) of  
base 0.182

25/11/35 ✓  
St. Anne  
H-0  
North 4-6  
Trench 1  
1st stratum  
O-30

St 452



Film Vg 3

1:5

crowned beardless head  
limestone

finished all round  
badly cracked  
has been set on plaster base

PH 0.102 W 0.083  
T (minus tip of nose) 0.093

7/12/35

St. Anne

W-P North 6-8

St 453



Film V9 3

1:8

laureate beardless head  
limestone

back sliced away, tip of nose gone,  
chip from brow  
has been set on plaster base

PH 0.14 W 0.12

10/11/35  
St. Anne  
A-M  
North 4-6  
Trench 1  
1st stratum  
0-120



St 454



Film V4 3 (#33)

1:8


laureate beardless head  
limestone

chunk broken away out of back and side  
chin gone

PH 0.142 W 0.119  
PT 0.116

St. Anne

St 455



Film V9 3 (#31)

1:10


front of laureate beardless head  
limestone

top and back broken away; crack  
under right eye  
has been set up on plaster base

PH 0.182 W 0.12  
PT 0.092

St. Anne  
(found by Christ  
outside excav.)

St 456 ✓



Film Vg 3

1:10

front of laureate beardless head  
limestone

back broken away; brow, nose, chin,  
chipped

PH 0.192 W 0.135

PT 0.097

25/11/35 ✓

St. Anne

Trench 1

K-Λ

1st stratum

McF. F.16

*(no further plan  
in n. 6.)*

St 457

fragment of laureate head  
limestone, fine-grained



top, front, of head, to eyes

greatest dimension of fragment (W) 0.132


Film Vq 3

1:7

St. Anne



St 458



Film V93

1:5

laureate beardless head  
limestone, fine-grained

finished all round  
chips missing from nose, etc.  
has been set on plaster base

PH 0.12 W 0.076  
gtest T 0.075

7/12/35  
St. Anne  
E-0  
North 4-6

St 459



Film V93

1:5

laureate beardless head  
limestone, fine-grained

roughly finished behind; chips from  
nose, etc.  
has been set on plaster base

PH 0.105 W 0.067  
gtest T 0.08

27/11/35 ✓

St. Anne

Λ-M


North 4-6

Trench 1

1st stratum

0-50

St 460



Film V9 3

1:4

laureate beardless head  
limestone, coarse-grained

red in nostrils, lips  
has been set up on plaster base

PH 0.08 W 0.054  
gtest T 0.053

St. Anne

St 461



Film V93

1:7

head in cap  
limestone, fine-grained

mended from two pieces;  
cap broken away below at both sides  
and above brow and at peak, which  
projected to proper right;  
back flat, rough-finished;  
has been set on plaster base

PH 0.137 PW 0.093  
gtest T 0.075

4/12/35  
St. Anne  
N-H  
North 8-10  
Trench 1  
1st stratum  
O-145



St 462



Film V93

1:4

head in peaked cap and laurel crown  
limestone, coarse-grained

back flat, roughly finished  
has been set on plaster base

PH 0.081 W 0.045  
T 0.041

St. Anne

St 463



Film v9 3

1:4

child's right hand holding spool toy  
limestone, coarse-grained

finished all round, save at break

greatest dimension 0.099

St. Anne

St 464



Film Vg 2

1:5

laureate beardless head  
limestone

back rough-finished (rather concave)  
but shows ends of wreath  
much worn; chip from top of head


PH 0.095 W 0.07 gtest T 0.068

1939

Kourion

stray find brou-  
ght in by shep-  
herd

St 465



Film V9 2

1:7

torse of male figure with chlamys  
white marble

neck to thigh; right forearm missing;  
much worn  
back finished

PH 0.138 W (gtest) 0.079

1939  
Kourion  
stray find  
brought in by  
shepherd



St 470



Film V.G. 12

1:12



Film V.G. 12

1:12

(showing treatment  
of border at corner)

corner frag. of rectangular table top  
white marble, polished

raised border with moulded edge and  
corner ornament; under surface smooth-  
ly picked  
2 joining fragments

PL 0.298


H of border 0.045

W of border 0.05

T of interior 0.012

Kourion  
Basilica  
marble pile

St 471



Film V.G.12

1:12

border frag. of rectangular table top  
white marble, polished


raised border with moulded edge; under  
surface smoothly picked

PL 0.147

H of border 0.052

W of border 0.063

T of interior 0.016




Film V.G.12

1:12

Kourion  
Basilica  
marble pile

St 472

border frag. of rectangular table top  
white marble, polished



Film V.G. 12, # 8

1:12

raised border with moulded edge;  
under surface slightly roughened and  
with shallow gauge at left end of  
frag. running almost perpendicular  
to finished edge

PL 0.123

H of border 0.052

W of border 0.062

T of interior 0.012-0.015 (l. to r.)

Kourion  
Basilica  
marble pile

St 473



Film V.G. 12, #9

1:12

border frag. of rectangular table  
white marble, polished top

raised border with moulded edge;  
under surface smoothly dressed

PL 0.055

H of border 0.048


W of border 0.072

Kourion  
Basilica  
marble pile



St 474

border frag. of rectangular table top  
white marble, weathered



Film V.G. 12, # 10

1:12

raised border with moulded edge;  
under surface slightly roughened

PL 0.203

H of border 0.04

W of border 0.053

T of interior 0.013

Kourion  
Basilica  
marble pile

St 475



Film V.G.12, #11

1:12

border frag. of rectangular table  
white marble, weathered top

raised border with moulded edge;  
under surface fairly smoothly picked  
with slightly raised band (ca. 0.025  
wide) along finished edge

PL 0.245

H of border 0.058

W of border 0.06

T of interior 0.011

Kourion  
Basilica  
marble pile

St 476



Film V.G. 12, #12

1:12

border frag. of rectangular table  
white marble, weathered top

raised border with moulded edge;  
under surface smoothly dressed

PL 0.15


H of border 0.053

W of border 0.061

T of interior 0.013

Kourion  
Basilica  
marble pile

St 477



Film V.G. 12, #13

1:12

border frag. of rectangular table  
top  
white marble, polished but weathered

raised border with moulded edge;  
under surface fairly smoothly picked  
with slightly raised band chiseled  
toward edge (0.025-0.017 wide -  
from right to left) as on St 475  
2 joining fragments

PL 0.237

H of border 0.06


W of border 0.066

T of interior 0.015- (impossible to  
determine lower limit accurately)

Kourion  
Basilica  
marble pile



St 478



Film V.G. 12, #14

1:12

border frag. of rectangular table top  
white marble with grayish tinge,  
polished

raised border with moulded edge;  
under surface slightly roughened with  
band (0.015 - 0.00 wide from left to  
right) slightly raised and chiseled  
away toward finished edge as on  
St 475 and St 477  
2 joining fragments

PL 0.267

H of border 0.039


W of border 0.069

T of interior 0.013

Kourion  
Basilica  
marble pile

St 479

border fragment of rectangular table  
white marble, polished top



raised border with moulded edge;  
under surface fairly smoothly dressed

PL 0.09

H of border 0.035


W of border 0.075

Film V.G. 12, #15

1:12

Kourion  
Basilica  
marble pile

St 480



Film V.G. 12, # 16 1:18

corner frag. of rectangular table  
top  
white marble, blue gray veins,

raised border with edges smoothly  
dressed, not moulded but bevelled  
toward upper surface; under surface  
smoothly dressed with gauge (as from  
uneven sawing) running diagonally  
across corner  
3 joining fragments

PL 0.488

FW 0.21

H of border 0.03

W of border 0.065-0.07

T of interior 0.015

Kourion  
Basilica  
marble pile

St 481



Film V.G. 12, # 34

fragmentary rectangular table(?) top  
white marble, grayish-blue veins

raised border; edges not moulded,  
long edge smoothly bevelled toward  
upper face, other edge bevelled with  
distinct traces of claw chisel; under  
surface fairly smoothly dressed with  
slight rilling as from uneven sawing  
2 joining and 3 non-joining fragments  
which, on account of color of marble,  
thickness, and treatment of under  
surface, probably belong

frag. a-PL 0.75

FW 0.445

H of border 0.04-0.057

W of border 0.07

T of interior 0.02-0.033

frag. b GD 0.19

T 0.023

frag. c GD 0.28

T 0.21

(over)



frag. d GD 0.165  
T 0.019

Kourion  
Basilica  
marble pile

St 482



Film V.G. 12, # 35

fragmentary rectangular table(?) top  
white marble

raised border; longer edge somewhat  
carefully bevelled toward upper face,  
other edge roughly dressed with  
marks of claw chisel; under surface  
shows distinct rilling (as from un-  
even sawing) running obliquely  
across corner

3 joining and 2 non-joining frags.  
which on account of color and thick-  
ness of marble as well as treatment  
of under surface probably belong

frag. a PL 0.552

PW 0.415

H of border 0.05-0.055

W of border 0.08

T of interior 0.015-0.02

frag. b GD 0.305

T 0.015-0.02

(over)

frag. c GD 0.205  
T 0.019


corner of frag.a  
from

Kourion Tr. 23  
(Basilica)


σ-τ; North 4-6  
60-90

other frags. from  
Basilica marble  
pile

St 483



Film V.G. 12, # 17 1:18



Film V.G. 12, # 36

St 483

St 485

St 484

St 486

border frag. of rectangular table(?)  
white marble top

raised border; edge fairly smoothly  
bevelled toward upper face; under  
surface slightly roughened

2 joining fragments  
for height and width of border, as  
well as color and finish of marble  
cf. St 482

PL 0.477

H of border 0.052

W of border 0.08

T of interior 0.023

Kourion Tr. 23  
(Basilica)

K-λ; South O-2  
20-40



St 484



V.G. 12, # 18 1:18

St 484  
St 485

border frag. of rectangular table(?)  
white marble top

raised border; edge fairly smoothly  
bevelled toward upper face; under  
surface fairly smooth with traces of  
scoring and rilling almost perpendi-  
cular to finished edge  
for height and width of border cf.  
St 482

PL 0.30  
H of border 0.052  
W of border 0.08

Kourion  
Basilica  
marble pile

St 485

border frag. of rectangular table(?)  
white marble top

cf. photograph St 484

raised border with edge fairly smoothly bevelled toward upper face; under surface slightly roughened for height and width of border cf. St 482

PL 0.52

H of border 0.46-0.05

W of border 0.08

T of interior 0.02

Kourion  
Basilica  
marble pile

St 486



Film V.G. 12, # 19

1: 18

interior frags. of rectangular table(?)  
white marble top

no finished edges preserved; under  
surface of all frags. slightly roughen-  
ed

3 large (1 of which, frag.b, is com-  
posed of 3 joining frags) and 5 small  
non-joining frags.

for color and thickness of marble, as  
well as treatment of under surface,  
cf. St 482

(note that frag.a preserves slightly  
raised border which surrounds interior  
recess of table(?) top)

frag. a GD 0.27  
T 0.02-0.022

frag. b GD 0.15  
T 0.018

frag. c GD 0.175  
T 0.017-0.019


(over)

frag. d GD 0.15  
T 0.02  
frag. e GD 0.11  
T 0.02  
frag. f GD 0.085  
T 0.017  
frag. g GD 0.06  
T 0.016  
frag. h GD 0.055  
T 0.022

Kourion  
Basilica  
marble pile



St 487



Film V.G. 12, # 20

1:18

interior frags. of rectangular table  
white marble, grayish tint (?) top

no finished edges preserved; under  
surface of all frags. slightly rough-  
ened

3 large non-joining frags., of which  
frag. a is composed of 5, frag. b of  
2, and frag. c of 4 joining frags.

(note that frags. a and b both preserv  
slightly raised border which surrounds  
interior recess of table(?) top  
frags. a and b certainly, and probably  
frag. c belong to same table, which on  
account of color and thickness of  
marble seems to have been St 480

frag. a GD 0.23  
T 0.012-0.015

frag. b GD 0.195  
T 0.014

frag. c GD 0.21  
T 0.012-0.015

(over)

Kourion  
Basilica  
marble pile

St 488



Film V.G. 12, # 22

1:12

St 489

St 488

St 490

border frag. of circular<sup>(?)</sup> table top  
white marble, highly polished

raised border curled over into a  
kind of reverse "hawk's beak"; out-  
side edge smoothly finished with  
shallow groove at base of moulding;  
under surface slightly roughened  
2 joining fragments

L of frag. 0.205

H of border 0.06

T of interior 0.016-0.018

Kourion  
Basilica  
marble pile

St 489

border frag. of circular table top  
white marble, weathered

cf. photograph St. 488

raised border with edge smoothly finished in slightly convex curvature;  
under surface smoothly dressed

L of frag. 0.134

H of border 0.038

T of interior 0.012

estimated diameter of table ca. 1.05

Kourion  
Basilica  
marble pile



St 490

border frag. of circular table top  
white marble, weathered

cf. photograph St 488

raised border with edge smoothly finished in convex curvature; under surface fairly smoothly dressed

L of frag. 0.105

H of border 0.031

T of interior 0.011

estimated diameter of table 0.58

Kourion  
Basilica  
marble pile

St 491



Film V.G. 12, # 24

1:12

interior frags. of table top  
white marble, highly polished

no finished edge preserved; under  
surface slightly roughened  
for highly polished surface cf.  
St 471 and St 488  
4 joining and 1 non-joining frags.

frag. a GD 0.305


T 0.013

frag. b GD 0.15

T 0.014

Kourion  
Basilica  
marble pile

St 492



Film V.G. 12, 32 1:18



Film V.G. 12, #33 1:18

border frag. of rectangular table  
white marble, gray veins top

edge smoothly finished in band (0.02 high) and then undercut in moulding of double curvature connecting it with under surface; under surface from top of moulding slightly roughened (for peculiarities of under surface and for O - part of reused inscription? - cf. second photograph) cf. St 493 for similar treatment of border

PL 0.475

H of border (incl. moulding) 0.037

W of border 0.062 and 0.122

T of interior 0.015


possibly from Baptistry?

Kourion Tr. 23  
(Basilica)

μ-v; South 14-16  
O-80



St 493



Film V. G. 12, # 38

corner frag. of rectangular table(?)  
gray marble, blue veins top

edge above in photograph smoothly bevelled with slightly convex curvature toward under surface; left edge smoothly dressed for contact surface in band 0.025 high below which it is roughly bevelled toward under surface with deep diagonal scoring from claw chisel; under surface roughly dressed with claw chisel; under surface of left border is ca. 0.01 higher and is separated from bottom of table proper by a smooth bevel, running parallel to left edge until ca. 0.09 from upper edge where it curves outwards toward corner for distinctive borders cf. St 492 and St 494  
5 joining fragments

(over)



PL 0.475

FW 0.405


H of border 0.087

W of border 0.07 and 0.16

T of interior 0.035

Kourion  
Basilica  
marble pile

St 494



Film V.G. 12, #39

border frag. of rectangular table(?)  
gray marble, blue veins top

edge of border smoothly dressed for  
contact surface 0.025 high, below  
which it is roughly bevelled (in  
2 stages: ) with deep diagonal  
scoring from claw chisel toward  
under surface, which is likewise  
heavily scored  
2 joining and 2 non-joining frags.

frag. a PL 0.325  
FW 0.265  
H of border 0.106  
W of border 0.17  
T of interior 0.037-0.045

frag. b GD 0.13  
T 0.042

frag. c GD 0.192  
T 0.037  
Kourion  
Basilica  
marble pile

St 495



Film V.G.12, # 37

fragmentary circular table(?) top  
gray marble, blue veins

edge of border smoothly dressed for  
contact surface 0.025 high, below  
which it is roughly bevelled with deep  
diagonal scoring from claw chisel to-  
ward under surface; under surface of  
border, which is smoothly dressed in  
band (0.025 wide) along edge but with-  
in heavily scored by claw chisel, is  
ca. 0.01 higher and is separated from  
bottom of table proper (also heavily  
scored) by a smooth bevel concentric  
with circumference  
5 joining fragments

GD 0.665

H of border 0.091

W of border 0.165

T of interior 0.035-0.04

estimated diameter ca. 0.84

(over)

largest frag. from  
Kourion Tr. 23  
(Basilica)  
C-14; North 2-4  
O-140

other frags. from  
Basilica marble  
pile



St 612

Sand stone with circular decoration  
and possible flower in relief.

Curium, Palace

Room X second layer near <sup>bath.</sup>

3 March '49, SF. 5

Fales, NB III, p. 16.

St 614



white marble.

with four pointed knobs, in panel 8 cm  
long. knobs contiguous. about 1.25 cm high.


Cunmín, Palace

East of Room W fourth layer.

10 March '48, SF. 3

Fales. NB. III p. 43.

ST 615



Piece of marble moulding. Possibly  
fr. of drapery.

Cunium, Palace.

Cellar under flagstones.

10 March '49, SF. 6

Fales, NB III, p. 43.